Fisheries and Oceans Canada

Pêches et Océans Canada

Corrected to 12/2021

# ARC 401

## Hudson Strait, Hudson Bay and Adjoining Waters

# Sailing Directions



Canada

## Pictograph legend

**Anchorage**

**Current**

**Radio calling-in point**

**Wharf**

**Caution**

**Lifesaving station**

**Marina**

**Light**

**Pilotage**

### Report discrepancies between real-world observations and descriptions in the publication

Users of this publication are requested to forward information regarding newly discovered dangers, changes in aids to navigation, the existence of new shoals or channels, or other information that would be useful for the correction of nautical charts and publications affecting Canadian waters to: chsinfo@dfo-mpo.gc.ca.


**IMPORTANT NOTICE**

The Canadian Hydrographic Service no longer produces hard copies of its publications.

Updates are published in Notices to Mariners at notmar.gc.ca
and on the Canadian Hydrographic Service website at charts.gc.ca

**REPRODUCTION FOR PERSONAL USE**

This digital publication - as published in charts.gc.ca - may be printed or reproduced in any format, without charge or further permission, provided that it is for non-commercial purposes, i.e. not for sale or any profit whatsoever.

To be used for navigation, the reproduction must be an unaltered, true copy of the publication found in charts.gc.ca, and kept up-to-date at all times.

**REPRODUCTION FOR COMMERCIAL PURPOSES**

This publication shall not be printed or otherwise reproduced in whole or in part for commercial purposes (i.e. in the purpose of sale or any profit whatsoever, as opposed to personal use), without prior written permission from the Canadian Hydrographic Service.

For full terms and conditions, visit
charts.gc.ca or email chsinfo@dfo-mpo.gc.ca.



Published under the authority of the
Canadian Hydrographic Service
Fisheries and Oceans Canada
200 Kent Street, Ottawa, Ontario, Canada, K1A 0E6



© Her Majesty the Queen in Right of Canada, 2022



Catalogue No. Fs72-3/22-2022E-PDF
ISBN 978-0-660-41375-4
Ottawa

# Record of Changes

As the CHS acquires new information, relevant changes are applied to Sailing Directions volumes in order to maintain safety of navigation. It is the responsibility of the mariner to maintain their digital Sailing Directions file by ensuring that the latest version is always downloaded. Visit charts.gc.ca to download the most recent version of this volume, with all current changes already incorporated.

The table below lists the changes that have been applied to this volume of Sailing Directions. This record of changes will be maintained for the current calendar year only

| Chapter / Paragraph | Description of Change |
|---|---|
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |
| | |

# TABLE OF CONTENTS


Preface ____ VIII
Explanatory notes ____ IX
Abbreviations ____ XI

CHAPTER 1 **Hudson Strait — South Shore — Ungava Bay**

**General** ____ 1-1
**Ungava Bay — East Shore** ____ 1-2
Killiniq (Killinek) Island to Cap (Cape) William-Smith ____ 1-2
Cap William-Smith to Rivière George (River) ____ 1-3
Rivière George and Approaches ____ 1-3
**Ungava Bay — South Shore** ____ 1-4
Rivière George to Rivière Koksoak (River) ____ 1-4
Approaches to Rivière Koksoak (River) ____ 1-5
Rivière Koksoak ____ 1-5
**Ungava Bay — SW Shore** ____ 1-6
Rivière Koksoak to Leaf Bay (Baie aux Feuilles) ____ 1-6
Leaf Bay and Lac aux Feuilles ____ 1-7
Leaf Bay to Hopes Advance Bay ____ 1-8
Approaches to Hopes Advance Bay ____ 1-9
Hopes Advance Bay to Payne Bay ____ 1-9
Approaches to Payne Bay and Rivière Arnaud (Payne River) ____ 1-10
Rivière Arnaud (Payne River) ____ 1-10
**NW part of Ungava Bay** ____ 1-11
Akpatok Island ____ 1-11
Five Islands to Cap (Cape) Hopes Advance ____ 1-12

CHAPTER 2 **Hudson Strait — South Shore — Cap Hopes Advance to Pointe Taliruq (Nuvuc)**

**General** ____ 2-1
**Diana Bay** ____ 2-1
East side of Diana Bay ____ 2-2
Central Islands in Diana Bay ____ 2-2
West side of Diana Bay ____ 2-3
SW side of Diana Bay ____ 2-3
South part of Diana Bay ____ 2-3
**Diana Bay to Wakeham Bay** ____ 2-3
Wakeham Bay and Approaches ____ 2-4
**Wakeham Bay to Douglas Harbour** ____ 2-5
Fisher Bay ____ 2-5
Fisher Bay to Douglas Harbour ____ 2-6
Approaches to Douglas Harbour ____ 2-6
Off-lying islands ____ 2-6
Douglas Harbour ____ 2-7
**Douglas Harbour to Deception Bay** ____ 2-7
Foul Bay ____ 2-7
Deception Bay ____ 2-8
**Deception Bay to Cap Wolstenholme** ____ 2-9
Deception Bay to Sugluk Inlet ____ 2-9
Sugluk Inlet ____ 2-9
Sugluk Inlet to Erik Cove ____ 2-11
Erik Cove to Cap Wolstenholme ____ 2-11

**Cap Wolstenholme to Pointe Taliruq (Nuvuc)** 2-11
Digges Islands 2-11
Passe Digges (Sound) 2-12
Mainland coast of Passe Digges 2-12

CHAPTER 3 **Hudson Strait — North Shore**
**General** 3-1
**Resolution Island** 3-1
East, south and SW coasts 3-1
Resolution Harbour 3-2
**Cape Warwick to Baffin Island** 3-4
**Baffin Island — East Bluff to Lake Harbour** 3-4
Kimmirut (hamlet of Lake Harbour) and approaches 3-7
**Lake Harbour to Fair Ness** 3-10
SE shore of Big Island 3-11
SW shore of Big Island 3-11
Big Island to Fair Ness 3-11
**Fair Ness to Chorkbak Inlet** 3-12
**Chorkbak Inlet to Cape Dorset** 3-12
Cape Dorset and approaches 3-13
**Cape Dorset to Lloyd Point** 3-14

CHAPTER 4 **Hudson Bay — East Side**
**General** 4-1
**Pointe Taliruq to Cape Smith** 4-2
Ice Harbour to Pointe Bernier 4-2
Offshore islands 4-2
Pointe Bernier to Cape Smith 4-3
**Cape Smith to Akulivik** 4-3
**Cape Smith to Cape Dufferin** 4-4
Pointe Akulivik to Povungnituk Bay 4-4
Approaches to Puvirnituq (Povungnituk) 4-4
Offshore islands 4-6
Povungnituk Bay to Cape Dufferin 4-7
**Cape Dufferin to Nastapoka Islands** 4-7
Cape Dufferin to Inukjuak 4-7
Approaches to Inukjuak 4-7
Inukjuak to Rivière Nastapoka 4-8
Offshore Islands — Marcopeet, Sleeper and King George Islands 4-9
Offshore islands — Belcher Islands 4-9
Belcher Islands — North part 4-10
Belcher Islands — South part 4-11
Nastapoka Islands 4-12
**Rivière Nastapoka to Le Goulet** 4-13
Approaches to Umiujaq 4-13
Umiujaq to Le Goulet 4-13
**Le Goulet to Pointe Louis-XIV** 4-14
Le Goulet to Grande rivière de la Baleine 4-14
Approaches to Kuujjuarapik (Poste-de-la-Baleine) 4-14
Grande rivière de la Baleine to Long Island 4-15
Long Island and Long Island Sound 4-16

CHAPTER 5 **James Bay**
**General** 5-1
**James Bay — East shore** 5-1
Pointe Louis-XIV to Fort George (Fort-George) and Chisasibi 5-2
Approaches to Fort George (Fort-George) and Chisasibi 5-2
Fort George and Chisasibi to Wemindji 5-3
Offshore islands 5-4
Approaches to Wemindji 5-4
Wemindji to Eastmain 5-4
Offshore islands 5-5
Approaches to Eastmain 5-5
Eastmain to Waskaganish (Fort-Rupert) 5-5
Rupert Bay 5-6
Approaches to Waskaganish (Fort-Rupert) 5-6
Waskaganish to Hannah Bay 5-7
**James Bay — West shore** 5-7
Cape Henrietta Maria to Albany River 5-7
Offshore islands 5-8
Approaches to Attawapiskat 5-8
Approaches to Kashechewan and Fort Albany 5-9
Albany River to Moosonee 5-9
Approaches to Moose River 5-10

CHAPTER 6 **Southampton Island (South Side) and Chesterfield Inlet**
**Southampton Island (South Side) — General** 6-1
Seahorse Point to Coral Harbour 6-2
Evans Strait 6-2
Fisher Strait 6-2
Coral Harbour and approaches 6-3
Coral Harbour to Cape Kendall 6-4
**Hudson Bay — NW shore — Cape Fullerton to Chesterfield Inlet** 6-4
Approaches to Chesterfield Inlet 6-5
**Chesterfield Inlet — General** 6-6
Chesterfield Inlet entrance to Ellis Island 6-6
Ellis Island to Centre Island 6-9
Centre Island to Farther Hope Point 6-9
Farther Hope Point to Terror Point 6-10
Terror Point to Baleen Island 6-11
Baleen Island to Chesterfield Narrows 6-11
Chesterfield Narrows 6-12
**Baker Lake** 6-12
Chesterfield Narrows to James Point 6-12
James Point to Baker Lake hamlet 6-13
Baker Lake Harbour 6-14

CHAPTER 7 **Hudson Bay — West Side**
**General** 7-1
**Chesterfield Inlet to Rankin Inlet** 7-1
Rankin Inlet and approaches 7-2
**Rankin Inlet to Eskimo Point** 7-4
Rankin Inlet to Whale Cove 7-4
Whale Cove and approaches 7-4
Walrus Island to Eskimo Point 7-5
Eskimo Point and approaches 7-6

**Eskimo Point to Churchill** 7-7
Eskimo Point to Egg Island 7-7
Egg Island to Churchill 7-7
Approaches to Churchill Harbour 7-7
Churchill Harbour 7-8
Port of Churchill 7-10
**Churchill to James Bay** 7-10
Cape Churchill to Cape Tatnam 7-11
Cape Tatnam to Fort Severn 7-11
Fort Severn to Winisk River 7-12
Winisk River to Cape Henrietta Maria 7-12

CHAPTER 8 **Foxe Channel — Roes Welcome Sound**
**General** 8-1
**Foxe Channel** 8-1
Offshore dangers 8-2
West side of Foxe Channel — Southampton Island 8-2
East side of Foxe Channel 8-3
**Frozen Strait** 8-3
SW side of Frozen Strait and approaches 8-4
Duke of York Bay 8-4
Comer Strait 8-4
West side of Frozen Strait 8-4
East side of Frozen Strait 8-5
Hurd Channel 8-5
**SE coast of Melville Peninsula** 8-5
Gore Bay and Moyle Bay 8-5
Lyon and Hoppner Inlets 8-6
Winter Island to Cape Wilson 8-6
**Roes Welcome Sound** 8-7
East side of Roes Welcome Sound 8-7
SW side of Roes Welcome Sound 8-8
Wager Bay 8-8
NW side of Roes Welcome Sound 8-9
Repulse Bay 8-9
Talun Bay 8-10

CHAPTER 9 **Foxe Basin — Fury and Hecla Strait**
**Foxe Basin — General** 9-1
**West side of Foxe Basin** 9-2
Cape Wilson to Hall Beach 9-2
Hall Beach 9-2
Hall Beach to Hooper Inlet 9-3
Hooper Inlet 9-4
Igloolik 9-4
**South and east sides of Foxe Basin** 9-5
Foxe Peninsula — North Coast 9-5
East side of Foxe Basin — Bowman Bay to Point Peters 9-5
Prince Charles and Air Force Islands 9-6
**North shores of Foxe Basin** 9-6
Jens Munk Island to Cape Thalbitzer 9-6
Cape Thalbitzer to Reid Point 9-7

**Islands in north part of Foxe Basin** 9-8
Spicer and Manning Islands 9-8
Rowley Island 9-8
East shore of Rowley Island 9-8
West shore of Rowley Island 9-8
Labrador Channel and Koch Island 9-9
Bray Island 9-9
SW approaches to Longstaff Bluff 9-10
SE and east approaches to Longstaff Bluff 9-10
Longstaff Bluff 9-11
**Fury and Hecla Strait — General** 9-11
Fury and Hecla Strait — SE entrance — Islands 9-12
SE approaches to Labrador Narrows 9-13
NE approaches to Labrador Narrows 9-13
Gifford Fiord 9-13
Labrador Narrows to Gulf of Boothia 9-13
South shore — Cape Lilly to Cape Englefield 9-14

APPENDICES **Sail Plan** A-1

Index I-1

# PREFACE

The First Edition of *Sailing Directions, ARC 401 — Hudson Strait, Hudson Bay and Adjoining Waters*, 2009, has been fully updated from Canadian Government and other information sources. In general, all hydrographic terms used in this booklet are in accordance with the meanings given in the *Hydrographic Dictionary (Special Publication No. 32)*, published by the International Hydrographic Bureau.

This edition introduces the new presention and layout of the Geographical areas.

*Sailing Directions, ARC 400 — General Information, Northern Canada* contains general navigational information and a brief description of the main port facilities and anchorages as well as geographic, oceanographic and atmospheric characteristics of this region.

Detailed descriptions of geographical areas are given in the *ARC 401*, *Arctic Canada Vol. II (ARC 402)*, *Arctic Canada Vol. 3 (ARC 403) and Great Slave Lake and Mackenzie River (ARC 404)*. Their limits are printed on the back cover. **The appropriate descriptive booklet(s) of** *Sailing Directions* **should be consulted in conjunction with *ARC 400 — General Information, Northern Canada*, which provides additional information**. Limits of the chapters in this booklet are shown on the inside of the front cover.

Tide, water level and current information has been revised by the Canadian Hydrographic Service.

Photographs are supplied by the Canadian Hydrographic Service and the Canadian Coast Guard, Fisheries and Oceans Canada.

Users' comments concerning the format, content or any other matter relating to *Sailing Directions* would be appreciated and should be forwarded to the Director General, Canadian Hydrographic Service, Fisheries and Oceans Canada, Ottawa, Ontario, Canada, K1A 0E6.

Canadian *Sailing Directions* amplify charted details and provide important information of interest to navigation which may not be found on charts or in other marine publications. *Sailing Directions* are intended to be read in conjunction with charts quoted in the text.

## Remarks

**Buoys** are generally described in detail only where they have special navigational significance, or where the scale of the chart is too small to clearly show all the details.

**Chart references**, in italics in the text, normally refer to the largest scale Canadian chart but occasionally a smaller scale chart may be quoted where its use is more appropriate.

**Tidal information** relating to the vertical movements of the water is not given and the *Canadian Tide and Current Tables* should be consulted. However, abnormal changes in water level are mentioned.

**Names** have been taken from the official source. Where an obsolete name still appears on the chart or is of local usage, it is given in brackets following the official name.

**Wreck information** is included where drying or submerged wrecks are relatively permanent features having significance for navigation or anchoring.

## Units and terminology

**Latitudes and Longitudes** given in brackets are approximate and are intended to facilitate reference to the general area on the chart quoted.

**Bearings** and **directions** refer to True North (geographic) and are given in degrees from 000° clockwise to 359°. Bearings of conspicuous objects, lights, ranges and light sectors are given from seaward. Courses always refer to course to be "made good".

**Tidal streams** and **currents** are described by the direction toward which they flow. The **ebb** stream is caused by a falling tide and the **flood** stream is caused by a rising tide. **Winds** are described by the direction from which they blow.

**Distances**, unless otherwise stated, are expressed in nautical miles. For practical purposes, a nautical mile is considered to be the length of one minute of arc, measured along the meridian, in the latitude of the position. The international nautical mile, which has now been adopted by most maritime nations, is equal to 1,852 m (6,076 ft).

**Speeds** are expressed in knots; a knot is 1 nautical mile per hour.

**Depths**, unless otherwise stated, are referred to chart datum. As depths are liable to change, particularly those in dredged channels and alongside wharves, it is strongly recommended that these be confirmed by enquiry to the appropriate local authority.

**Elevations** and **vertical clearances** are given above Higher High Water, Large Tides; in non-tidal waters they are referred to chart datum.

**Heights** of objects, as distinct from the elevations, refer to the heights of structures above the ground.

The *List of Lights, Buoys and Fog Signals* number is shown **in brackets** following the navigational aid (light, leading lights, light buoy). The expression "seasonal" indicates that the navigational aid is operational for a certain period during the year; mariners should consult the *List of Lights, Buoys and Fog Signals* to determine the period of operation. The expresion "private" means that the aid is privately maintained; it will not necessarily be mentioned in the *List of Lights* and its characteristics may change without issuance of a *Notice to Shipping*.

**Time**, unless otherwise stated, is expressed in local standard or daylight time. Details of local time kept will be found in Chapter 2 of booklet *ARC 400 — General Information, Northern Canada*.

**Deadweight tonnage** and **mass** are expressed in metric tonnes of 1,000 kilograms. The kilogram is used for expressing relatively small masses.

**Public wharf**, owned by a government authority, is a public port facility governed by various acts and regulations. Local authorities may charge harbour, berthing and wharfage fees for use of the facility. Contact must be made with the wharfinger before using the facility.

**Conspicuous** objects, natural or artificial, are those which stand out clearly from the background and are easily identifiable from a few miles offshore in normal visibility.

**Small craft** is the term used to designate pleasure craft and in general, small vessels with shallow draught.

Datum 1983 (NAD 83). **Depths** are in **metres** and are reduced to the chart datum to which the diagram refers. **Elevations** are in **metres** above Higher High Water, Large Tides and in non-tidal waters, above chart datum.

**Pictographs** are the symbols placed at the beginning of certain paragraphs. Their main purpose is to allow quick reference to information or to emphasize details. Consult the Pictograph Legend shown on the inside covers of this booklet.

## References to other publications:

### Transport Canada

- *Illustrated table of life-saving signals*

### Canadian Coast Guard

- *Canadian Aids to Navigation System*
- *List of Lights, Buoys and Fog Signals, Inland Waters*
- *Radio Aids to Marine Navigation (Atlantic, St. Lawrence, Great Lakes, Lake Winnipeg and Eastern Arctic)*
- *Ice Navigation in Canadian Waters*
- *Annual Edition of Notices to Mariners*
- *Monthly Edition of Notices to Mariners*

### Environment Canada

- *Sea Ice Climatic Atlas — Northern Canadian Waters 1971-2000*
- *MANICE*

### Canadian Hydrographic Service (www.charts.gc.ca)

- *Sailing Directions booklet ARC 400 — General Information, Northern Canada*
- *Catalogue of Canadian Nautical Charts and Related Publications #4, Arctic*
- *Chart 1*
- *Canadian Tidal Manual*
- *Tides in Canadian Waters*
- *Canadian Tide and Current Tables, Volume 4, Arctic and Hudson Bay*

### International Maritime Organization

- *International Code of Signals*
- *IMO Standard Marine Communications Phrases*
- *International Aeronautical and Marine Search and Rescue Manual (IAMSAR)*

# ABBREVIATIONS

## Units

| | |
|---|---|
| **°C** | degree Celsius |
| **cm** | centimetre |
| **fm** | fathom |
| **ft** | foot |
| **h** | hour |
| **ha** | hectare |
| **HP** | horsepower |
| **kHz** | kilohertz |
| **km** | kilometre |
| **kn** | knot |
| **kPa** | kilopascal |
| **m** | metre |
| **mb** | millibar |
| **min** | minute |
| **MHz** | megahertz |
| **mm** | millimetre |
| **t** | metric tonne |
| **°** | degree (plane angle) |
| **'** | minute (plane angle) |

## Directions

| | |
|---|---|
| **N** | north |
| **NNE** | north northeast |
| **NE** | northeast |
| **ENE** | east northeast |
| **E** | east |
| **ESE** | east southeast |
| **SE** | southeast |
| **SSE** | south southeast |
| **S** | south |
| **SSW** | south southwest |
| **SW** | southwest |
| **WSW** | west southwest |
| **W** | west |
| **WNW** | west northwest |
| **NW** | northwest |
| **NNW** | north northwest |

## Various

| | |
|---|---|
| **A.P.A.** | Atlantic Pilotage Authority |
| **A.P.L.** | Laurentian Pilotage Authority |
| **CCG** | Canadian Coast Guard |
| **CHS** | Canadian Hydrographic Service |
| **ETA** | estimated time of arrival |
| **ETD** | estimated time of departure |
| **HF** | high frequency |
| **HW** | high water |
| **LW** | low water |
| **MCTS** | Marine Communications and Traffic Services |
| **M** | million, mega |
| **NAD** | North American Datum |
| **No.** | number |
| **SAR** | Search and Rescue |
| **TDW** | Total deadweight |
| **USA** | United States of America |
| **VHF** | very high frequency |
| **VTS** | Vessel Traffic Services |

# Hudson Strait — South Shore
## Ungava Bay




### General

*Chart 5002*

1 **Hudson Strait** lies between Péninsule d'Ungava and Baffin Island and connects Labrador Sea to Foxe Channel and Hudson Bay, allowing access to the interior of the North American continent. The strait is entered from the east between Button Islands *(60°40'N, 64°40'W)* and Resolution Island, 37 miles to the north. *(Button Islands and the areas to the east and south are described in ATL 121 — Labrador, Hamilton Inlet to Cape Chidley (including Button Islands and Gray Strait).)*

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

2 The boundary between Hudson Strait and Hudson Bay is a line between Pointe Taliruq (Pointe Nuvuc), near Ivujivik on the NW tip of Péninsule d'Ungava, and Leyson Point, the SE end of Southampton Island.

3 The boundary between Hudson Strait and Foxe Channel is a line between Lloyd Point *(64°26'N, 78°02'W)*, on Baffin Island, and Seahorse Point *(63°46'N, 80°10'W)*, on Southampton Island.

4 The part of Quebec north of 55°00′N is known as the **Region of Nunavik**. The Inuit inhabitants of this region are working toward self-government. Settlements and villages along the Nunavik shore of Hudson Strait include Kangiqsualujjuaq (Port-Nouveau-Québec), Kuujjuaq (Kuujaq or Fort-Chimo), Tasiujaq, Aupaluk, Kangirsuk (Bellin or Payne Bay), Quaqtaq (Koartac), Kangiqsujuaq (Maricourt),

Salluit (Saglouc or Sugluk) and Ivujivik. There is no road access to any of these communities. Most are connected to each other by trails. Bulk commodities and fuel are supplied by annual sealift. Scheduled flights by *First Air* and *Air Inuit* and modern telecommunications connect the communities to each other and to population centres in the south. The settlements at Port Burwell, Fox Harbour, Kuurujjuaq, George River and Deception Bay are no longer occupied.

5 Baffin Island, which forms the north shore of Hudson Strait, is part of **Nunavut**. The region includes most of the Arctic inhabited by the Inuit and is self-governing. Nunavut spreads across nearly 2,000,000 square kilometres of northern Canada and supports a population of less than 27,000 *(2001)* in 26 isolated settlements. There are no roads to or between any of the Nunavut communities except between Arctic Bay and Nanisivik. Bulk commodities and fuel are supplied by annual sealift. Scheduled and charter flights by a number of carriers and modern telecommunications connect the communities to each other and to population centres to the south. Some communities are linked by foot trails in summer; these become snow machine trails in winter. The only settlements on the south coast of Baffin Island are Kimmirut (Lake Harbour) and Cape Dorset.

6 The south shores of Hudson Strait extend from Button Islands to Digges Islands and Pointe Taliruq (Point Nuvuc), 400 miles to the WNW. This chapter describes Ungava Bay, between Button Islands and Cap (Cape) Hopes Advance.

7 **Caution**. — Many of the charts referred to in this chapter include areas that have not been surveyed or have not been surveyed to modern standards; many other areas show only soundings reported by ships crossing the area. Much of the charted information in offshore waters is of a reconnaissance nature.

*Chart 5300*

8 **Ungava Bay**, on the south shore near the east end of Hudson Strait, is entered between Button Islands *(60°40'N, 64°40'W)* and Cap (Cape) Hopes Advance, 142 miles to the west. Akpatok Island, in the NW part of the bay, is the only large island.

9 The high rugged shores of Hudson Strait give way to low rolling terrain rising inland to 500 feet (152 m) in Ungava Bay.

10 The weather is more moderate towards the head of the bay; it is warmer with less fog than further north. The tree line is close to the shore at the mouths of Rivière George, Rivière à la Baleine and Rivière Koksoak.

11 **Caution**. — There are very high **tides** and strong **tidal streams** in Ungava Bay.

## Ungava Bay — East Shore

*Charts 4773, 5065*

### Killiniq (Killinek) Island to Cap (Cape) William-Smith

12 **Killiniq (Killinek) Island** *(60°25'N, 64°40'W)*, 18 miles long and 6 miles wide, has high steep headlands and is separated from Button Islands by **Gray Strait**. **Bush Island** *(60°30'N, 64°44'W)* is at the north end of Killiniq Island. **Perrett Island**, **Hettash Island** and **Flat Island**, elevation 30 feet (9 m), lie west of Bush Island. **Lenz Strait** lies between these islands and the NW part of Killiniq Island.

13 **Caution**. — There are **tide rips** in the west part of Gray Strait and 0.5 mile NW of Hettash Island and Flat Island. *(Gray Strait and the areas east and SE of Killiniq Island are described in Sailing Directions booklet ATL 121 — Labrador, Hamilton Inlet to Cape Chidley (including Button Islands and Gray Strait).)*

*Chart 4773*

14 The NE shore of Ungava Bay between Flat Island and **Amittok (Amittoq) Inlet**, 3 miles to the south, on Killiniq Island, is **not surveyed**.

*Chart 5064*

15 **Jackson Island** *(60°25'N, 64°52'W)* lies 3.5 miles south of Flat Island. **Fox Harbour** is an inlet between the NE shore of Jackson Island and Killiniq Island. There is a **drying flat** at the head of Fox Harbour. **Munro Harbour**, an inlet on the south shore of Jackson Island, is suitable only for small craft.

16 **Anchorage** can be found in the outer part of Fox Harbour but it is exposed to north winds, swell and ice and swinging room is limited.

17 **Historical note**. — The former settlement at Port Burwell, including 25 buildings, was moved to Fox Harbour in 1965. Fox Harbour was abandoned in 1978 and the inhabitants were moved to other northern communities.

18 **Forbes Sound** lies south of Jackson Island. **Cap (Cape) William-Smith** *(60°22'N, 64°51'W)* is the south entrance point of Forbes Sound.

19 **Caution**. — An unexamined **shoal** with a depth of 26 feet (7.9 m) lies in the middle of the mouth of Forbes Sound 1.2 miles NW of Cap William-Smith. Islets and **drying area**s lie up to 0.7 mile off the south shore of the sound.

20 The harbour of **Port Burwell** *(60°25'N, 64°51'W)*, on the north shore of Forbes Sound, has rugged shores with steep rocky cliffs 100 to 500 feet (30 to 152 m) high. **Mission Cove** is in the NW arm of Port Burwell.

21 **Caution**. — The **tidal streams** in Port Burwell run at up to 3 knots.

22 Vessels of up to 1,500 t can find **anchorage** with ample swinging room and good holding in 16 fathoms (29 m), mud, in the middle of the harbour or, with less room, in the inner part of the harbour. The harbour offers good shelter in most winds but may become unusable in a southerly gale. The surrounding hills and valleys can cause a strong breeze in the harbour even when it is calm outside.

23 **Anchorage** can also be found in Forbes Sound in 20 to 25 fathoms (37 to 46 m), fair holding, 1 mile east of Port Burwell harbour entrance and 0.25 to 0.5 mile offshore, but west winds can bring a heavy swell.

24 There is a **landing beach** of mud, gravel and **boulders** on the north side of the head of Fox Harbour, just west of the **drying flat**. The landing can be reached from Fox Harbour at most stages of the tide but only for 2 hours before and after high water from Port Burwell anchorages.

25 The *Canadian Coast Guard* radio station "*Killinek*" is 0.3 mile NE of Mission Cove. This is a remote station controlled by *MCTS Iqaluit*. *(See Radio Aids to Marine Navigation — Atlantic, St. Lawrence, Great Lakes, Lake Winnipeg and Eastern Arctic)*.

*Charts 4773, 5064*

26 **Goddard Island** is at the SE end of Forbes Sound; there is reported to be a **shoal** off the west side of the island. **McLelan Strait** leads between Goddard Island and Killiniq Island. **Young Inlet**, stretching 6 miles SE from Goddard Island, can be approached from McLelan Strait and entered through a passage on the east side of Goddard Island.

27 **Anchorage** has been found, in 17 fathoms (31 m), east of Goddard Island in the entrance to Young Inlet.

28 McLelan Strait continues SE to connect with Grenfell Sound and the Labrador Sea. *(Grenfell Sound and the Labrador Sea are described in Sailing Directions booklet ATL 121 — Labrador, Hamilton Inlet to Cape Chidley (including Button Islands and Gray Strait).)*

29 The usual approach to Fox Harbour and Forbes Sound is from northward following the sounded track.

30 **Caution**. — A vessel approaching from the west would make landfall on Button Islands because the coast south of Forbes Sound is **foul**. The water is deep close to the rocks; soundings give no warning.

*Charts 5300, 4773*

## Cap William-Smith to Rivière George (River)

31 The land between Cap William-Smith *(60°22'N, 64°51'W)* and the mouth of Rivière George (River) *(58°54'N, 66°17'W)*, 100 miles to the SSW, is low but rises to 500 feet (152 m) a few miles inland and to over 1,000 feet (305 m) in places. **Drying flats** and islets and **rocks** lie off most of the shoreline. Named inlets along this coast, from north to south, are: **Coates Inlet**, **Polunin Inlet**, **Christopher Inlet**, **Singer Inlet**, **Bell Inlet**, **Langley Inlet**, **Low Inlet**, **Bray Inlet**, **Cox Inlet**, **Alluviaq (Abloviak) Fiord**, **Weymouth Inlet**, **Gregson Inlet** and **Davis Inlet**. These inlets are **not surveyed**.

*Chart 5300*

32 **Cap Kattaktoc** *(59°17'N, 65°44'W)*, the west entrance point of Davis Inlet, is low with a sharp point.

33 **Beacon Island** *(58°54'N, 66°21'W)* is the northernmost of a group of rocky islands and islets on a wide **boulder**-strewn **drying flat** that extends north and NE of **Pointe Hubbard**.

*Chart 5373*

34 **Kikkertoksoak Islands**, in the mouth of **Keglo Bay**, are low. There are islets and ledges and **drying flats** around the shorelines of these features.

35 The **beacon** at Beacon Island consists of fluorescent-orange rectangular **daymarks** and a **radar reflector** on a square skeleton **tower**.

36 A **racon** is also on the tower.

*Charts 5373, 5335*

## Rivière George and Approaches

37 **Rivière George (River)** is approached from north of Beacon Island; the area south and SW of Beacon Island is foul. The river is entered east of Beacon Island. It is reported to be navigable by small craft for 200 miles with only one portage but the current is swift. Sealift vessels travel 14 miles upstream from the entrance to the village of Kangiqsualujjuaq (Port-Nouveau-Québec).

38 **Ningiuluit Islands** *(59°03'N, 66°07'W)* and **Pissiulaarsitik Islands**, 6 miles to the south, are on the east side of the approach to Rivière George. **Tikiraaluk Island** and **Qiggutuq Islands** lie farther to the east.

39 **Cap Kattatuuq**, 2 miles south of Tikiraaluk Island, divides the two arms of **Tasiujaaluk Bay**; **Rivière Koroc** enters the head of the south arm of Tasiujaaluk Bay.

40 **Pointe Elson** *(not named on Chart 5373)*, at the mouth of the south arm of Tasiujaaluk Bay, is an island at high water.

41 **Qikirtaaluk Island** *(58°51'N, 66°08'W) (not named on Chart 5373)* is 6.5 miles ESE of Beacon Island; it is 60 m high.

42 **Sallijukak Islet** is 2 miles west of Beacon Island.

43 **Caution**. — There are **dangerous reefs** in the approaches to Rivière George; rough seas will break on some of these reefs at low water. The outermost of these is a patch 3 miles NNE of Beacon Island that dries 3.5 m. **Shoal**

**banks** and **isolated shoals** with depths of 3.4 m extend into the river from the east and west sides of the entrance.

44 The **tidal range** in Rivière George is 7.6 to 9.8 m in large tides and 3.7 to 6.7 m in mean tides.

45 **Caution**. — **Tidal streams** in the river reach 5 knots or more and there are **tide rips** when the wind is against the current.

46 Unsheltered **anchorage** can be found 1.0 mile east of Beacon Island.

*Chart 5335*

47 **Îles Naujakallak** lie 3 miles SSE of Beacon Island on the west side of the river.

48 **Pointe Kapitattalik** *(58°49'N, 66°16'W)* is on the west shore 5.6 miles SSE of Beacon Island; the site of the abandoned settlement of **Kuurujjuaq** is 0.9 mile SSE of the point.

49 **Pointe Allatalik** is on the same side 7.5 miles farther SSE.

50 **Cap Qairtualuk** *(58°46'N, 66°06'W)* and **Cap Nuvukallak** are on the east bank 7 and 11 miles from the entrance.

51 **The Narrows** is 13 miles from the river entrance and 2 miles SE of Cap Nuvukallak.

52 **Colline Qikirtaujaq** is a hill SW of The Narrows.

53 The land on both shores rises to 140 m, in gentle slopes, from the entrance of the river to The Narrows. Above The Narrows, the valley is more fiord-like. Most of the small bays along the river have bottoms of mud, some with scattered **boulders**, and **dry** out at low water.

54 **Caution**. — A **rock** 0.2 mile SSE of the SE point of Cap Nuvukallak dries 0.3 m.

55 At the downstream entrance to The Narrows there is a depth of 7.3 m at the edge of **shoals** extending from the SW shore. Depths of 7.7 m are found in the middle of The Narrows at the upstream entrance.

56 **Anse Akilasakallak** is a bay on the NE shore NE of The Narrows.

57 The village of **Kangiqsualujjuaq (Port-Nouveau-Québec)** *(58°41'N, 65°57'W)*, population 710 *(2001)*, is on the NW shore of Anse Akilasakallak. The village has a post office, police station, nursing station, retail stores and a hotel. *Air Inuit* provides daily flights except Sundays.

58 There are two breakwaters and a beach access ramp on the west shore of Anse Akilasakallak near the village. The south **breakwater**, 0.2 mile SSE of the village, is 1.3 m high and extends 160 m offshore. The **landing beach** protected by this breakwater is accessible from the village road by a stone and gravel ramp. The north **breakwater** is an extension of the natural point on the shore just SE of the village; it is 1.3 m high and extends the point by 30 m to protect the bay in front of the village. Much of the beach and channel area between the breakwaters has been cleared of boulders.

59 An **anchorage** charted 0.9 mile ESE of Pointe Allatalik has a bottom of mud and gravel.

60 Shallow-draught vessels with oil supplies for the settlement have used the two **anchorages** off the entrance to Anse Akilasakallak.

61 **Caution**. — The **tidal stream** in these berths is reported to run strongly southward for 3 hours after low water at the river entrance; a period of slack water lasts from then until 3½ hours after high water when the current becomes strongly northward. The inner berth has been reported to be unsafe because of strong eddies but the outer berth was considered to be more satisfactory.

*Chart 5300*

62 **Île Ford** is 8 miles upstream from Kangiqsualujjuaq.

63 **Historical note**. — A settlement known as George River, dating back to 1876, was on the east shore of the river near Île Ford. In 1965, the village was relocated to Anse Akilasakallak and renamed Port-Nouveau-Québec. The village officially became known by its Inuit name in 1990.

## Ungava Bay — South Shore

### Rivière George to Rivière Koksoak (River)

64 Between Pointe Hubbard *(58°50'N, 66°28'W)*, 5.5 miles SW of Beacon Island, and Pointe Qirniraujaq (Congnarauya Point), 50 miles to the WSW, the coast is low with **drying flats**, **shoal water** and many **outlying dangers**. Rivière Koksoak (River) enters Ungava Bay 5 miles SW of Pointe Qirniraujaq (Congnarauya Point).

*Charts 5374, 5375*

65 **Caution**. — The coastal waters covered by *Charts 5374* and *5375* were surveyed to different standards, as indicated on the "Source Classification" diagram on the charts. Most inshore waters have not been surveyed.

*Chart 5374*

66 **Îles Nauyut** and **Îles Arvalik** lie 6 and 14 miles SSW of Pointe Hubbard.

67 **Cap Kernertut** *(58°31'N, 66°56'W)*, 60 m high, is west of the mouth of **Rivière Qurlutuq**. **Pissiulaarsitik Island**, 55 m high, is the largest of a group of islets and **shoals** off Cap Kernertut.

68 **Alukpaluk Bay**, 9 miles SW of Cap Kernertut, has the mouth of **Rivière Tuttutuuq** at its head. **Colline Inuksulik**, 45 m high, is a hill on the NE side of the bay.

69 **Qikirtaaluk Islands** *(58°37'N, 67°10'W)* are 9 miles NW of Cap Kernertut.

*Chart 5300*

70 **Rivière à la Baleine** *(58°20'N, 67°30'W)* is at the south end of Ungava Bay. The banks of the river are generally low and wooded with small black spruce and larch trees almost to the river mouth. The land rises to 150 m a few miles inland.

71 There is an abandoned *Hudson's Bay Company* post 8 miles up Rivière à la Baleine. The channel to the site passes through **drying mud flats**. The current is swift and there are **rapids** and **tide rips** in several places.

*Chart 5375*

72 **Qikirtajuaq (Big) Island** *(58°20'N, 67°35'W)* is in the mouth of Rivière à la Baleine with **Tuvakutaaq Channel** on its west side. The island is 61 m high in its SW part; many islands, islets and **shoals** lie off its north and NE sides. **Sallijuaq Islands** and **Narruriat Islands** are groups of offshore rocky islands and **reefs** NE and north of Qikirtajuaq Island. **Saeglorsoak Island**, the southernmost of the larger Narruriat Islands, can be identified by a 30 m high hill in its south part; low land extends 1 mile north of this hill.

73 **Caution**. — **Drying patches** and **shoals** with depths of less than 10 m lie up to 20 miles NE, 12 miles north and 13 miles NW of Narruriat Islands.

74 **Pointe Tasker** *(58°28'N, 67°45'W)*, 6 miles NW of Qikirtajuaq Island, is 30 m high. **Rivière False**, west of Pointe Tasker, is very **shoal**. Rivière False is so named because it is often mistaken for the mouth of Rivière Koksoak (River).

75 **Pointe Qirniraujaq (Congnarauya Point)** *(58°35'N, 68°01'W)* is a low dark point 10 miles NW of Pointe Tasker; the point is 5 miles NE of the entrance to Rivière Koksoak (River). A **mud flat**, extending 1 mile NE of the point, has a **rock ledge drying** 2.7 m at its outer edge.

76 There is a **racon** and a **radar reflector** on a 9.1-m tall aluminium **tower** on Pointe Qirniraujaq.

*Charts 5376, 5300*

77 **Cap Inuksutujuq** *(58°33'N, 68°12'W)*, 6 miles WSW of Pointe Qirniraujaq, is the west entrance point of Riviere Koksoak (River). **Mud flats** and **drying ledges** extend more than 1 mile off the cape and off the shores west and north of here.

78 There is a **radar reflector** on a 30-m tall aluminium **tower** 1.2 miles south of Cap Inuksutujuq.

## Approaches to Rivière Koksoak (River)

79 **Caution**. — The outermost dangers in the NE approaches to **Rivière Koksoak (River)** *(58°33'N, 68°09'W)* are **shoal patches** 15 miles NE of Cap Inuksutujuq and **isolated depths** of less than 10 m farther offshore.

80 **Springs Reef** and **Octopus Reef** are **drying area**s 8 miles NNE and 6 miles north of Cap Inuksutujuq; there are heavy **tide rips** near the reefs. **Caution Shoals**, which extend 3 miles west and NW of Pointe Qirniraujaq, have depths of 5.4 m and 7.3 m near the track usually followed.

*Charts 5376, 5338*

## Rivière Koksoak

81 Rivière Koksoak is navigable by medium-draft ships to within 2 miles of the village of Kuujjuaq, 31 miles upstream. The upper reaches are **shoal** and must be navigated between half tide and high water.

82 Rivière Koksoak has been used regularly by a tanker drawing 5.5 m.

83 The **tidal ranges** for mean tides and large tides are 8.9 m and 12.6 m at the river entrance and 4.6 m and 5.9 m at Kuujjuaq.

84 High water travels from the river entrance to Île Mackays, 17 miles upstream, in 1¼ hours and to Kuujjuaq in 2 hours.

85 The tidal streams turn 1¼ hours after the times of high and low water.

86 **Caution**. — It has been reported that the **tidal stream** in the river can reach 12 knots in places during large tides and reach a rate of 6 to 8 knots in the river entrance. Tide **rips** and **overfalls** form in the entrance in NE winds when the ebb stream is running. In large tides there are **whirlpools** in the narrow parts of the river. These conditions are **dangerous** for small craft.

87 **Caution**. — **Depths** in Rivière Koksoak may change due to the action of ice and current and the movement of boulders on the river bed.

89 *Beacon Point (Inukshuktuyuk) range* **lights** *(2595, 2596)*, on Cap Inuksutujuq, lead clear of the dangers in the approaches.

90 Vessels usually approach the entrance to Rivière Koksoak at low water, when the off-lying **drying patches** are visible.

91 The **racon** on Pointe Qirniraujuq is a useful aid until the *Beacon Point (Inukshuktuyuk) range* lights are seen.

*Chart 5338*

92 **Pointe Aisavartalik** *(58°32'N, 68°08'W)*, separated from Pointe Qirniraujaq by **drying flats** of mud and **boulders**, is the east entrance point of Rivière Koksoak. **Anchor Island** lies 0.1 mile NW of Pointe Aisavartalik. **The Wart** is a **conspicuous** hill 0.7 mile to the south.

93 The river bank has **drying patches**, **conspicuous** at low tide, in front from Cap Inuksutujuq to **Schnak Cove** 1.7 miles to the south.

94 *Koksoak River East range* **lights** *(2593, 2594)* are on the east bank of the river 2.2 miles SSE of Schnak Cove.

95 **Caution**. — The range leads from the intersection with *Beacon Point (Inukshuktuyuk) range* into the mouth of the river. Do not use *Koksoak River East range* to approach the river from offshore between Octopus Reef and Springs Reef *(Chart 5376)*.

96 *Koksoak River range* **lights** *(2591, 2592)*, on the west bank of the river 4.2 miles south of Schnak Cove, lead through the lower reach of Rivière Koksoak.

97 **Île Edge** *(58°29'N, 68°12'W)* lies off the west shore 3 miles upstream from Schnak Cove. **The Narrows** is entered 1.5 miles SSE of Île Edge.

98 Vessels with local knowledge continue upstream and await the pilot at an **anchorage** 5 miles beyond The Narrows.

99 **Pointe Kisarvik** *(58°23'N, 68°13'W)* is on the west shore 4.2 miles SSW of The Narrows.

100 A series of **lighted beacon ranges** aid navigation south of here. Each **beacon** consist of a fluorescent orange trapezoid **daymark**, with a black vertical stripe, mounted on a galvanised steel **tower**.

101 **Anchorage** can be found in the river 0.7 mile SSE of Pointe Kisarvik.

102 In 1981, *MV Polar Circle* anchored here in 16 m, fine sand, 0.4 mile off the west shore, opposite a white boulder.

103 The river **shoals** to 5.8 m 2.5 miles south of Pointe Kisarvik. **Île Hendry** and **Île Mackays**, with **Île Pakkivik** at its south end, lie 4 and 5 miles south of the shoal area.

104 **Caution**. — Because of strong **currents** and nearby **shoals**, extreme **Caution** is necessary at all stages of the tide when passing Île Hendry.

105 There are privately maintained **lights** on the SW side of Île Hendry and on the east part of Île Mackays.

106 **Cap Whales**, rising abruptly to 23 m, lies 5 miles farther SSW.

107 There is a privately maintained **light** on the east side of Cap Whales.

108 **Colline Chapel** is a **conspicuous hill** opposite Cap Whales.

109 **The Elbow** is a **shoal** passage entered 4 miles south of Cap Whales. Islands in the river SE and south of The Elbow include **Grande île Elbow**, with a **conspicuous boulder** on its NE part, **Petite île Elbow**, **Île Midway** and several smaller islands and islets. **Île Bar** is in mid-river 1 mile SW of Île Midway.

110 **Anse Nascopie**, sheltered by **Pointe Illukuluttalik**, is on the NW shore west of Île Midway.

111 There are privately maintained **lights** on the west shore 0.9 mile north of Grande île Elbow, near the NE tip of Grande île Elbow, on the NW end of Île Midway, and on the NE side of Île Bar.

112 The village of **Kuujjuaq (Kuujjaq or Fort Chimo)**, population 1,932 *(2001)*, is on the NW shore of Anse Nascopie. The region of Nunavik is administered from here. The community has a post office, bank, police services, a hospital with dental care facilities, several retail stores and restaurants and 2 hotels. *First Air* and *Air Inuit* provide daily flights. Aircraft, including helicopters, are available for charter.

113 **Historical note**. — The site of the former community of Fort Chimo, abandoned in 1958, is 2.5 miles south of Colline Chapel. The present village is on the site of a former US military airport, built in 1942, turned over to Canada at the end of the Second World War. The two long airstrips make Kuujjuaq the transportation hub of Nunavik.

114 The usual **anchorage** for Kuujjuaq, in depths of 5 to 14 m, is from 0.15 to 0.35 mile north of a line between the NE point of Grande Île Elbow and a **conspicuous boulder** on the east shore.

115 **Caution**. — The holding ground of coarse stone is reported to be good but no anchorage in the river can be considered safe because of the ever-changing **currents**; a vessel should be ready to move at short notice.

116 The **landing beach** is on the shore of Anse Nascopie near a group of **oil tanks**.

117 Barges are used to land dry cargo at a small **pier** on the beach.

118 Oil products are offloaded to shallow-draught barges and taken to the pier to be pumped to the tank farm.

119 Due to swift **tidal streams** and **shoal** water, barges can only cross the river to the anchorage for 2 hours before and 2 hours after high water.

120 A privately maintained **aeromarine radiobeacon** *(58°03'N, 68°29'W)* near Kuujjuaq transmits on 390 kHz with identification VP (• • • — • — — •).

121 The average maximum thickness of winter **fast ice** at Kuujjuaq is 138 cm, with a record thickness of 177 cm *(1973)*. Break-up usually begins in the second half of May, with the river clear of ice in the first week of June. Freeze-up usually begins in the first week of November with complete ice cover in early January. Dates of break-up and freeze-up can vary by three to four weeks.

## Ungava Bay — SW Shore

*Charts 5376, 5467*

### Rivière Koksoak to Leaf Bay (Baie aux Feuilles)

122 **Pointe Ragged** *(58°49'N, 68°24'W)* is 17 miles NNW of Cap Inuksutujuq. Features between Cap Inuksutujuq

and Pointe Ragged include **Qikirtaguluk Island** and **Baie Sèche**, **Qikirtaajuit Islands**, **Sham Bay**, **Itittaviit Islands**, **Pauktorvik Island**, **Sawtooth Bay**, **Pointe Asuqaaq (Asuraaq)** and **Asuuqaaq Island**.

123 **Caution**. — There is a **drying patch** surrounded by **shoals** 6 miles east of Pointe Ragged.

124 **Stony Islands** *(58°53'N, 68°32'W)*, rocky knolls that become islands at high water, are 6 miles NNW of Pointe Ragged. There are huge masses of rock scattered in the area.

125 **Caution**. — Most of the coast between Cap Inuksutujuq and Stony Islands is **not surveyed** but is known to be **foul** for several miles offshore; **shoals** of less than 6 fathoms (11 m) lie 12 miles and more from shore.

126 **Blind Reef** *(59°02'N, 68°41'W)* is a **drying area** 10 miles NNW of Stony Islands. A **rock** 1.5 miles to the NNE has a depth of 14 feet (4.3 m) and there are depths of less than 6 fathoms (11 m) up to 3 miles north, east and south of Blind Reef.

127 **Pointe Stony** *(58°55'N, 68°36'W)*, on the SE side of the entrance to Leaf Bay, rises to a rocky hill 200 feet (61 m) high. The water is very **shoal** for 2 miles off the point.

128 Five miles farther offshore, the sea breaks on **reefs**; one of these, **Bosuns Reef**, 5 miles NE of Stony Islands, dries 8.5 m.

129 The land west of Pointe Stony rises gradually to long rounded hills 200 feet (61 m) high.

*Charts 5300, 5467, 5468, 5469*

## Leaf Bay and Lac aux Feuilles

130 **Leaf Bay** *(58°57'N, 68°50'W)* is the outer part of an inlet which leads 35 miles WSW to the mouth of Rivière aux Feuilles. The inner parts of this inlet are Passe Smoky, **Passage aux Feuilles**, Passe de l'Algerine and **Lac aux Feuilles**.

131 The **tidal ranges** in Lac aux Feuilles are among the highest in the world.

132 **Caution**. — There are very strong **currents** and **dangerous eddies** in Leaf Bay and Passage aux Feuilles. The **tidal currents** in Passe Smoky reach a maximum of 12 knots at springs and 4 knots at neaps, near the time of local high water.

*Chart 5467*

133 **Gyrfalcon Islands** *(59°03'N, 68°55'W)*, extending northward 10 miles from Leaf Bay, are formed of barren broken ridges of stratified rock. The islands vary from 50 to 300 feet (15 to 91 m) high and have cliffs that face SW. The mainland has the same character as the islands and is so broken by bays that it is very difficult to identify.

134 **Dome Island** *(59°04'N, 68°51'W)* is the easternmost of the Gyrfalcon Islands group. The **dome shape** is **conspicuous** when seen from the south.

135 **Falcon Anchorage**, between **Nipper Island** and **Tiercel Island**, offers good shelter and holding in 12 fathoms (22 m). Vessels planning to use Passage aux Feuilles anchor here while waiting for a favourable tide. The **tidal stream** in the anchorage is not excessive. **Nipper Reef**, 1 mile SE of Nipper Island, dries 34 feet (10.4 m).

136 There is a **beacon** with a fluorescent-orange rectangular **daymark** and a **radar reflector** on a skeleton **tower**, 25 feet (7.6 m) high, near the east tip of the south end of Nipper Island.

137 A **racon** is on top of the beacon.

138 **Talon Reefs**, off the south and SW part of Tiercel Island, **dry** 22 and 32 feet (6.7 and 9.8 m).

139 **Peregrine Sound** is between Gyrfalcon Islands and the mainland to the west.

140 **Pointe Flat** *(58°55'N, 68°46'W)* and **Pointe False**, 7 miles to the west, are on the south side of Leaf Bay, west of Pointe Stony. **False Islet**, **conspicuous**, is connected to Pointe False at low water by a rocky ridge. **Stony Shoals** extend 2 miles and more off the south shore of Leaf Bay, north of Pointe Stony and Pointe Flat and east of False Islet.

141 Passage aux Feuilles tends SW 15 miles from Leaf Bay to Lac aux Feuilles. **Passe Smoky** *(58°55'N, 69°15'W)* is the east entrance narrows. There is **shoal** water along the south shore of the narrows. Wide **rocky drying flats** line both sides of Passage aux Feuilles.

142 **Pointe Henderson**, 200 feet (61 m) high, is on the mainland north of Passe Smoky. **Îles Smoky** form the north side of Passe Smoky.

143 **Pointe Wedgehead** is a **conspicuous** headland to the south of Passe Smoky.

*Chart 5468*

144 On the north shore of the passage, **Detroit Island** leads NW of Îles Smoky.

145 **Îlot Irqituq** *(58°54'N, 69°24'W)* is in the entrance to **Baie Boulder**. The bay is **not surveyed**.

146 **Pointe au Fer**, 2.5 miles farther SW, is 50 feet (15 m) high.

147 **La Grande Ravine**, a point 2 miles farther WSW, has a **conspicuous vein** of yellow rock extending from the water's edge to its summit. **La Petite Ravine**, a small island with a similar feature, lies 1 mile to the south.

148 Features on the south shore of Passage aux Feuilles are **Cap Fox** *(58°52'N, 69°23'W)*, **Cap Halfway**, **Pointe Garry** and **Pointe Spur**. There is a **conspicuous waterfall** 1.2 miles SSE of Cap Halfway.

149 **Iron Shoal**, in mid-channel WSW of Cap Halfway, has a depth of 16 feet (4.9 m). There are depths of less than 5 fathoms (9.1 m) between Iron Shoal and Pointe au Fer.

150 **Pointe Reef** *(58°47'N, 69°32'W)* is on the south shore 2 miles WSW of Pointe Spur.

151 **Pointe Bluff**, 1.4 miles NNW of Pointe Reef, is 300 feet (91 m) high. **Drying banks** and **shoal** water extend up to 0.5 mile from Pointe Bluff.

152 **Passe de l'Algerine** is entered between Pointe Reef and Pointe Bluff. **Pointe de l'Algerine**, on the north shore, and **Pointe Mary**, 2 miles to the SE, are the west and SW entrance points to the narrows.

153 **Caution**. — There are very strong **currents** and **dangerous eddies** in Passage aux Feuilles. Vessels should transit Passage aux Feuilles only with a favourable tide. The **tidal currents** in Passe Smoky reach a maximum of 12 knots at springs and 4 knots at neaps; in Passe de l'Algerine, they reach a maximum of 10 knots at springs and 3 knots at neaps. These maximum currents occur near the time of local high water. The tidal stream is comparatively weak for 1 hour after the turn of the tide.

*Chart 5469*

154 Lac aux Feuilles *(58°46'N, 69°44'W)*, entered through Passe de l'Algerine, is a large landlocked basin with wide **drying flats** along its shores.

155 The climate in Lac aux Feuilles is milder than that at the entrance to Leaf Bay; Lac aux Feuilles is almost always free of fog.

156 The **tidal range** at spring tides in Lac aux Feuilles is estimated to be 54.5 feet (16.6 m); if confirmed, this would be the largest range in the world. High water at Baie Profonde is 1 1/3 hours after high water at Falcon Anchorage.

157 **Caution**. — The **tidal streams** are 1 to 4 knots in Lac aux Feuilles.

158 **Whaleback Reef**, in the middle of the entrance to Lac aux Feuilles, dries 19 feet (5.8 m). Ships usually pass north of the reef.

159 **Trading Post Cove**, on the SE shore of the basin and sheltered to the west by **Îles Radisson**, offers **anchorage** in 12 fathoms (22 m). The buildings at the head of the bay are an abandoned *Hudson's Bay Company* post.

160 **Baie Sèche**, with extensive **drying flats**, is entered west of Îles Radisson. The bay lies between **Pointe Copper** and **Pointe Lajus**.

161 **Île de l'Hélicoptère (Copter Island)** *(58°46'N, 69°50'W)*, with a central hill 452 feet (138 m) high and two small islands to the south, is connected to **Pointe de la Jauge** at low water.

162 **Îlot Bittern**, 110 feet (33.5 m) high, **Île en Cône**, 250 feet (76 m) high, and **Récif Long** lie north, NE and SE of Île de l'Hélicoptère.

163 **Pointe de la Rivière** is 1.4 miles west of Île de l'Hélicoptère. **Îlot Poly** and **Îlot Mandarin** lie off Pointe de la Rivière.

164 **Baie Profonde** is entered between Îlot Bittern and Îlot Poly.

165 Baie Profonde offers the best **anchorage** in Lac aux Feuilles, with room for several medium-draught vessels. Little sea develops in the landlocked basin; the 225-foot (69-m) survey ship *Algerine* rode out 70-knot winds here without trouble. Anchorage can be found in most of the bay; a good well-sheltered location is midway between Pointe de la Jauge and **Île Rowe**, in 22 fathoms (37 m) with excellent holding ground, mud bottom.

165.1 **Caution**. — An isolated **shoal depth** of 33 feet (10 m) is 0.5 mile east of Île Rowe and an isolated **shoal depth** of 6 fathoms (11 m) is 1.4 miles south of the island.

166 **Rivière Bérard** flows into the SW corner of Baie Profonde.

167 The village of **Tasiujaq**, population 228 *(2001)*, is on the west shore north of Rivière Bérard. The village was founded in the 1960's to remove some of the hunting pressure on wildlife around Kuujjuaq. It has a post office, a nursing station and a police station. There is a community-owned-and-operated store; quantities of supplies for sale to non-residents are very limited. *Co-op* accommodation is available by prior arrangement. *Air Inuit* provides daily flights except Sundays.

168 **Baie aux Baleines**, on the north shore of Lac aux Feuilles between Pointe de l'Algerine and **Pointe Kennedy** *(58°50'N, 69°48'W)*, is **not surveyed**.

169 **Île Qirnilik** *(58°49'N, 69°54'W)*, 50 feet (15 m) high, is 1.7 miles west of Pointe Kennedy. **Anse aux Refuges** is a **drying bay** between Pointe Kennedy and Île Qirnilik.

170 **Fresh water** can be obtained from a **waterfall** and several small streams around Lac aux Feuilles.

171 **Rivière aux Feuilles** enters Lac aux Feuilles from the west between Pointe de la Rivière and Île Qirnilik; it flows between high bluffs and is deep in mid-channel as far as a **drying bar** 6 miles upstream. Only the mouth of the river has been surveyed.

*Chart 5300*

## Leaf Bay to Hopes Advance Bay

172 The coast between Leaf Bay and Hopes Advance Bay, 30 miles to the NNW, has a belt of islets and **reefs** extending 10 to 15 miles offshore.

*Chart 5348*

173 **Sentinel Reef** *(59°16'N, 68°49'W)* dries 4 feet (1.2 m); it is the outermost charted danger. Between Sentinel Reef and the mainland are **Nanertak Reefs**, a group of **drying patches** in a wide area of unexamined foul ground. **Nanertak Island**, 45 feet (13.7 m) high, is at the NNW end of the reefs.

174 **Ikattok Bay**, SW of Nanertak Reefs, is **not surveyed**. **Cone Island** *(59°12'N, 69°09'W)*, small but 160 feet (48.8 m) high, is **conspicuous** in the mouth of Ikattok Bay.

175 **Pointe De Villiers**, at the NW end of **Pointe Takiyok** 9 miles NNW of Cone Island, is 100 feet (30 m) high. Pointe de Villiers is the east entrance point of **Anse De Villiers**. **Escarpement Tryon**, 7 miles SW of Pointe De Villiers, is a **conspicuous bluff** 402 feet (123 m) high.

176 **Shoal water** extends 6 miles NE from Pointe Takiyok. **Takiyok Reef** and **Sawtooth Reef** are two **drying area**s near the outer end of the shoal area.

## Approaches to Hopes Advance Bay

177 **Hopes Advance Bay** *(59°21'N, 69°36'W)* is the site of an abandoned mining development. Inuit wishing to return to traditional hunting grounds established the settlement of Aupaluk near the old mine site in 1977.

178 The usual track through the approaches and into Hopes Advance Bay is shown on the chart. Much of the track has been wire-dragged; these areas are shown by broken lines and swept-depth symbols. A **conspicuous** radio **tower** *(59°18.190'N, 069°36.070'W)* with an elevation of 184 feet (56 m) showing a fixed red **light** is visible up to 20 miles to seaward while on the usual track through the approaches.

*Charts 5348, 5349*

179 **Barrier Shoals** *(59°33'N, 69°08'W)* lie along the NW side of the track.

180 **Caution**. — A **rock** on the SW part of Barrier Shoals has a depth of 6 feet (1.8 m) or less.

181 **Low Islands** is a line of **drying patches** and islets NW of Barrier Shoals. Low Islands include **Young Island** and **Lookout Island**. **Sandpiper Islet** and **Buttress Island** are 3 miles NE and 3 miles NW of Lookout Island.

182 A line of **reefs** extends 4 miles NE from **Alle Island** on the NW side of the entrance to Hopes Advance Bay. Two reefs at the outer end **dry** 6 and 17 feet (1.8 and 5.2 m). **Coffin Islet** is SW of Alle Island. **Alle Reefs** lie around the SW, south and east sides of Alle Island, forming the north side of the outer part of the bay.

183 **Pointe Gable** *(59°22'N, 69°26'W)* is the SE entrance point of Hopes Advance Bay.

184 **Black Rock**, 3 miles NE of Pointe Gable, dries 38 feet (12 m) and is **conspicuous** at low water.

*Chart 5349*

185 **Funnel Cove** is on the south side of Hopes Advance Bay. The cove lies between **Pointe Range** *(59°20'N, 69°34'W)* and the **conspicuous** cone-shaped **Colline Apex**.

186 **Rivière au Chien Rouge**, almost **dry** in summer, flows into the head of the bay through 20-foot (6-m) high sand banks.

187 **Anse Merganser** *(59°21'N, 69°39'W)* is on the north side of the inner part of Hopes Advance Bay between **Pointe Breakwater** and **Pointe Merganser**. Pointe Merganser was once the site of a mining camp.

188 A **reef** with 6 feet (1.8 m) over it lies near the middle of the bay 1 mile SW of Pointe Breakwater. A **shoal spit** projects 1 mile NNW from the east side of Funnel Cove.

189 **Anchorage** with good holding in 10 fathoms (18.3 m), mud, and excellent shelter can be found in Anse Merganser.

190 The route into Anse Merganser is marked by four **leading beacon ranges**.

191 Each **beacon** is a fluorescent-orange trapezoid **daymark** with a black vertical stripe on a square skeleton **tower**.

192 The outermost pair of beacons are on Pointe Range in line bearing 228°. They mark the approach to Hopes Advance Bay.

193 The next pair of beacons, in line bearing 239°, is on Colline Apex.

194 Beacons on Pointe Gable, in line astern bearing 078°, lead south of Pointe Breakwater.

195 Beacons in Anse Merganser, in line bearing 293°, lead to the anchorage off Anse Merganser.

196 The maximum **tidal stream** between Pointe Gable and Anse Merganser is less than 2 knots and in the anchorage it is negligible.

197 **Caution**. — The **tide** in the cove ebbs rapidly; the water level off Pointe Merganser has been observed to fall 5 or 6 feet (1.5 or 1.8 m) in 20 minutes. Rocks appear to rise from the water at an alarming rate.

198 Because of the large **tidal range**, the appearance of the approaches changes considerably between high and low water and can be deceiving. However, the following are good **landmarks** for visual fixing: Cone Island, Nanertak Island, Pointe Gable, Black Rock, Young Island, Lookout Island and Colline Apex. Landfall can usually be made while still in sight of Akpatok Island *(described in the next section)*.

199 The community of **Aupaluk** *(not shown on the charts)*, population 159 *(2001)*, is on the south coast of Hopes Advance Bay on the east shore of Funnel Cove. The settlement is the smallest of the Nunavik communities. There is a post office, nursing station and a police station. A *Co-op* store can provide only limited supplies. *Co-op* accommodation is available by prior arrangement. *Air Inuit* provides daily flights except Sundays.

*Chart 5348*

## Hopes Advance Bay to Payne Bay

200 **False Bight**, on the mainland west of Low Islands *(previously described)*, has many **shoals** and **reefs**. **Rivière**

**Saint-Fond** and **Rivière Borel** flow into the west side of False Bight.

*Chart 5300*

201 **Baie de Bonnard** *(59°42'N, 69°32'W)*, 23 miles north of Hopes Advance Bay, is almost completely **dry** at low water. **Rivière Lefroy** empties into the bay. This stretch of coast is **not surveyed**.

*Chart 5351*

## Approaches to Payne Bay and Rivière Arnaud (Payne River)

202 **Baie Brochant** *(59°54'N, 69°42'W)* is **not surveyed**. **Rivière Brochant** flows into the head of the bay.

203 **Ivik Island** *(59°56'N, 69°40'W)*, with twin summits 250 feet (76 m) high, is on the north side of Baie Brochant. The island is separated from the mainland by **Illusion Sound**. The sound dries at low water but has not been completely surveyed. **Tuvak (Tuwak) Reefs**, 2 reefs 6 miles east of Ivik Island, **dry** 6 feet (1.8 m) and 24 feet (7.3 m). **Kidlikpait (Kitdliat) Islet** *(59°59'N, 69°38'W)* is near the outer edge of **drying flats** reaching more than 1 mile NE from Ivik Island. **Kidlikpait (Kitdliat) Reefs** extend 2 miles farther ENE.

204 There is a **radar reflector** on an aluminium **tower** 25 feet (7.6 m) tall on Kidlikpait Islet.

205 A **racon** is on the tower.

206 **Pamiok Island** is on the NE side of a wide **drying flat** on the north side of the entrance to Payne Bay. **Pamiok Point** is the SE end of the island. **Ranger Island** is on the south part of the **drying area**.

207 **Caution**. — **Ranger Reef**, 1 mile east of Ranger Island, dries 28 feet (8.5 m). **Guillemot Shoal** *(60°04'N, 69°28'W)*, submerged 3 fathoms (5.5 m), is 2.6 miles ESE of Pamiok Point. An **isolated shoal** of the same depth lies 1 mile SE of Pamiok Point.

*Charts 5351, 5352*

208 **Payne Bay** *(60°01'N, 69°39'W)* is entered between Kidlikpait Reef and Ranger Reef. **Colline Alakakvik (Altavik Summit)** *(60°05'N, 69°47'W)* is a useful landmark.

209 **Caution**. — Payne Bay has deep water in its entrance but is **shoal** in its west part. A channel through the SW part of the bay and into Rivière Arnaud (Payne River) has been wire-swept to 16 feet (4.9 m).

210 **Tuvalik Bay**, between **Tuvalik Point** and **Pointe Savik (Point)**, is the north part of Payne Bay. **Natsik (Natsek) Islet** is 1 mile south of Tuvalik Point. **Nanuk (Nanook) Islet** *(60°02'N, 69°42'W)* is 0.8 mile SSE of Pointe Savik. **Agvik (Arvik) Island** *(60°01'N, 69°43'W)* and **Akunok (Akunak) Islet** lie on **shoal** ground further SW.

211 **Kyak Bay**, between Pointe Savik and **Cap Sarvak (Sarfak Point)** *(60°00'N, 69°47'W)*, dries completely at low water. **Napatak (Nappatak) Island** is the easternmost island of a group inside the mouth of Kyak Bay.

212 The **anchorage** just south of Pointe Savik has poor holding ground and is uncomfortable in cross-currents.

213 **Anchorage** can be found 0.6 mile west of Tuvalik Point in 8 fathoms (14.6 m), rock bottom with patches of mud. This is sheltered from the east only by **drying ledges** and is exposed to the south but the tidal streams here are less than at Pointe Savik.

214 The route into Tuvalik Bay is marked by two **leading beacon ranges**.

215 Each **beacon** is a fluorescent-orange trapezoid **daymark** with a black vertical stripe mounted on a square skeleton **tower**.

216 The pair on Pointe Savik, in line bearing 302°, lead into the entrance of Tuvalik Bay.

217 The beacons at the head of Tuvalik Bay, in line bearing 013°, lead to the anchorage.

218 A **drying flat** of mud and **boulders** lines the south side of Payne Bay as far west as **Pointe Entrance (Point)** *(59°58'N, 69°43'W)*.

*Chart 5352*

## Rivière Arnaud (Payne River)

219 **Rivière Arnaud (Payne River)** is entered between Pointe Entrance and Cap Sarvak. Rivière Arnaud is navigable by shallow-draught vessels for 35 miles but only the lower 11 miles have been sounded. The river broadens 6 miles upstream to form Bassin Payne (Basin); the settlement of Kangirsuk (Bellin or Payne Bay) is on the north shore 8 miles from the entrance.

220 **Caution**. — During large tides, **tidal streams** reach speeds of 10 knots in the mouth of Rivière Arnaud and 8.5 knots in Chenal Nakirtuq (Nakertok Narrows). Unpredictable **eddies** and **overfalls** form from the river entrance to the basin when these currents are at their strongest. These conditions are **dangerous** for small craft.

221 **Îlets Sitamat (Islands)**, the outermost with an elevation of 55 feet (17 m), are on the south side of the river 2 miles inside the entrance.

222 **Passe Mikittuq (Mikitok Narrows)** and **Chenal Nakirtuq (Nakertok Narrows)** run on each side of **Île Pikiulirjuakallak (Pikiyulik Island)** *(60°00'N, 69°55'W)*. Chenal Nakirtuq has been wire-swept to a depth of 20 feet (6.1 m); Passe Mikittuq has not been wire-swept and may have depths less than charted.

223 South of the track, **Récifs Malrok (Makok Reefs)**, between Chenal Nakirtuq and **Île Lodestone (Island)**, are on a **shoal** area with numerous **eddies** and **overfalls**. **Récif Lodestone (Reef)** lies on a wide **drying ledge** extending NW from Île Lodestone.

224 Very strong **tidal streams** run through the narrows; the time of transit must be carefully chosen. The survey ship *Algerine* steamed at 10.5 knots for 55 minutes abeam of Île Pikiulirjuakallak, stemming the flood stream, before being able to clear Chenal Nakirtuq.

225 **Bassin Payne (Basin)**, west of the narrows, has wide **drying ledges** around most of its shores. Depths in the central part are irregular and there are numerous **reefs** in the NW part. **Île Basking (Island)** is near the middle of Bassin Payne 3.6 miles west of Île Lodestone. **Pointe de l'Igloo (Point)** is on the north shore 1.5 miles NNW of Île Basking.

226 **Anse Kanik (Cove)** *(60°01'N, 70°01'W)* is on the north shore of Bassin Payne. An **isolated shoal** with a depth of 10 feet (3 m) is 0.9 mile SSW of the cove.

227 The route into Bassin Payne is marked by four **leading beacon ranges**.

228 Each **beacon** is a fluorescent-orange trapezoid **daymark** with a black vertical stripe mounted on a square skeleton **tower**.

229 The beacons on Pointe Entrance, in line bearing 241°, lead through Payne Bay to the entrance of Rivière Arnaud.

230 The beacons on Île Lodestone and an adjoining island, in line bearing 271°, lead through the entrance of Rivière Arnaud.

231 The beacons on one of the Îlets Sitamat and the mainland behind, in line bearing 298°, and a reciprocal pair on the north shore east of Anse Kanik, in line bearing 118°, mark the route through Chenal Nakirtuq.

232 Well-sheltered **anchorage** with good holding in 12 fathoms (22 m), mud bottom, can be found 0.5 mile SE of the *Hudson's Bay Company* store in Kangirsuk (Bellin or Payne Bay). The survey ship *Algerine* rode out gale force winds here with no difficulty.

233 Good **anchorage** can also be found on the south side of Bassin Payne. The **tidal stream** in the basin seldom exceeds 3 knots.

234 The village of **Kangirsuk (Bellin or Payne Bay)**, population 436 *(2001)*, is on the NW shore of Anse Kanik. Kangirsuk has a post office, nursing station and a police station. There are two retail stores and a coffee shop, as well as *Co-op* hotel accommodation. *Air Inuit* provides flights 7 days a week.

*Chart 5351*

235 **Kuglukvik (Kudloovik) Point**, 4 miles north of Pamiok Island *(previously described)*, is a group of islands on a **drying flat** attached to the mainland.

236 **Five Islands** *(60°11'N, 69°26'W)*, 7 miles NNE of Pamiok Point, lie in the NE approaches to Payne Bay. **Mont Sugar Loaf**, a **conspicuous** hill on the mainland 5 miles to the west, is 300 feet (91 m) high.

## NW part of Ungava Bay

*Chart 5300*

237 The NW coast of Ungava Bay between Five Islands *(60°11'N, 69°25'W)* and Cap (Cape) Hopes Advance, 54 miles to the north, is low. There are numerous wide **shoal** bays that show great expanses of **boulder-strewn flats** at low water. The land rises a mile or so inland to 200 or 300 feet (61 or 91 m) and farther inland the nearly flat terrain is broken only by a few rocky ridges less than 1,000 feet (305 m) high.

238 **Caution**. — Parts of this stretch have rocky islands close to shore. The water between them is so **shoal** that almost all of them are joined to the mainland and to each other at low water. The water stays **shallow** for a considerable distance outside the islands and the bottom is uneven. Any approach is **dangerous**.

*Charts 5450, 5300*

### Akpatok Island

239 **Akpatok Island** *(60°25'N, 68°08'W)*, 35 miles offshore in the NW part of Ungava Bay, is a bare limestone plateau split by deep ravines. From offshore the coast appears as a line of unbroken vertical cliffs 400 to 600 feet (122 to 183 m) high, except for a few miles along the NE coast where the shoreline is low and composed of shingle. The cliffs are pale yellow in summer, backed by the flat or gently rounded skyline of the interior plateau. Small patches of snow that remain in the deeper ravines all summer are **conspicuous** from seaward. Below the cliffs a **flat ledge** of limestone **rock** dries for 150 feet (46 m) from the high water mark. Most of the ledge ends abruptly in 12 or 18 feet (3.7 or 5.5 m) of water. A narrow shingle beach lines the base of the cliffs. At the mouths of the larger ravines the ledge and shingle beach give way to the muddy bottom of Ungava Bay. The coastal waters of Akpatok Island have not been sounded.

240 **Harp Cove** *(60°20'N, 67°57'W)*, between **Scree Point** and **Southeast Point** on the east side of Akpatok Island, appears from soundings to shelve gently downward from the shoreline. **Bell Cove** *(not named on the charts)* lies 2 miles west of Southeast Point; **Umiak Cove** *(not named on the charts)* is 2 miles farther SW.

241 **Clutterbuck Head** is the south point of the island. **Singer Point**, **Hell Point** *(not named on the charts)* and **D'Aeth Point** are the NW, NE and east points. **Northeast Cliff** is between Singer Point and Hell Point. **Central Hill** *(not named on the charts)*, 6 miles west of Scree Point, has an elevation of 927 feet (283 m).

242 **Caution**. — **Tidal streams** along the east and west coasts of Akpatok Island flow

SW when flooding and NE when ebbing. The maximum recorded rate was 3 to 4 knots in large tides.

243 **Caution**. — **Shoal spits** are reported to extend 0.2 mile from the north, east and south points of the island; there are also **tide rips** off these points. It is **dangerous** to approach the shore within 0.2 mile because of the **rock** ledges at the foot of the cliffs.

244 **Anchorage** can be found in 5 to 15 fathoms (9.1 to 27 m) within 0.4 mile of the cliffs. There is good holding but no shelter.

245 **Fresh water** is available from streams in the larger ravines around Akpotok Island.

*Chart 5300*

## Five Islands to Cap (Cape) Hopes Advance

246 The southernmost of **Plover Islands** *(60°18'N, 69°32'W)* lies 3 miles NW of Five Islands. Plover Islands is an extensive group of islets and rocks named for the large flocks of plovers and other birds seen here.

247 A **magnetic disturbance** has been reported 4 miles offshore from Plover Islands.

248 **Dry Bay** and **Baie De Rozière** lie 6 and 12 miles NNW of Plover Islands. An islet and an island are 5 and 11 miles offshore east of Dry Bay, and there is an islet 5 miles ESE of the north entrance point of Baie De Rozière.

249 **Ruisseau Garnier** is a river on the west shore 4 miles north of Baie De Rozière. **Île Guindon** *(60°44'N, 69°33'W)* is a low island 8 miles to the NNE.

250 **Eider Islands** are a labyrinth of islands and rocks 10 miles farther NNE. Large numbers of ducks nest here. **Aeeraktoo Island**, 9 miles to the NNW, is one of a group of low islands.

*Chart 5452*

251 The north end of a flat peninsula with a general elevation of 250 feet (76 m) ends in cliffs at **Cap (Cape) Hopes Advance** *(61°05'N, 69°33'W)*. This is the west entrance point of Ungava Bay.

252 *Cape Hopes Advance* **light** *(2560)* is near the NNE edge of the cape.

253 There are two cabins, a white building with a red roof and a helipad near the light structure; another cabin is near the shore 0.1 mile east of the light *(2003)*.

# Hudson Strait — South Shore
## Cap Hopes Advance to Pointe Taliruq (Nuvuc)




## General

*Chart 5450*

1 This chapter describes the south shore of Hudson Straight from Cap Hopes Advance (described in Chapter 1) to Pointe Taliruq (Nuvuc), 260 miles WNW.

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

2 **Caution**. — Many of the charts referred to in this chapter include areas that have not been surveyed or have not been surveyed to modern standards; many other areas show only soundings reported by ships crossing the area. Much of the charted information in offshore waters is of a reconnaissance nature.

## Diana Bay

*Chart 5452*

3 **Diana Bay** lies between Cap Hopes Advance and **Pointe Jean-Talon** *(61°06'N, 70°08'W)*, a bluff head 15 miles to the west. Diana Bay offers excellent shelter with good holding in several **anchorages** including Arvavik Bay, Theron Bay and Kamik Bay. The approaches are not difficult and Diana Bay is free of the shoal areas that line the west shores of Ungava Bay. The village of Quaqtaq (Koartac) is 2 miles SSW of Cap Hopes Advance.

4 **Historical note**. — Diana Bay is named after the steam whaler *Diana*, which was chartered by the Canadian Government for an expedition to Hudson Bay in 1897.

5 The land around Diana Bay is rolling and rocky. A few of the long hills on the east shore are 400 feet (122 m) high. The rock on the east side is sedimentary and crumbling; there are grassy plains between the hills. On the west side the rock is igneous; hills are 400 feet (122 m) to 1,000 feet (305 m) high.

6 The **tidal range** is less than that of Ungava Bay. The **tidal streams** in the mouth of Diana Bay and near Cap Hopes Advance are strong but in the south part of the bay the maximum rate is 2 knots.

7 The **weather** is more severe than that of the Ungava Bay coast to the south and there is more fog.

8 The average maximum thickness of winter **fast ice** in Diana Bay is 126 cm with a record thickness of 163 cm *(1973)*. The bay is usually ice-free from late July until mid-November.

## East side of Diana Bay

9 **Pointe Short (Point)** *(61°05'N, 69°37'W)* is the NW tip of Cap Hopes Advance. **Hearn Island** is 2 miles to the west. There is a 9-foot (2.7-m) **shoal** 0.3 mile SW of Pointe Short. A deep passage separates Hearn Island from the mainland. **Escarpement Eyrie** and **Little Lake Cove** are south of Pointe Short.

10 **Anchorage** can be found in the passage in 15 fathoms (27 m) 0.3 mile SE of Hearn Island but holding is poor.

11 **Caution**. — Strong **tidal streams** in the passage frequently cause **tide rips**. Northerly and westerly gales produce a heavy sea around the island.

12 **Mission Cove** *(61°03'N, 69°38'W)* is on the NE side of Diana Bay 1.5 miles SE of Hearn Island. Mission Cove is **not surveyed** but is reported to be deep. A **rock** that dries 29 feet (8.8 m) is in the mouth of the cove. The passage on the north side of the rock has a depth of 10 fathoms (18.3 m); on the south side there is 4 fathoms (7.3 m).

13 The village of **Quaqtaq (Koartac)** *(61°03'N, 69°38'W)*, population 305 *(2001)*, is at the head of Mission Cove. Quaqtaq has a post office, police station and a nursing station. There are 2 retail stores and a *Co-op* hotel in the village. *Air Inuit* provides flights 7 days a week.

14 A breakwater and a small-craft launching ramp have been constructed at Quaqtaq. The **breakwater** is 5.2 m high; it extends from the SW entrance point of the small river at the head of Mission Cove and protects the **landing beach** in front of the village. The launching **ramp** is on the SW side of a hill that forms the south side of Mission Cove.

15 A privately maintained **aeromarine radiobeacon** *(61°03'N, 69°38'W)* near the village broadcasts on 285 kHz with identification UHA (• • — • • • • • —).

16 From **Long Cove** *(61°02'N, 69°39'W)* to **Kinak Island**, 3 miles SSW, the coastline consists of a series of small narrow bays open to the NW. These bays are **not surveyed**. Small islands, **drying rocks** and **shoals** also trending NW lie up to 1 mile or more offshore.

17 **Hall Bay**, **not surveyed** but reported to be **shoal**, is on the SE shore of Diana Bay.

18 **Cap Jagged** is the NE end of a peninsula that forms the west side of Hall Bay. **Dog Island**, to the east, is connected to Cap Jagged by a **drying flat**. There is a **conspicuous rock cairn** on a peak of **Collines Jagged** on the peninsula west of Hall Bay.

19 A dark diagonal **fault** on **Cap Pain**, 2 miles SW of Cap Jagged, is **conspicuous** from the north.

20 A cluster of islands, **shoals** and **drying patches** extends 4 miles north from Cap Jagged with deep water between some of them. **Middleton Island** is the northernmost and **Mary Island** is the largest of these features.

## Central Islands in Diana Bay

21 **Diana Island** is the largest island in the bay; **North Head** *(61°02'N, 69°57'W)* and **Nuvugapik Point** are its north and NE points. **Taligok Point** and **Tulugak Point** are the SE and west points. A mesa-like **hill**, 699 feet (213 m) high, is **conspicuous** 2 miles SSE of Tulugak Point. There are three rock cairns on a ledge 0.7 mile SW of Taligok Point. **Berthe Cove** is on the east side of the island.

22 **Hannah Island** *(60°58'N, 69°55'W)*, with several rolling hills, and **Flat Island** lie east and SE of Diana Island. **La Petite Ile** is an islet off the east shore of Hannah Island.

23 **Anchorage** can be found 0.4 mile SW of Hannah Island.

24 **Eastern Passage** leads east of Diana and Hannah Islands to the head of Diana Bay. **Iceberg Shoal**, with a depth of 35 feet (10.7 m), lies near mid-channel 1.8 miles WNW of Middleton Island *(previously described)*.

25 Closer to Diana Island are **Pink Island**, **Taktuk Island** and **Mikoalat Island**.

26 **Caution**. — There is a **drying patch** of **rock** midway between Hannah Island and Mikoalat Island.

27 **Opingivik Island**, **Tiny Island** and **Fingernail Island** are joined to the south end of Diana Island by **drying flats**.

## West side of Diana Bay

28 **Pointe Duchesnau** *(61°04'N, 70°07'W)* and **Tuvak Bay**, **not surveyed**, lie south and SSE of Pointe Jean-Talon on the west side of the entrance to Diana Bay.

29 **Ford Island** lies between Pointe Duchesnau and Diana Island. **Kingnektak Island**, **Imnak Island** and **Smooth Island**, all joined by **drying flats**, are between Ford Island and the mainland. **Ekkik Cove**, on the west shore, dries at low water.

30 **Anchorage** can be found south of Ford Island with good holding, weak tidal streams and shelter much better than that off Hearn Island.

31 **Waterfall Cove** *(60°58'N, 70°07'W)*, with a **waterfall** on its west shore, offers sheltered **anchorage** for small vessels in 10 fathoms (18.3 m). There is a **drying patch** of **rock** to the north of the entrance.

32 **Solomon Island**, **Slim Island**, **Paw Island** and **Claw Rock** lie off the west shore south of Ford Island; **Western Passage** leads between these islands and Diana Island.

33 **Caution**. — A **rock** with a depth of 3 feet (0.9 m) lies between Solomon and Slim Islands.

*Chart 5464*

## SW side of Diana Bay

34 **Arvavik Bay** is on the SW shore of Diana Bay and is sheltered to the east by **Narrow Island** *(60°54'N, 70°03'W)*. **Rivière Latourette** and **Ruisseau Kogaluk** flow over **drying flats** at the head of Arvavik Bay.

35 Arvavik Bay offers **anchorage** with good holding in 13 fathoms (24 m), clay. The anchorage is sheltered but there is limited swinging room.

36 The best approach to Arvavik Bay is from the north; **Baldpate Rock**, which dries 5 feet (1.5 m), obstructs the channel SW of Narrow Island.

37 **Point Islands** *(60°52'N, 70°03'W)*, south of Narrow Island, extend from **Pointe Théron** to form the north side of **Theron Bay**. The bay is deep and free of hazards. The hills around the bay are 500 feet (152 m) high; a stream enters the NW part through a grassy valley.

38 Excellent **anchorage** with good holding can be found in the NW part of Theron Bay in 3 to 12 fathoms (5.5 to 22 m). Vessels have ridden out severe winds, including easterlies, in this anchorage without difficulty.

## South part of Diana Bay

39 **Okivik Island** *(60°53'N, 69°59'W)*, **Papik Island** and **Round Rocks Island**, in the middle of the south part of Diana Bay, obstruct the south end of Eastern Passage.

40 **Caution**. — A **drying patch** of **rock** is close SW and a **reef** with a depth of 14 feet (4.3 m) lies 0.4 mile NNE of Round Rocks Island.

41 **Harlequin Rock** is on a **shoal** area that extends 0.5 mile north of Okivik Island; **Puffin Rock** is 1 mile to the east.

42 **Misfortune Shoals**, least depth 2 fathoms (3.7 m), lie midway between Round Rocks Island and **Ayuak Island**, 1.3 miles to the ENE.

43 **Igloo Island (Île Illutalialuk)** is at the head of Diana Bay. The NE part of the island is separated from the mainland only at high water springs. **(Pointe) Grave Point** is the south end of the island. **West Mussel Island** and **East Mussel Island** lie off the NW shore of Igloo Island.

44 **Caution**. — There is an 8-foot (2.4-m) **shoal** 0.5 mile WSW of Grave Point.

45 **Kamik Bay**, lying around the SW, south and SE sides of Igloo Island, is entered between **Pointe Buteo** *(60°51'N, 70°00'W)* and Igloo Island.

46 **Rivière Merganser** enters the bay south of Pointe Buteo.

47 **Heel Cove** is the south end of Kamik Bay; **shoal spits** extend from its west and SW sides. **Ankle Passage** leads SE of Grave Point to the inner basin of Kamik Bay.

48 **Caution**. — A **boulder shoal** with a depth of 1 foot (0.3 m) lies in the middle of the basin.

49 **Lake Cove (Baie Tasiujaaluk)** is the NE part of Kamik Bay.

50 Well-sheltered **anchorage** in 10 to 17 fathoms (18.3 to 31 m) can be found in Heel Cove.

51 Small craft can find protected **anchorage**, in 12 fathoms (22 m), 0.8 mile ENE of Grave Point.

# Diana Bay to Wakeham Bay

*Chart 5450*

52 The inshore waters between Diana Bay and Wakeham Bay are **not surveyed**. The coast between Pointe Jean-Talon *(61°06'N, 70°08'W)* at the west entrance point of Diana Bay and Burgoyne Bay, 40 miles to the WNW, is rugged with hills rising directly from the water to heights of 700 to 1,000 feet (213 to 305 m). From Burgoyne Bay to Cape Prince of Wales, 20 miles to the north, the coast is comparatively low and the land behind it is seldom more than 500 feet (152 m) high.

53 **Caution**. —The bays along this stretch are **shoal**; **rocks**, **shoals**, **reefs** and strong **tidal streams** make the coastal waters **dangerous** to navigate.

54 **Baie Héricart** *(61°03'N, 70°26'W)* is 8 miles west of Pointe Jean-Talon. **Pointe de Tracy**, rising steeply to 1,000 feet (305 m), is a **conspicuous headland** 8 miles farther west. There is reported to be a good landlocked **anchorage** in the vicinity.

55 **Burgoyne Bay** is divided into two arms by a low peninsula.

56 Bergoyne Bay is reported to offer good **anchorage** but is exposed to northerly winds.

57 **Caution**. — A **rock** 5 miles offshore is 6 feet (1.8 m) high. A group of islands and **rocks**, including one which dries 18 feet (5.5 m), lie 5 miles north of the bay.

58 **Whitley Bay** *(61°22'N, 71°42'W)* **dries** completely. Eider ducks in the thousands are reported to feed on the boulder-strewn mud flats.

59 **Caution**. — **Tidal streams** rush through a narrows in the bay at 7 or 8 knots, causing powerful **rapids** at times.

60 **Joy Bay** is a **drying area** between **Pointe Frontenac** *(61°25'N, 71°34'W)* and **Tuttle Point**, 8 miles north *(both points are unnamed on Chart 5450)*. The bay has a low, broken shoreline backed by hills 300 to 700 feet (91 to 213 m) high.

61 **Caution**. — There are rocky islands in the bay and **dangerous rocks** near the middle of the bay.

*Chart 5365*

62 **Stupart Bay** lies between Tuttle Point and **Cap Neptune (Head)**, 1.5 miles NE. The bay is only partly sounded but is reported to have depths of 3 to 11 fathoms (5.5 to 20 m) with **shoal** water extending 0.2 mile from its shores. The mouth of the bay is obstructed by a **reef** reaching from the south side of the bay to within 0.3 mile of a **submerged rock** off the NE side of the entrance. This is the extent of sounding coverage.

63 **Caution**. — There are reported to be **uncharted** islets 1.6 miles ESE of the head. **Shoal water** and **drying patches** lie up to 1.5 miles ESE and east of Cap Neptune. **Drying patches** extend 0.5 mile north of an island 1.8 miles ENE of Neptune Head.

64 **Anchorage** for small vessels can be found in 24 feet (7.3 m) just inside the entrance to the cove in the north part of Stupart Bay. This anchorage provides good shelter except from south and SE winds.

65 **Cape Prince of Wales (Cap du Prince-de-Galles)** *(61°36'N, 71°31'W)* and the land nearby are low. Higher land lies 2 miles to the west.

66 **Caution**. — An islet on a **drying patch** surrounded by a large **shoal** area lies 3.6 miles east of the cape.

67 **Caution**. — Extreme care is necessary when navigating near Cape Prince of Wales because of the outlying **dangers** and inconspicuous shoreline.

68 **Doctor Island** is 1 mile offshore 3 miles NW of Cape Prince of Wales.

69 **Caution**. — There are several islets to the SE and to the west on the jagged **rock** ledges which surround the island. The island is difficult to distinguish against the high dark background of the mainland. A **rock** with a depth of 2 feet (0.6 m) is 1 mile NNW of Doctor Island.

70 **Historical note**. — Doctor Island is named after Dr. McDonald, surgeon aboard *Diana* for the Hudson Bay expedition of 1897.

71 **Uglik Islands** *(61°41'N, 71°41'W)* are 2 miles WNW of Doctor Island.

72 **Caution**. — **Reefs** extend from the south and east sides of the inner Uglik Island and from the SE point of the outer island.

73 Small craft can find shelter from all but westerly winds in a small cove on the NW side of the inner Uglik Island. A cove on the mainland south of the inner Uglik Island is protected to north and NE by a **drying spit**. This cove offers shelter for small craft from all except NW winds.

*Chart 5390*

## Wakeham Bay and Approaches

74 **Wakeham Bay** *(61°37'N, 72°00'W)* is a deep fiord, 14 miles long, that trends SW through rugged rocky hills. The village of Kangiqsujuaq (Maricourt or Wakeham) is on the east shore 6 miles south of the entrance.

75 **Cap la Boule (La Boule)**, the SE entrance point of Wakeham Bay, appears to be a high prominent island from NE. A low neck of marshy land joins Cap la Boule to a perpendicular cliff to the SE. This cliff, which sometimes shows red and other colours, has a white fault cutting diagonally across its face. **Boat Cove** is a small cove with sand beaches on the north side of Cap la Boule. The cove offers good shelter for small craft except in NW winds but there is usually a heavy swell. **Nannuk Rock**, 0.3 mile off the north shore of Cap la Boule, dries 8 feet (2.4 m).

76 **Caution**. — Nannuk Rock has deep water on the south and east sides but **shoal** water extends NW from the rock for 0.4 mile.

77 **Walrus Island** *(61°43'N, 71°51'W)* is 2 miles ENE of Cap la Boule.

78 **Caution**. — A **reef** with 2 **drying spots** extends 0.7 mile WSW of Walrus Island. An **isolated rock** with a depth of 3 feet (0.9 m) lies midway between the island and the mainland shore to the south.

79 **Daryl Rock** *(61°45'N, 71°55'W)* and **Pelican Rock** are **isolated drying rock**s 2 miles north and 3 miles NW of Cap la Boule. There is a **rock** submerged 46 feet (14 m) 3.2 miles east of Daryl Rock; a **rock** submerged 48 feet (14.6 m) is 0.5 mile north of Pelican Rock.

80 The west end of Cap la Boule in line bearing 200° with the east tangent of Pointe Nichols leads 0.25 mile west of Daryl Rock; these points slightly open leads between Daryl and Pelican Rocks.

81 **Caution**. — Do not attempt to pass between Daryl Rock and Pelican Rock in restricted visibility until they both have been positively

identified on radar. The **tidal stream** may set a vessel on either reef during the 6.5-mile run from Wales Island.

82 The NW entrance point *(61°42'N, 72°00'W)* of Wakeham Bay is a remarkable perpendicular cliff rising over 1,200 feet (366 m) from the water. A low but **conspicuous** rounded **ridge** slopes gently from the cliff to a sharp point 0.2 mile north. This point is a useful **landmark** if the cliff tops are obscured by clouds.

83 **Berthé Islet**, only 1 foot (0.3 m) high, lies 1 mile NNW of the NW entrance point.

84 **Pointe Nichols (Point)** *(61°40'N, 71°59'W)* is on the west side of Wakeham Bay 3 miles inside the entrance. **Pointe Ford (Point)** is on the east side, 4 miles to the SSW. **Shoal water** extends 0.2 mile NNW of Pointe Ford.

85 The village of **Kangiqsujuaq (Maricourt or Wakeham)** *(61°36'N, 71°57'W)*, population 536 *(2001)*, is 1.6 miles ENE of Pointe Ford on the east shore of a bight with sandy beaches. There is a post office, nursing station and a police station. The community has two retail stores and a bakery. Hotel accommodations are available and *Air Inuit* provides flights seven days a week.

86 Two **breakwaters** and a beach access **ramp** have been constructed 1 mile north of the community. The breakwaters form a well-sheltered basin for small boats and landing craft; the entrance to the basin is at the SW corner of the breakwaters and the ramp is at the NE corner of the basin.

87 **The Narrows**, near the head of the bay, has a mid-channel depth of 7 fathoms (12.8 m) opposite a **drying boulder spit** extending out from the south shore.

88 **Caution**. — This is the **shoalest** part of the bay and **tidal streams** here are strong.

89 **Rivière Wakeham (River)** flows into the basin at the head of the bay over a wide **boulder**-strewn **drying flat**. Strong squalls from the surrounding hills are common in the basin.

90 **Anchorage** can be found 0.4 mile off the village in 30 fathoms (55 m) with good holding. The anchorage is sheltered from swell but strong winds may be experienced.

91 Small vessels can find **anchorage** in 20 fathoms (37 m) in the small bay on the south side of Cap la Boule. The bay is sheltered by the surrounding high cliffs and is free of tidal streams and the associated dangers of quickly moving ice.

92 **Anchorage** can also be found 1.5 miles west of Pointe Ford inside the 20-fathom (37 m) line, south of the three islets, off the north shore.

93 Local fishing vessels sometimes land at high water in the southernmost stream south of the village or on the gravel strip at the high water line.

## Wakeham Bay to Douglas Harbour

94 There is a **drying cove** 1 mile NNW of Berthé Islet *(previously described)*. The cove has a beach at the high tide mark, suitable for landing small craft, just inside the SE entrance.

### Fisher Bay

95 **Fisher Bay** *(61°47'N, 72°08'W)* is 4 miles NW of Wakeham Bay. Although its anchorage area is small it is an excellent harbour.

96 **Cap La Potherie**, the point on the north side of Fisher Bay, is rounded and 200 feet (61 m) high. When approaching Fisher Bay from offshore, this point and the point on the south side of the entrance are low compared with the greater heights in this area. **Pointe Cantley (Point)** extends from the west side of Fisher Bay and divides the bay in two. Most of the NW arm of Fisher Bay dries.

97 **Drying banks** of sand and **boulders** surround **Parsons Island** and **Chalmers Island** in the south arm of Fisher Bay. These islands are joined to the mainland at low water by **boulder** and gravel ridges.

98 **Caution**. — Strong **tidal streams** run through the passages between Parsons and Chalmers Islands and between the islands and the mainland.

99 **Shepherd Island** *(61°46'N, 72°11'W)*, between Chalmers Island and Pointe Cantley, is small but easily recognized. The channel between Shepherd Island and Chalmers Island has a least mid-channel depth of 6 fathoms (11 m) and a width between the 5-fathom (9.1 m) contour lines of 0.1 mile.

100 Landlocked **anchorage** with good holding in 5 to 12 fathoms (9.1 to 22 m), mud, can be found in the basin west of Chalmers Island. Violent squalls from the high hills may be experienced but there is little danger of dragging. Fresh water is available from a stream draining a beautiful clear lake to the south between **Mont (Mount) Albert-Low** and **Mont (Mount) Young**.

101 A strong **tidal stream** flows NW out of the passage between Chalmers and Parsons Islands on the ebb tide.

102 **Fisher Rock**, midway between Cap La Potherie and Pointe Cantley, covers only at high water spring tides. Depths of less than 10 feet (3 m) extend 0.3 mile south of the rock and a ridge with depths less than 6 fathoms (11 m) joins the rock to Pointe Cantley.

103 Temporary **anchorage** with shelter from all but easterly winds can be found under the lee of Cap La Potherie.

## Fisher Bay to Douglas Harbour

104 **Wales Island** *(61°52'N, 72°03'W)* has steep sides and although it has no pronounced peaks it can be recognized by the smaller islands extending to the NNW. **Drying patches** and **shoal** water reach 1.3 miles off the SW shore of Wales Island.

105 *Wales Island* **light** *(2558)* is at the east end of the island.

*Chart 5365*

106 A wide **drying bank** encompassing several islets extends 1 mile north of the west end of Wales Island. A narrow channel with a depth of 8 feet (2.4 m) separates this bank from a **bank** to the NW surrounding **Wivanhoe Island** *(61°55'N, 72°08'W)*. An **isolated rock** with a depth of 27 feet (8.2 m) lies 1.2 miles east of Wivanhoe Island. There is an **isolated** 6-fathom (11 m) **shoal** 1 mile SW of Wivanhoe Island; **Wales Rock** is at the outer end of the **reefs** 0.5 mile to the north.

*Chart 5390*

107 **Anchorage** with good holding in 20 fathoms (37 m), blue clay, and shelter from winds from west to north can be found in the lee of Wales Island.

108 **Wales Sound** lies between Wales Island and the mainland.

109 **Woman Islands** *(61°50'N, 72°09'W)* are surrounded by **shoal** water. **Isolated rocks** with depths of 35, 22 and 11 feet (10.7, 6.7 and 3.4 m) are 1.8 and 1.4 miles SE and 1.2 miles east. The channel through Wales Sound leads east of Woman Islands.

110 **Pinnacle Bluff**, on the mainland SSW of Woman Islands, makes an excellent **landmark**; it rises directly from the sea and from close eastward appears to be a sharp pinnacle; from farther out it looks more conical.

111 **Pointe Gillam (Point)** is a small peninsula 2.5 miles NNW of Pinnacle Bluff.

112 **Dark Island** *(61°53'N, 72°10'W)*, at the NW end of Wales Sound, is steep with two summits. The eastern summit rises from the sea to a height of 400 feet (122 m). The **island** has a very dark appearance and is **conspicuous** from south of Wales Island. An islet and **reefs** lie off the NW and north sides of Dark Island and an **isolated rock** with a depth of 33 feet (10.1 m) is 1.1 miles to the WNW.

113 **Caution**. — The **tidal streams** in Wales Sound flow strongly at both ebb and flood. **Tide rips** caused by opposing winds are **dangerous** to small craft.

*Chart 5365*

## Approaches to Douglas Harbour

### *Off-lying islands*

114 **King George Archipelago** is a chain of islands in the approaches to Douglas Harbour.

115 **Caution**. — There are always swift **tidal streams** through this chain.

116 **Peak Island** *(61°59'N, 72°11'W)*, the easternmost of the islands, is a **conspicuous landmark** rising symmetrically to a sharply defined summit with an elevation of 330 feet (101 m). Its NW end rises steeply from deep water and heavy **tide rips** occur off the north part of the island. There is an **isolated** 50-foot (15.2 m) depth 2 miles north of Peak Island. After an easterly gale there is a heavy swell here.

117 **Double Island**, with twin summits, is separated from Peak Island by a channel. The channel has an **isolated** 40-foot (12.2 m) **shoal** in the middle. A narrow ring of **shoal** water almost surrounds Double Island. There is an unnamed island NNW of Double Island.

*Chart 5391*

118 **Smooth Island** *(62°00'N, 72°17'W)* is surrounded by **drying area**s and **shoal** water. Islets and **reefs** extend up to 0.5 mile off its north and NW shores.

119 Local small craft have used a cove in the NW part of the island as an **anchorage**. The basin in the cove is landlocked at low water.

120 **Maiden Island**, the largest in the archipelago, is the next island to the west; it has many hills. A **drying ridge** connects low **Cairn Islet** to a **boulder**-filled **drying bay** in the SE part of Maiden Island. Islets and **shoal** water extend more than halfway across the channel between Maiden Island and Smooth Island. **Bold Point** *(62°02'N, 72°28'W)*, a perpendicular **cliff** at the west end of Maiden Island, is a useful **landmark** for making Douglas Harbour.

121 **Anchorage** with shelter from NE to NW winds and good holding can be found near the south or east sides of Maiden Island.

122 The western island of **Pinnacle Islands**, north of Maiden Island, rises to a **conspicuous summit** and is joined by **reefs** and **shoal** water to the SE Pinnacle Island. The NE island of this group is a prominent round islet separated from the western island by a narrow passage with a depth of 2 fathoms (3.7 m). There are **drying patches** and depths of 39 and 40 feet (11.9 and 12.2 m) near mid-channel between Maiden Island and Pinnacle Islands.

123 **Saddle Island** *(62°07'N, 72°27'W)*, named for its appearance from the SE and NW, is 2.4 miles north of Pinnacle Islands. **Reefs** and **shoal** water extend up to 0.2 mile off its

south and east shores and there are islets on a **reef** 0.3 mile to the west.

124 **Flat Island** is 1 mile NNW of Saddle Island; a **drying patch** lies midway between these two islands.

125 **King George Sound** runs between King George Archipelago and the mainland. The mainland coast has rocky shores rising abruptly to 400 to 900 feet (122 to 274 m) and backed by hills of 1,500 feet (457 m) and more.

126 **Middle Island** *(61°57'N, 72°24'W)*, near the middle of King George Sound, has **shoal** water extending 1 mile to the ESE with a **drying patch** near the outer end. **Isolated rocks** 0.7 mile NW and up to 1.7 miles ESE of the island have depths of 3 to 6 fathoms (5.5 to 11 m).

127 **Cleft Island** *(61°57'N, 72°31'W)*, 1.5 miles east of the south entrance point of Douglas Harbour, is split by two fissures forming three summits; it is a good mark for approaching the harbour. The summit of Cleft Island *(61°57'N, 72°31'W)* bearing 270° in line with the north tangent of Middle Island leads 1 mile north of Wales Rock.

128 There is a cluster of small rocky islets on a **drying patch** off the mainland shore west of Maiden Island; an **isolated rock** with 49 feet (14.9 m) over it lies near the middle of the sound 2 miles ESE of these islets.

### Douglas Harbour

129 **Douglas Harbour** *(61°58'N, 72°35'W)*, on the SW side of King George Sound, offers good well-sheltered **anchorage**. There is no settlement here. The harbour, which penetrates more than 10 miles inland, divides into two arms 5 miles inside the entrance. Both arms run between towering rocky hills with tumbling cataracts but the SW arm is more grand and severe.

130 The south entrance point of Douglas Harbour is low with scattered rocky hills; the north entrance point is steeper and higher. **Entrance Island**, 0.2 mile off the north entrance point, is joined to the point by a **drying boulder flat**. **Shoal water** extends up to 0.2 mile into the entrance channel. An **isolated rock** with a depth of 13 feet (4 m) lies 0.7 mile ENE of Entrance Island.

131 **Douglas Islet** and **Douglas Rock** are in the middle of the harbour entrance. There is a 34-foot (10.4-m) **shoal** 0.4 mile off the north shore 1.3 miles inside the entrance. An **islet** on the east shore, at the edge of the **drying foreshore** 0.5 mile inside the entrance, is 67 feet (20 m) high and makes a good **landmark**. There are two **conspicuous** pink rocky **bluffs** over 400 feet (122 m) high on the east side 1.5 miles south of the islet.

132 **The Helmet** *(61°54'N, 72°37'W)* is a **conspicuous** sharp-pointed **hill** on the east shore 4 miles south of the entrance.

133 The entrance to **Southeast Arm**, almost obstructed by **shoals**, is SW of The Helmet. Wide, **boulder**-covered **tidal flats** line most of the east side of Southeast Arm. A 10-fathom (18.3 m) basin near the head is separated from the outer part of the arm by **shoal water** and there is a **drying flat** at the head.

134 **Southwest Arm** is deeper than the other and is free of mid-channel dangers. A small river empties into the head through a terrace, 100 feet (30 m) high. The terrace extends 1 mile inland from the head.

135 **Anchorage** with good holding can be found almost anywhere in Douglas Harbour. **Fresh water** can be taken from a stream on the east shore 1 mile north of The Helmet; however, SW gales can blow with great violence out of Southwest Arm making the anchorage near the stream unsafe. A good **anchorage** can be found 2 miles NNW of The Helmet, in 30 fathoms (55 m), under the high west shore.

136 Douglas Harbour can be entered either north or south of Douglas Islet but at high water, when Douglas Rock is covered, the south channel is better.

## Douglas Harbour to Deception Bay

*Charts 5365, 5450*

### Foul Bay

137 **Promontoire De Martigny** *(62°07'N, 72°37'W)* is a prominent and imposing headland 10 miles north of the entrance to King George Sound. It has a high, sharply defined steep face but falls away to a low valley on its mainland side.

138 **Foul Bay**, between Promontoire De Martigny and **Pointe Radisson**, 20 miles to the NW, is named for its many islets, **rocks** and **shoals**. A large stream enters the bay 3 miles west of the promontory through a **boulder** foreshore that skirts the whole of Foul Bay. A narrow channel between a low unnamed island in the NW part of the bay and the foreshore does not dry and offers good sheltered **anchorage** for small craft.

139 **Davies Island** *(62°14'N, 72°50'W)*, 300 feet (91 m) tall at its west end, and **Weggs Island**, 7 miles to the NW, are both high and prominent. There are steep cliffs on the north side of Weggs Island.

*Chart 5450*

140 **Outer Island**, bare and yellow, is 9 miles NW of Weggs Island. It is steep-to on its east side but **dangerous rocks** lie SE and NW.

141 **Cap de Nouvelle-France** *(62°28'N, 73°42'W)* is 17 miles NW of Pointe Radisson. It rises abruptly to a height of 600 feet (183 m) and is **conspicuous** from east and west. There is a high perpendicular cliff just west of the cape and farther west there is a distinct summit.

142 **Caution**. — A 46-foot (14 m) **shoal** lies 6 miles offshore 15 miles WSW of Cap de Nouvelle-France.

143 **Charles Island** *(62°39'N, 74°20'W)*, 10 miles NW of Cap de Nouvelle-France, is uninhabited and bare. The east part of the island is high and prominent on the north and east sides, rising from deep water to 200 to 600 feet (61 to 183 m). The west part of the island ends in a flat boulder point 2 feet (0.6 m) high and is surrounded by a **boulder bank**. The 20-fathom (37 m) line, in contrast to the NE shore, lies 3 miles off the south coast of the island. **Cape Moses Oates** is a prominent headland at the east end of the island.

144 *Charles Island West End* **light** *(2556)* is on the low west end of the island.

145 **Foreman Island** *(not named on the chart)* is a small narrow island close south of the east end of Charles Island. Foreman Island is 80 feet (24 m) high and has three islets off the east end.

146 **Charles Inlet** *(62°35'N, 72°00'W)*, between Foreman Island and Charles Island, is 0.35 mile wide at its deep east end. The inlet narrows to the west to 0.15 mile and ends in a wide **bar** with a depth of 1 fathom (1.8 m).

147 **Anchorage** in 10 to 18 fathoms (18.3 to 33 m), sand, can be found in the inlet with good shelter from all but easterly gales and swells. The anchorage area is 1 mile long and 0.15 to 0.3 mile wide.

148 **Charles Bay**, on the north shore of Charles Island, offers **anchorage** with protection from southerly winds.

149 There is a **magnetic anomaly** north of Charles Island.

150 West of Cap de Nouvelle-France the coast rises to 500 feet (152 m) inland and there are sandy beaches; the coast becomes higher and steep again 7 miles east of Deception Bay.

*Chart 5457*

## Deception Bay

151 **Deception Bay** *(62°15'N, 74°46'W)* is 9 miles long from the entrance to the wide **drying flats** at the mouth of **Rivière Deception**. The shores of the bay rise steeply from the water on the west side and more gradually on the east.

152 A **tidal stream** flows 270° at 1.7 knots 9 to 11 miles off the entrance and a westerly set has been reported in the inner part of the bay.

153 **Pointe Rouge** *(62°15'N, 74°42'W)* is the east entrance point of Deception Bay. **Arctic Island** is in the middle of the entrance between Pointe Rouge and **Neptune Island**.

154 *Arctic Island* **light** *(2555)* is on the north side of Arctic island.

155 **False Passage** is a wide **drying bank** that separates Neptune Island from the mainland to the west. **Shoal water** less than 12 m deep extends up to 0.6 mile north and east of Neptune Island and extends 2 miles NNE from Arctic Island. An **isolated rock** with a depth of 9.1 m lies in mid-channel 0.6 mile NE of Arctic Island.

156 **East Channel** runs between Pointe Rouge and Arctic Island. **Main Channel** leads west of Arctic Island.

157 **Pointe Noire** *(62°13'N, 74°45'W)*, dark and 11 metres high, is on the east shore 2 miles SSE of Arctic Island. **Black Rock**, which dries, and **Channel Rock**, with a depth of 2.1 m, lie 0.2 mile SW and 0.5 mile SSE of Pointe Noire.

158 **False Cove** is on the west shore south of False Passage. **Rocher Tulugarnaq** is in the mouth of False Cove; **Mont de la Table** rises to the south.

159 **Moosehead Island** is three islets surrounded by **drying patches** and **shoal** water off the east shore of the bay 1.3 miles SSE of Pointe Noire. **Île Qikirtaapik** lies off the west shore of the bay 0.8 mile SSW of Moosehead Island.

**ENTRANCE TO DECEPTION BAY**



160 **Careenage Arm** is an inlet on the SW shore of Deception Bay; **Pointe Théron** *(62°09'N, 74°43'W)* is its east entrance point.

161 **Anchorage** can be found in Careenage Arm in 20 m, mud; also at the head of Deception Bay and SE of Moosehead Island in 22 m.

162 An ore storage **warehouse** on the SW shore of Deception Bay, 1 mile SE of Pointe Théron, is **conspicuous**. There is an ore loading **wharf** 137 m to the north of the warehouse and **oil tanks** to the south. The wharf consists of two gravel-filled steel cells, faced with fenders, (76 m) apart. Depths alongside range from 11 to 13.4 m. There is a mooring bollard with a capstan on the shore north of the wharf and another at the north end of the warehouse. A mooring bollard is near the south end of the warehouse.

163 Two **leading beacon ranges** mark the route to the wharf. The **beacons** are fluorescent-orange **daymarks**, each with a black vertical stripe, shown from square skeleton **towers**.

164 The pair of beacons WSW of Moosehead Island on the west shore lead through Main Channel on a bearing of 174°.

165 The second pair near the head of the bay on the west shore, in line bearing 142°, lead from the intersection with the first range towards the wharf.

166 **Plage du Bombardier**, 3.4 miles SE of the ore wharf, is the **landing beach** on the south shore at the head of the bay. There is a sealift wharf here and a dispersal area with a large shed. Four abandoned radio **towers** are all that remain of the former settlement of **Déception**.

167 There is no permanent settlement at Deception Bay; the mine and its administration and housing facilities are some 100 kilometres to the SE by gravel road. A small number of mine employees, when needed at the ore storage and loading facility, live in trailers parked on the north side of the warehouse.

168 The mine complex is connected to the harbour facilities by telephone. In emergencies, the staff at the mine can handle mechanical repairs, supply food and water and provide medical attention. The reception office at the mine can arrange air transportation.

## Deception Bay to Cap Wolstenholme

*Chart 5450*

### Deception Bay to Sugluk Inlet

169 Between Deception Bay *(62°15'N, 74°46'W)* and Sugluk Inlet, 21 miles to the west, the coast is high and generally steep. **Promontoire Maurepas**, at the east part, rises to almost 2,000 feet (610 m). **Baie Nanuttuvik** *(62°15'N, 75°06'W) (not named on the chart)* dries almost completely. **Promontoire Pontchartrain**, further west, *(not named on the chart)* is a little less steep and has areas of low land and **drying flats** in front.

*Chart 5458*

170 **Cap Daulat** *(62°18'N, 75°25'W)* and **Cap du Long-Sault** are the entrance points to **East Cove**. The cove has steep shores but has **drying flats** along its west side and at its head.

171 A deep ice-filled **crevice** 1.5 miles SSW of Cap du Long-Sault shows as a **conspicuous** white mark.

172 **Cap Valets** is 3.5 miles SW of Cap du Long-Sault. **Ford Channel**, with a least depth of 2 feet (0.6 m), separates Cap Valets from **Sugluk Island**. **Shoal** depths under 6 fathoms (11 m) extend 0.5 mile NE and 0.3 mile east of Sugluk Island and a **rock** with 29 feet (8.8 m) over it lies 0.5 mile off its NW shore. A **bar** with a least depth of 34 feet (10.4 m) in mid-channel lies across the mouth of Sugluk Inlet abreast of Sugluk Island.

173 **Le Dôme** is 5 miles west of Sugluk Island. It is a prominent **landmark** with a steep cliff 500 feet (152 m) high.

### Sugluk Inlet

174 The entrance to **Sugluk Inlet** *(62°16'N, 75°32'W)*, between Cap du Long-Sault and Sugluk Island, is easily recognized by a low part in the coast with Sugluk Island in the middle of the dip. The land around Sugluk Inlet is not as high and rugged as most other inlets in Hudson Strait. There is considerable grass and moss and the hills are smooth and rounded. Parts of the shores are lined with **drying flats** of sand and **boulders**.

175 **Pointe Niaqunnguut** *(62°14'N, 75°37'W)* is on the SE shore 5 miles from the entrance and is the most prominent **landmark** in the inlet. **Pointe Tikiraassiaq** and **Cap Aupartuapik**, farther up the inlet, are both low.

176 The village of **Salluit (Sugluk)**, population 1,072 *(2001)*, is on the shores of a small cove on the SE shore of the inlet 6 miles from the entrance. Salluit has a post office, police station and a health centre with a doctor and a dentist. There are a variety of retail stores. Hotel accommodations are available. *Air Inuit* provides flights seven days a week.

176.1 Three breakwaters at the west side of the cove provide shelter for a landing ramp and a small-craft harbour. The entrance has privately maintained navigation lights.

177 **The Bar**, which dries except for a narrow channel 4 fathoms (7.3 m) deep, protects **Sugluk Basin** at the head of the inlet. Two rivers flow into the basin through extensive

**DECEPTION BAY**
STORAGE FACILITY AND WHARF
QUAIETINSTALLATIONSD'ENTREPOSAGE

**drying flats**; the SE of these is said to be navigable by small craft for 10 miles to the head of tidewater.

178 The best **anchorage** is 0.5 mile east of The Bar in 30 fathoms (55 m), mud, opposite a prominent cliff on the south shore.

179 An **anchorage** for smaller vessels is in the SE part of Ford Channel in 10 to 15 fathoms (18 to 27 m), mud. Protection is good from all but NE gales.

180 Ships serving the settlement usually find **anchorage** off the cove in 30 fathoms (55 m), mud; but the holding here is poor.

*Chart 5450*

## Sugluk Inlet to Erik Cove

181 The coast between Sugluk Inlet *(62°16'N, 75°32'W)* and Erik Cove, 54 miles to the WNW, is comparatively low for the first 10 miles but then rises to steep granite cliffs 1,500 to 2,000 feet (457 to 610 m) high. Valleys alternate with bluffs and coves are numerous but there is little shelter except from offshore winds. There are few distinctive features in this stretch and with snow on the ground it is difficult to pick out the coves. Depths of 100 fathoms (183 m) are found within 1 mile of the coast but the inshore area is **not surveyed**.

182 **Caution**. — A current flows SE along this shore with an appreciable set into the bight west of Sugluk Inlet.

183 **Kugluk Cove** *(62°20'N, 76°00'W)*, much used by Inuit when travelling up and down this coast, has high steep shores and deep water with poor holding ground.

184 **Caution**. — Onshore **winds** bring a swell and offshore winds at times blow out of the cove with hurricane force, making the cove unsafe.

185 **Cap Hébert** is the west entrance point of an unnamed cove west of Kugluk Cove. **Cap Tavernier** *(not named on the chart)*, separating the two coves, has a small summit near its end.

186 **Promontoire Colbert**, 30 miles WNW of Kugluk Cove, rises steeply to over 1,200 feet (366 m).

*Chart 5412*

187 The entrance to **Erik Cove** *(62°33'N, 77°24'W)* is between the sheer and heavily rust-stained cliff of **Cap Dalmas** and lower and sloping **Cap De Châteauguay**. The cove has high ranges of bare rock hills on either side and is free of mid-channel dangers. There is a winding river channel through a fine sandy beach at the head of the cove. Small craft drawing 3 or 4 feet (0.9 or 1.2 m) enter the river at high water and shelter just inside the entrance. The former *Hudson's Bay Company* post of **Wolstenholme**, long since abandoned, was at the head of the cove.

188 Good **anchorage** can be found near the head of Erik Cove in 20 fathoms (37 m), sand, with a small valley high on the west shore bearing 243°.

189 **Caution**. — Heavy swells from NW to NE gales or sometimes very violent southerly squalls from out of the valley at the head of the cove can make the anchorage unsafe.

190 **Fresh water** can be obtained from the streams at the head of the cove. Water from some of the other streams has an unpleasant iron taste.

## Erik Cove to Cap Wolstenholme

191 The coast between Cap De Châteauguay and **Cap Wolstenholme** *(62°35'N, 77°31'W)* has remarkable perpendicular cliffs rising from the water. Cap Wolstenholme, an imposing headland with a concave slope, has a low and short beak-like projection extending northward; this makes a useful **landmark** when the cliff tops are obscured.

192 **Caution**. — Strong **currents** and **tidal streams** sweep past Cap Wolstenholme; east of the cape the flow is always eastward. A heavy sea, **dangerous** to small craft, builds up when the wind is against the current.

# Cap Wolstenholme to Pointe Taliruq (Nuvuc)

## Digges Islands

193 The two **Digges Islands** *(62°34'N, 77°52'W)*, west of Cap Wolstenholme, are separated by a deep narrow channel. The east island is the higher of the two; it is hilly with cliffs on its south side. **Cape Digges**, the east end of the east island, rises to 400 feet (122 m). A nearby islet is joined to the cape at low water.

194 The west end of the western Digges Island is a low peninsula joined to the island by a low narrow isthmus. **Port de Laperrière**, an inlet on the south side of the isthmus, shoals rapidly but offers **anchorage** for small vessels with shelter from all but southerly winds. A **rock awash** and a **drying patch** are 0.2 and 0.5 mile south of the east entrance point.

195 **Digges Islet** *(62°35'N, 78°07'W)*, off the NW end of the western Digges Island, is 65 feet (20 m) high. An **isolated rock** with 21 feet (6.4 m) over it lies 1.3 miles west of Digges Islet, and islets surrounded by **shoal** water lie 1.6 miles to the SW.

196 *Digges Islet* **light** (2553) is on the north part of the islet.

197 Secure **anchorage** with excellent holding in mud and sticky clay and little effect from tidal streams

can be found in the passage between Digges Islands. There is protection from easterly gales and from moderate winds from all directions.

198 Fair **anchorage** with limited swinging room but good holding ground in clay can be found off the SE corner of the west Digges Island. A *Canadian Coast Guard* vessel found shelter here in NW to NE winds.

199 **Digges Harbour** *(62°34'N, 77°52'W)*, an inlet at the east end of the western Digges Island, offers good **anchorage** for small vessels in 21 fathoms (38 m). It is not recommended in northerlies as the harbour acts as a funnel for winds from that direction. The harbour has freshwater brooks and a place to beach small craft and was frequently used by Inuit when crossing from the mainland to Nottingham Island for the walrus hunt.

200 **Snelgrove Rock** *(62°34'N, 78°24'W)*, 7.8 miles west of Digges Islands, has a depth of 27 feet (8.2 m). Depths shoal rapidly; soundings give little warning. *Digges Islet* light in line with the north edge of Digges Islands, bearing 078°, leads 0.7 mile south of Snelgrove Rock.

## Passe Digges (Sound)

201 **Passe Digges (Sound)** *(62°28'N, 77°49'W)* leads along the mainland shore for 23 miles SW of Cap Wolstenholme. The sound provides a shorter route to destinations on the east side of Hudson Bay and has the advantage of being ice-free for some 10 days after the route north of Digges Islands is filled with ice from Foxe Channel.

202 **Caution**. — It is not safe to use Passe Digges once Hudson Bay ice enters this sound. The strong **tidal streams** cause heavy rafting off Nuvuk Harbour and Ivujivik Harbour.

203 A group of islands, none more than 200 feet (61 m) high, and several **shoals** and **drying patches** lie along the NW side of Passe Digges. The area between these features is not completely sounded. **Dome Islet** *(62°31'N, 77°58'W)*, in the NW part of the group, is perhaps the most **conspicuous** while **Fairway Island**, the southernmost, is the largest.

204 **North Skerries**, 1.5 miles west of Fairway Island, are a cluster of bare rocks on a **shoal bank**. There is an **isolated shoal** with a depth of 5 fathoms (9.1 m) 1 mile south of North Skerries. **South Skerries** *(62°23'N, 78°12'W)*, a smaller cluster of bare rock islets, mark the south side of the west entrance to Passe Digges.

205 A **beacon** on the NE islet of the South Skerries consists of a slatwork **daymark** with red and white vertical stripes on the west side of a skeleton **tower**, 32 feet (9.8 m) high. The condition of this beacon is unknown *(2006)*.

206 **Nuvuk Islands**, in the SW part of the sound east of South Skerries, are low ragged islands separated from each other and the mainland by narrow channels of **shoal** water.

207 **Staffe Islet**, **conspicuous** from NE, is a high, symmetrical and mostly steep-to island in the east part of Passe Digges.

208 Small vessels can find **anchorage** sheltered from westerly winds in a cove in the SE part of the island.

209 The beacon on South Skerries well open south of Fairway Island clears the **shoals** on the NW side of the sound west of Staffe Islet.

## Mainland coast of Passe Digges

210 The coastline SW of Cap Wolstenholme *(62°35'N, 77°31'W)* is a serrated cliff of light grey rock, rising almost vertically to 1,000 feet (305 m) and backed by higher land. This cliff is not visible from the east until the channel between the cape and Digges Islands is well open. In early summer thousands of Brönnich's guillemots, also called thick-billed murres, nest here high above the sea.

211 Between Cap Wolstenholme and Nuvuk Harbour, 16 miles to the SW, high perpendicular cliffs rise from deep water; near Nuvuk Harbour the coast becomes lower. The north part of the coast has provided a strong radar response at distances of 40 miles after Digges Islands faded at 30 miles.

212 **Cap Siukkaaluk (Siakkaaluk)** is 4 miles SW of Cap Wolstenholme.

213 **Ivugivik Harbour** *(62°25'N, 77°55'W)* is deep and free of shoals but exposed to both northerly winds and violent offshore winds blowing down the harbour. **Pointe d'Ivujivik** is the west entrance point.

214 **Caution**. — The flood **tidal stream** at the entrance to Ivugivik Harbour flows strongly SW.

215 The village of **Ivujivik**, population 298 *(2001)*, is on the west shore of the harbour. The settlement has a post office, police station and a health centre with a doctor and a dentist. There is a *Co-op* store and a *Co-op* hotel in the village. *Air Inuit* provides daily flights.

216 **Anchorage** can be found off the settlement in 30 fathoms (55 m) but it is not good because of the great depth and lack of shelter from the winds.

217 A coarse sand **landing beach** with deep water in front is near the settlement. A bollard has been installed near the shoreline *(62°24'58.392"N, 77°54'05.352"W)* to secure ships while unloading cargo and fuel.

218 **Nuvuk Harbour** *(62°24'N, 77°58'W)* lies between the mainland and Nuvuk Islands. There are cliffs around the east entrance point and there is a T-shaped inlet on the east shore of the harbour.

219 Good **anchorage** in 22 fathoms (40 m), mud and clay, can be found in the SE part of the harbour but the bottom drops off steeply to the NW. This anchorage has provided good shelter in a strong easterly gale.

220 **Anchorage** in 21 fathoms (38 m), mud and clay, with shelter from westerly winds can be found in the west part of the harbour.

221 Shelter from northerly winds can be found just off the mouth of the SW arm of the T-shaped inlet; small vessels can find sheltered **anchorage** inside this arm.

222 Inconspicuous **Pointe Taliruq (Nuvuc)** *(62°22'N, 78°05'W)*, south of Nuvuk Islands, is the SE entrance point of Hudson Bay.

# Hudson Strait — North Shore




## General

*Chart 5300*

1 Resolution Island *(61°33'N, 65°00'W)*, Edgell Island, Lower Savage Islands and numerous smaller islands lie in a group on the north side of the east entrance to Hudson Strait.

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

## Resolution Island

2 **Resolution Island**, barren and rough with many lakes, rises to over 1,600 feet (488 m) near the north shore. The coastline of the island has numerous inlets and bays. Some of these might provide shelter but only Sorry Harbour and Brewer Bay in the NE part of the island and Acadia Cove and Resolution Harbour near the southern point have been surveyed. Resolution Island was named in 1612 by Sir Thomas Button after his ship of that name.

*Chart 5459*

### East, south and SW coasts

3 **Caution**. — Much of the area covered by *Chart 5459* is **not surveyed**; these waters should not be entered without local knowledge. Those areas in which

soundings are shown have not been surveyed to modern standards. **Caution** is recommended in sounded waters.

4 **Hatton Headland** *(61°19'N, 64°47'W)* is at the SE end of an island separated by a narrow channel from Resolution Island. The headland is generally regarded as the SE point of Resolution Island and is the most prominent landmark in the south approach. The south end of the headland is less than 200 feet (61 m) high but the land 1 mile to the north rises to 600 feet (183 m).

5 **Tidal streams** south of Hatton Headland in the east entrance to Hudson Strait flow east and west and attain a rate of 5 knots. Streams with rates of 6 to 7 knots have been reported flowing parallel to the shore near the SW shore of Resolution Island. Strong **tide rips** and **overfalls** have been reported 10 miles south of Hatton Headland and to westward closer inshore.

6 There are rocky islands with **drying rock flats** and **reefs** in the unnamed bay and in the waters off the unnamed peninsula between Hatton Headland and **Tusk Island** *(61°19'N, 64°49'W)*, 1 mile west.

7 **Foul Passage**, with **Watt Islands** and **Star Island** on its west side, has shoals and **dangerous** rocks in its northern part.

## Resolution Harbour

8 **Resolution Harbour** is entered through **Resolution Tickle** between the islands described above and the coast of Resolution Island to the west. This channel narrows west of Star Island to a width of 150 feet (46 m) between the 6-fathom (11-m) lines. **Topsail Head** *(61°18'N, 64°51'W)*, on the west side of the entrance behind a group of islets, is a high bluff visible like a topsail for many miles. The beacon charted west of Topsail Head may no longer exist *(2006)*.

9 **Caution**. — **The Swirlers** is an area of strong **tidal streams** with heavy **tide rips**, **dangerous** in bad weather, close off Topsail Head.

10 **Haven Island**, with **Beak Point** at the south end, forms the east side of Resolution Harbour. **Mark Island**, **Mizzen Island**, **Dwarf Island** and **Stock Island** are inside the harbour.

11 **Shoals** line the shores of the harbour. **Puck Rock** and **Twin Rocks**, **drying** 4 and 11 feet (1.2 and 3.4 m), lie on the west side of the north part of the harbour. The beaches in this area are rocky and steep.

12 **Anchorage** with good shelter and excellent holding has been obtained SE of Twin Rocks by a vessel of about 1,000 t.

13 **Fresh water** is available from a stream draining **Sweetwater Lake** on the west side of the harbour.

14 **Caution**. — **Tidal streams** flow very strongly across the entrance to Resolution Harbour and entry should only be attempted at about the time of high water.

15 **Radio Island** *(61°19'N, 64°53'W)*, 1.3 miles west of the entrance to Resolution Harbour, is flanked by **Trident Island**, **Entry Islands** and **Boatswain Island**. Strong **tide rips** occur off the islands. **Lanyard Passage** separates Boatswain and Radio Islands from the mainland. The passage, suitable only for small craft, has been used for carrying stores from vessels anchored in Acadia Cove to Radio Island.

16 Two radio towers shown on Radio Island on the 2003 edition of the chart do not exist.

17 **Acadia Cove** *(61°20'N, 64°54'W)*, 1 mile NW of Radio Island, is sheltered to the SW and west by **Hen and Chicks**, **Sentinel Island** and **Cockade Island**. The cove offers **anchorage** for vessels up to 300 feet (91 m).

18 A small **beacon** with a diminutive cross, visible only at close range, stands on the summit of Sentinel Island at an elevation of 120 feet (37 m). The condition of this beacon is unknown *(2006)*.

19 **Shoals** lie off most of the shores of Acadia Cove. **Bilge Rocks**, parts of which **dry** 2 feet (0.6 m), are in the central part of the cove; a 22-foot (6.7-m) patch lies 0.1 mile SSW of the rocks.

20 **Acadia Passage** runs south of Sentinel Island. A **shoal bank** with depths between 21 and 33 feet (6.4 and 10.1 m) extends across much of the entrance.

21 Two small slatted **leading beacons** on the east shore of Acadia Cove, in line bearing 072½°, lead through Acadia Passage but are too close together to afford a precise transit. The condition of these beacons is unknown *(2006)*.

22 **Danger Passage**, well-named, is north of Sentinel Island. The passage has occasionally been used by vessels but **shoals** extending from both sides make the channel very narrow and a strong **tidal stream** flows across the entrance.

23 **Cook Passage** has shoals in its north part and is only used by small craft.

24 **Anchorage** is available in the NE part of Acadia Cove in 20 fathoms (37 m) with good holding over mud and clay. Elsewhere in the cove the bottom is rocky. Shelter is good from the prevailing winds of NW through north to SE. Some swell enters the cove with southerly winds and in strong easterly gales. Shelter from westerly winds is limited.

25 The beaches around the cove are rocky and the cliffs rise steeply from the water. Fresh water is plentiful in the vicinity.

26 During the navigation season, **fog** is common when there is **ice** in the vicinity.

27 **Caution**. — The entrance to Acadia Passage is not easy to distinguish and very strong **tidal streams** flow almost directly across the entrance. The passage is usually entered at about the time of high

water, which nearly coincides with slack water. The **shoal** spit extending north from Hen and Chicks may have depths less than charted.

28 **Cook Bay** is entered between Sentinel Island and **White Head** *(61°20'N, 64°58'W)*, a rocky promontory 1 mile WNW. **Watering Cove** is joined to Cook Bay by a **shallow** passage. The inner part of Cook Bay has many **shoals**.

*Chart 5300*

29 The SW coast of Resolution Island NW of Cook Bay is much lower than the north and east coasts and has many bays and inlets. The inshore waters have not been sounded; the suitability of the inlets for shelter is not known. Islets and **rocks** abound along the shore. This coast should be given a wide berth.

30 The east coast of Resolution Island between Hatton Headland *(61°19'N, 64°47'W)* and Cape Warwick, 17 miles NNE, has many indentations and its shores consist mostly of cliffs rising sheer from the sea. Many of the headland ridges continue offshore as **submerged ledges** or islets; some are up to 4 miles offshore. This coast should not be approached closer than 10 miles.

*Chart 5340*

31 **Caution**. — Much of the coast of Resolution Island covered by *Chart 5340* is **not surveyed**; these waters should not be entered without local knowledge. The areas in which soundings are shown have not been surveyed to modern standards. **Caution** is recommended in sounded waters.

32 **Cape Warwick** *(61°35'N, 64°38'W)* is a **conspicuous** steep red **cliff** unlike any other on Resolution Island. A large **dome** atop a tower and a nearby abandoned **radar installation** on the cape are **conspicuous** from seaward.

33 **Brewer Bay** *(61°35'N, 64°39'W)* offers **anchorage** in good weather, for vessels up to 240 feet (73 m) in length, off the small cove with Yellow Beach at its head. A vessel has moored in this berth, lying to two anchors on a heading of 045° with quarter lines to the shore, but the berth is **dangerous**. The bay is small and provides little shelter; there is, occasionally, heavy ground swell. Larger vessels, in good weather, can find **anchorage** *(not charted)* off the entrance to Brewer Bay.

34 **Caution**. — The **wreck** of the M/V *Minna* is on the north side of the entrance to Brewer Bay. Its position and depth over were determined in 1998, but mariners are cautioned that the wreck might have shifted due to ice action, in which case its exact position and depth over would be unknown.

35 **Yellow Beach** *(not named on the chart)*, in Brewer Bay, is well-sheltered for small craft by high hills on both sides. The beach is 150 feet (46 m) wide and 750 feet (229 m) long with a gradient of 1:30. It is flanked by prominent rock ridges and there are numerous boulders in the approach but no underwater obstacles in the beaching slot. The beach from low water to half tide is fine sand; from half tide to high water it is rough **rock**. A swell of from 4 to 6 feet (1.2 to 1.8 m) occasionally runs here.

36 **Mooring bollards** *(not charted)* are positioned on both sides of the entrance to Yellow Beach. Two large fuel **storage tanks** are located close west of Yellow Beach.

37 **Sorry Harbour**, 2 miles NNW of Cape Warwick, provides **anchorage** with fair shelter but poor holding over a rocky bottom with patches of mud, hard clay and shell. The harbour is open to the east but is better than Brewer Bay.

38 Two yellow triangular **leading beacons** on islands on the north side of Sorry Harbour, in line bearing 267°, aid in approaching the harbour. A **beacon** *(not shown on the chart)* is on the south side of the harbour 0.7 mile within the entrance. These aids are no longer maintained and their condition is unknown *(2006)*.

39 **Fresh water** is available from streams in Sorry Harbour.

40 **Caution**. — Several islets and many rocky **shoals** are in Sorry Harbour and its approaches. Mariners should note the "**Caution**" on *Chart 5340* concerning dangers reported south of the dashed line which extends SE and east from Brewer Bay. Uncharted **shoals** have been reported in the area extending up to 1 mile offshore between Cape



Warwick and the point 1 mile to the north. **Breakers** have been reported near the 13-fathom (24-m) sounding 3.7 miles east of Cape Warwick. The NW side of the approach to Sorry Harbour appears to contain much **foul ground**. A small, low, **uncharted** islet, with islets and **reefs** extending SSW, has been sighted 013° from Cape Warwick, 3.1 miles distant.

41 The **tidal streams** in this vicinity are strong. In Brewer Bay, the tidal stream runs swiftly in a circular path at high water and there can be considerable **swell**. At half tide and below the tidal streams and swell are considerably dampened by reefs. A **current** of 2 to 3 knots, flowing 210°, has been experienced 15 miles east of Resolution Island.

## Cape Warwick to Baffin Island

42 An unnamed bay *(61°38'N, 64°43'W)*, filled with islets and **rocks**, is on the north coast of Resolution Island immediately NW of Sorry Harbour. The coast of Graves Strait west of this bay is high cliff in the east and central sections but towards the west the cliffs are lower.

*Chart 5300*

43 **Graves Strait**, between Resolution and Edgell Islands, has many **rocks** and small islands and irregular depths. It is only partly surveyed and **uncharted dangers** may exist.

44 **Edgell Island**, rough and barren with many lakes, reaches its maximum elevation near **Black Bluff** *(61°56'N, 65°06'W)*. The bays and inlets around Edgell Island have not been surveyed but have many **rocks** and islets and could be extremely **dangerous** to approach. There are **tide rips** or very strong **currents** off the SE point of the island.

45 **Gabriel Strait** separates Edgell and Resolution Islands from Lower Savage Islands. **Tidal streams** of up to 5 knots run through the deep strait causing a confused sea with **whirlpools** and remarkable **tide rips** near the Lower Savage Islands.

46 **Caution**. — Navigation of these waters by small craft is often hazardous during **spring tides**. When the **tidal streams** are strongest, vessels are set strongly towards the island and careful handling is necessary.

*Chart 5411*

47 **Caution**. — The area covered by *Chart 5411* is **not surveyed** to modern standards; caution is recommended.

48 **Lower Savage Islands** *(61°48'N, 65°47'W)*, three main islands separated by two narrow steep-sided channels, have numerous smaller islands, islets, **rocks** and **reefs** on the SW and east coasts. The terrain is extremely rough with many lakes, and all coasts rise precipitously from the sea. Elevations are lowest in the west section of the NW and SW coasts. **Point Meridian** *(61°47'N, 65°57'W)*, at the west end of the islands, has an elevation of 150 feet (46 m).

49 **Caution**. — Extreme caution is recommended in the vicinity of the Lower Savage Islands because of the strong **tidal streams** and the possibility of **uncharted dangers** near the coasts.

50 The channel between the east main island and the finger-shaped island off its SE coast has many **rocks** and **reefs**.

51 The two channels separating the main islands are blocked by **rocks** and islets at their south ends. The bay at the north end of the west channel has **rocks** off the east side and there are **rocks** off the east side of the point at the head of the bay.

52 **Savage Harbour** *(61°50'N, 65°46'W)*, at the north end of the east channel, is entered between headlands over 350 feet (107 m) high on the NW side and 500 feet (152 m) on the SE side. **Anchorage** with good shelter from all winds in 22 fathoms (40 m), mud, can be found NW of two 50-foot (15-m) high islands 1 mile inside the entrance. The anchorage, 0.4 mile long by 0.3 mile wide, is approached between the north shore and the NE island through a channel with a depth of 13 fathoms (24 m). The channel is only 300 feet (91 m) wide between **shoal spits** and **reefs** which extend from both shores.

53 High and low water at Savage Islands occur 55 minutes before the times of high and low water at Diana Bay *(see Tide and Current Tables, Volume 4)*. The approximate **tidal range** during large tides is 26 to 29 feet (7.9 to 8.8 m); during mean tides it is 9.5 to 20 feet (2.8 to 6.1 m).

54 **Fresh water** can be obtained by small craft from a cascade 2 miles within the channel.

55 **Annapolis Strait** is a deep passage running between the Lower Savage Islands and the SE end of Meta Incognita Peninsula on Baffin Island.

56 *Frobisher Bay and its east approaches are described in Sailing Directions booklet ARC 402 (ARCTIC CANADA VOL. II).*

## Baffin Island — East Bluff to Lake Harbour

*Chart 5300*

57 The south coast of Baffin Island is very bleak; bare rugged hills of gneiss and granite rise to 600 feet (183 m) close to the sea and to greater heights inshore. The white surface of **Terra Nivea Ice Cap**, 18 miles inland on Meta Incognita Peninsula, is visible from Hudson Strait. Streams tumble from numerous small lakes into the sea at the heads of many of the narrow inlets that break the rough shore.

58 Many islands and **rocks** lie offshore, as far as 15 miles in places; the coast is difficult to approach. The water deepens rapidly seaward of the outer islands and rocks and there are no known isolated dangers farther out in the strait.

*Charts 5411, 5300*

59 *The topography of Chart 5300, based on more recent surveys, is more accurate than that of Chart 5411.*

60 **East Bluff** *(61°53'N, 65°57'W)*, the SE extremity of **Meta Incognita Peninsula**, is an imposing promontory rising sheer from the water to 750 feet (229 m). The bluff is at the south end of a high wall of solid rock extending for 3.5 miles into Annapolis Strait. Very strong **tidal streams** are deflected well out into the strait by the bluff.

61 The coast west of East Bluff is bold and rugged with many rocky islets and **reefs**.

62 **South Reefs** *(61°52'N, 66°14'W)* are a cluster of rocks and islands 8 miles west of East Bluff. The largest has an elevation of 160 feet (49 m). From east or west, the reefs appear to be a long spit jutting out into the sea. The terrain inland of the reefs is low. Small craft can find some shelter in the small bays or under the lee of the islets here while waiting for favourable conditions to round East Bluff.

63 **Nannuk Harbour** *(61°54'N, 66°22'W)* affords good shelter for small vessels. The narrow harbour is flanked on the east side by hills rising abruptly to over 400 feet (122 m). The west entrance point is low and shelving and backed by lower terrain. **Fresh water** can be obtained from a small overhanging fall on the west side 0.5 mile inside the entrance.

64 Numerous islands and reefs extend up to 2 miles offshore between Nannuk Harbour and Pritzler Harbour, 30 miles WNW. Vessels without local knowledge are cautioned not to approach within 3 miles of the coast or the off-lying islets. The coast is low and rocky, rising 2 to 3 miles inland to rugged hills up to 400 feet (122 m) high.

65 An inlet *(61°58'N, 66°38'W)*, **not surveyed**, lies 8 miles WNW of Nannuk Harbour. Many **reefs** and islets are off the north entrance point and the outer part of the inlet has low rocky shores. The south shore rises gradually in height within the inlet to a steep north-facing escarpment over 400 feet (122 m) high at the head of the east fork. The north shore is much lower.

66 **Sister Islets** *(62°00'N, 66°53'W)* lie in the approaches to an inlet, **not surveyed**, with low rocky shores sheltered to southward by an island and a peninsula *(see Chart 5300 for topography)*.

67 An inlet, 8 miles WNW of Sister Islets, is protected by extensive rocky islets and **drying reefs** and affords good shelter for small vessels. Soundings show depths of 2 to 32 fathoms (3.7 to 59 m). The island on the SW side of the entrance has an elevation of 60 feet (18 m).

*Charts 5411, 5403*

68 **Caution**. — The area covered by *Chart 5403* is **not surveyed** to modern standards; caution is recommended.

69 **Pritzler Harbour** *(62°07'N, 67°21'W)* is the best harbour in this area. The east shore of the harbour rises gradually northward to a group of rugged hills with elevations of over 300 feet (91 m) at the head. There are no known offshore dangers in the harbour or the south approach and **anchorage** is available in depths suitable for medium-draft vessels with shelter from all but south winds. Pritzler Harbour is sheltered to the west by a group of rocky islands and islets with **Thompson Island** at the west end. Small craft can obtain good shelter inside the islands. A passage, **not surveyed**, leading into the harbour from WSW is narrow with many islets and **reefs**.

*Charts 5403, 5300*

70 Many islets and very **dangerous rocks** and **shoals** line the shores between Pritzler Harbour and Barrier Inlet, 44 miles WNW. Mariners without local knowledge are cautioned to stay outside the 50-fathom (91-m) line for at least as far west as Gray Goose Islands *(62°13'N, 68°25'W)*. The coast is similar between Barrier Inlet and Maniittur Cape (Cape Weymouth), 20 miles WNW, but there are fewer offshore dangers.

71 **Saddleback Island** *(62°09'N, 67°54'W)*, named for its shape, is the largest and highest of **Middle Savage Islands**. Islands, **rocks** and **foul ground** extend up to 5 miles SE and 7 miles SW and west of Saddleback Island. Depths increase rapidly to seaward of the foul area; soundings give little warning. **Duck Island** and **Lyon Rocks** are at the SE and west extremities of the group.

72 **Bond Inlet** *(62°11'N, 67°49'W)*, small and landlocked, offers good **anchorage** for small vessels but the approach channel from westward between the islands and the mainland is narrow and intricate. Local knowledge is required.

73 **Tides** in this area rise over 35 feet (10.7 m) at springs and the **tidal streams** run violently between the offshore islands.

74 **Caution**. — A **tidal stream** of 5 knots has been encountered close south of Middle Savage Islands. A heavy sea builds up when the wind is against the current. These conditions are hazardous for small craft.

75 **Wight Inlet** *(62°13'N, 68°12'W)* is blocked by islets and **reefs** and, except for one small area in its mouth, dries at low water. **Gray Goose Islands** lie 6 miles to the west. The **shallow** mouth of a **drying inlet**, 5 miles WNW of Gray Goose Islands, is obstructed by islets and **reefs**.




VIEW IN TWO PARTS OF EAST BLUFF AND THE LOWER SAVAGE ISLANDS
VUE EN DEUX PARTIES DE EAST BLUFF ET DE LOWER SAVAGE ISLANDS

76 **Balcom Inlet** *(62°19'N, 68°43'W)* offers good **anchorage** in a landlocked basin but the entrance has many dangers. **Mary Rock**, with less than 6 feet (1.8 m) over it, lies 2 miles WSW of the west entrance point. Depths of 15 and 12 feet (4.6 and 3.7 m) are in mid-channel in the mouth of the inlet and 2 miles within the mouth. The inlet can be entered only during favourable states of tide; near low water heavy seas against the outgoing tidal stream break to the bottom. Local knowledge is recommended.

77 **Barrier Inlet** *(62°21'N, 68°51'W)* is obstructed by **reefs** and **shoal water** in its entrance and outer part and by a reversing falls 2 miles within the entrance. Barrier Inlet does not afford safe anchorage even for small craft and should not be attempted without local knowledge. A sheer outward **waterfall** 8.5 feet (2.6 m) high was observed at the reversing falls at the time of low water. The outward movement of water continued for 2½ hours while the tide was rising at the foot of the falls. There was slack water briefly when the flood tide reached the level of the waters in the upper reach but almost immediately the inward rush of water formed **whirlpools**, great **eddies** and waves up to 6 feet (1.8 m) high.

78 **Inuit Islet** is on the east side of the mouth of Barrier Inlet in the approaches to **Observation Cove**. The cove has a least depth of 1 foot (0.3 m) in the narrow channel leading to a deeper basin at its head.

79 High and low **tides** at Barrier Inlet occur 10 minutes after high and low tides at Diana Bay *(see Tide and Current Tables, Volume 4)*. The **tidal range** during large tides is from 32 to 35.5 feet (9.8 to 10.9 m); the range during mean tides is 25 feet (7.6 m).

80 The coast between Barrier Inlet and Shaftesbury Inlet, 16 miles NW, rises abruptly to rugged hills and is comparatively free from outlying islets and reefs.

*Chart 5316*

81 **Caution**. — Most of the inshore waters covered by *Chart 5316* have not been sounded and should not be entered without local knowledge.

82 **Shaftesbury Inlet**, entered between **Sentry Islet** and **Michael Point** *(62°32'N, 69°21'W)*, is flanked by high rocky hills. The inlet has steep shores through most of its length and is free of shoals. **Hare Islet** lies in mid-channel 3 miles north of Sentry Islet. **Anchorage** with good shelter can be obtained but the entrance requires careful navigation. **Depths** of 15 feet (4.6 m) and a **rock** which dries 16 feet (4.9 m) are within 2.3 miles south of Michael Point.

*Charts 5316, 5455*

## Kimmirut (hamlet of Lake Harbour) and approaches

83 **Caution**. — Much of the area covered by *Chart 5455* is **not surveyed** and should not be entered without local knowledge.

84 Lake Harbour *(62°51'N, 69°52'W)*, at the head of Glasgow (Westbourne) Bay, is the best-sheltered harbour in this region. The hamlet of Kimmirut (Lake Harbour) is at the north end.

85 **North Bay**, in the south approaches to Glasgow (Westbourne) Bay and Lake Harbour, lies between **Maniittur Cape (Weymouth)** *(62°33'N, 69°25'W)* and the west entrance point of **Bruce Harbour** *(62°46'N, 70°09'W)*, 24 miles NW. A **rock**, 1.5 feet (0.4 m) high, is close SSE of Maniittur Cape.

86 **Carew Bay**, east of Maniittur Cape, is **not surveyed**. The east coast of North Bay between Maniittur Cape and **Cape Tanfield**, 8 miles NNW, is rocky and low in the south part becoming higher and bolder towards the north. **Juet Island** *(62°36'N, 69°30'W)*, highest at its north end, is one of many islands lying off this stretch. **Drying reefs** exist up to 2 miles off the islands.

87 **Upper Savage Islands**, a group of islands and islets visited and named by Bylot and Baffin in 1615, lie off the SW part of North Bay. **High Bluff Island** *(62°34'N, 70°01'W)* has high cliffs except at its SE and SW points but the other islands of the group are low; all are partly surrounded by **reefs** and **shoal water**.

88 **Pleasant Inlet**, in the NW part of North Bay, is entered west of **Cape Novoa** *(62°45'N, 69°51'W)*, a small point at the south end of **Tikkuut (Tikko) Peninsula**; **Soper Lake** is at the head of Pleasant Inlet. Pleasant Inlet is blocked 5 miles within its entrance by a maze of **rocks** and **drying reefs**. **Tidal streams** here are fierce.

89 **Itivirk Bay**, on the east side of North Bay, is entered between Cape Tanfield and the Sheer Islands; it is **not surveyed** but deep water close inshore has been reported. **Mount Chaunsler**, a **conspicuous** mass of grey and reddish gneiss, rises at the head of the bay.

90 **McKellar Bay**, **not surveyed**, lies between **Lee Island** *(62°41'N, 69°36'W) (not named on the chart)* and **Napparti Point (Noovoksit)**. **Black Bluff Island** *(62°43'N, 69°38'W)*, **Poodlatee Island** and several other islets and rocks lie in the entrance. **Drying rocks** lie up to 0.4 mile south of Poodlatee Island.

91 **Tidal streams** rush violently between these islands and islets causing **tide rips** and **eddies**. The channels are open throughout the winter and this is a favourite seal-hunting area for the Inuit.


IJJURITTIAK ISLAND
WESTERN REEFS
BEACON ISLAND
APPROACHES TO
APPROCHES DE LAKE HARBOUR

LAKE HARBOUR

*Chart 5455*

92 **Beacon Island** *(62°42'N, 69°43'W)*, in the north part of North Bay, is named for a large wooden pyramid; the condition of this beacon is unknown *(2006)*.

93 **Stanley Reef** lies 1 mile NW of Beacon Island; two rocky patches are in mid-channel between them. **Ivisaat Island (Eveeska)**, 1.5 miles west of Stanley Reef, has **shoal patches** of 16 to 30 feet (4.9 to 9.1 m) extending 1.8 miles SSE. A 23-foot (7-m) patch is 1 mile ENE of Beacon Island and **Larch Reef** is one of a number of **reefs** up to 1.5 miles SE and south of Beacon Island. A gravel **shoal patch** with a depth of 33 feet (10.1 m) and two **rocks** with least depths of 15 and 4 feet (4.6 and 1.2 m) extend 1 mile east and SE of Larch Reef.

94 **Glasgow (Westbourne) Bay** is entered between **Nuvursirpaaraaluk Island (Noovoserparalo)**, the SE island of the group lying off **Cape Wight** *(62°44'N, 69°45'W)*, and Napparti Point, 2 miles ENE, the SE tip of the islands close off **Nuvualujjuaq Peninsula (Novoalojuak)**. **Aulassivik Island (Aulatsevik)** lies close off Cape Wight.

95 **Western Reefs**, only two of which are visible at high water, lie on the west side of the main ship channel just inside the entrance to Glasgow Bay. **Tasseoyak Bay** *(62°46'N, 69°39'W)* is sheltered to the west by **Sulussugut Peninsula (Sooloosoogut)**. **Ijjurittiak Island (Ejooreeta)** and **Glasgow Island (Takeyooala)**, along with islets, rocks and reefs, lie on the west side of Glasgow Bay.

96 The main ship channel leads through **Sealer Narrows** *(62°48'N, 69°49'W)*, between the north part of Glasgow Island and **Uugalautiit Island (Ongalaota)**. At high water springs Uugalautiit Island does not appear at all like its charted shape. Only a few pinnacles are visible. **Shoal depths** of 16 and 18 feet (4.9 and 5.5 m) are in the north part of the narrows off **Baldpate Island**. A **spit** with a **rock awash** and a depth of 4 fathoms (7.3 m) near its end projects north from Glasgow Island. There is a 3-knot **tidal stream** in the narrows.

97 **Buoys** are placed every year in Sealer Narrows for the duration of the resupply operation. Red conical buoys, marked "L2", "L4" and "L6" are placed off the south tip of Uugalautiit Island, and 0.15 mile ESE and 0.05 mile SE of the south end of Baldpate Island, respectively. A black can buoy, marked "L3", is placed 0.15 mile SE of the south end of Baldpate Island.

98 **Anchorage**. — In 1987, the CCGS *Norman McLeod Rogers* safely rode out 30 knot gusts in position 62°46'N, 69°41'W, 0.58 mile north of the north end of Nuvualujjuaq Peninsula. The vessel was anchored in 180 feet (55 m), clay bottom, using 540 feet (165 m) of cable. Mariners using this berth are cautioned about the **reef** with a depth of 32 feet (9.8 m) 0.38 mile NNW of the north end of Nuvualujjuaq Peninsula.

99 **Glasgow Inlet**, with **Iqaijuq Cove (Eegaiyo)** at its head, is entered east of **Nascopie Point** *(62°49'N, 69°50'W)*. **Glasgow Falls** *(not named on the chart)*, at the head of the inlet, provides **fresh water**.

100 **Lake Harbour**, entered west of Nascopie Point, is very well sheltered and has a least mid-channel depth of 40 feet (12.2 m). It is bordered for most of its length by land rising from 500 to 700 feet (152 to 213 m). The hills rise steeply in the upper reaches of the harbour. **The Heel** is a peninsula at the head of the harbour. The RCMP structure east of The Heel is abandoned. Lake Harbour was visited by whalers prior to 1900.

101 **Caution**. — An **anchorage** 0.4 mile SE of Sealer Narrows is not recommended in bad weather. A 370-foot (113-m) vessel has lain to a single anchor 0.4 mile SSE of The Heel and a 225-foot (69-m) vessel has moored to bow and stern anchors 0.1 mile SSE of The Heel. Both vessels dragged in NW gusts of 25 to 30 knots even though the holding ground had been reported to be good.

102 Tankers can berth 0.4 mile SSE of The Heel in 26 fathoms (48 m), laying on a SE heading, with stern lines out to the west shore and to the point SSW of the RCMP building. From this berth a vessel can discharge direct to the shore through 3,600 feet (1,100 m) of floating hose.

103 The **tidal stream** in Lake Harbour is negligible.

104 A **landing beach** of mud and boulders, NE of the hospital, can be used for two hours before and after high water.

105 The hamlet of **Kimmirut (Lake Harbour)**, population 433 *(2005)*, grew around an Anglican Mission established in 1900 and a *Hudson's Bay Company* post established in 1911. The hamlet has a post office, health centre and RCMP detachment. There are two retail stores and accommodations are available at a *Co-op* hotel. *First Air* provides flights to Iqaluit on Monday, Tuesday Thursday and Friday.

106 The **Itijjagiaq Trail**, used by the Inuit for centuries, leads 120 km (75 statute miles) from Kimmirut up through the Soper River valley and across Meta Incognita to Frobisher Bay.

## Lake Harbour to Fair Ness

*Charts 5316, 5450*

107 The coast is very rugged between North Bay, in the approaches to Lake Harbour, and Fair Ness, 70 miles NW. The coastal hills, ranging in elevation from 50 to 700 feet (15 to 213 m), are backed 10 to 15 miles inland by mountains which rise 1,000 to 1,500 feet (305 to 457 m) and are generally more

rounded and rolling than those along the coast. Big Island is the largest of the numerous islands along this shore.

108 **Caution**. — Most of the coastal waters covered by *Chart 5450* have not been surveyed and should not be entered without local knowledge.

109 **Big Island** *(62°40'N, 70°36'W)*, barren and rough, reaches elevations of 1,200 feet (366 m) in the central NE part and 800 feet (244 m) in the NW part. Most of the north coast of the island consists of a line of cliffs rising sheer from the water to over 700 feet (213 m) at the east end of the island and reduce gradually to 200 feet (61 m) at the west.

110 **White Strait** *(62°50'N, 70°34'W)*, between Big Island and Baffin Island, has not been fully surveyed but has mid-channel **depths** from 4 to 34 fathoms (7.3 to 62 m). The Baffin Island shore is rough and rocky and there are low, bare, rocky islands in the strait.

*Chart 5316*

111 Bruce Harbour *(62°46'N, 70°09'W)* and **Beaulieu Bay** are on the Baffin Island shore near the SE entrance of White Strait.

112 **Bosanquet Harbour**, on the NE coast of Big Island, is well-sheltered by steep cliffs except to the SW. The harbour shoals rapidly 1.5 miles within the entrance and there are **drying mud flats** in the upper reaches.

113 An unnamed inlet 10 miles NW of Bosanquet Harbour cuts through the cliffs inland for 2 miles to a restricted section and then widens into a small basin. The head is filled with **mud flats** but elsewhere this inlet appears to be deep close to the shores. This is believed to be the harbour described as "a good harbour" by Dr. Robert Bell in 1877.

*Chart 5450*

114 **Fisher Harbour** *(62°51'N, 70°54'W)*, in the north part of White Strait, is a bay on Big Island sheltered by a long, finger-shaped island. The finger-shaped island is separated from Big Island by a **drying channel** and has an islet and **shoals** with 6 feet (1.8 m) or less extending 5 miles to the WNW.

115 Broad rocky ridges rise steeply out of the water to 500 feet (152 m) on either side of a cut leading to **Beaumont Harbour**, on the Baffin Island shore of White Strait. **Henderson Harbour** *(63°00'N, 70°56'W)*, between rounded hills reaching 1,000 feet (305 m) in elevation, is obstructed halfway to its head by a rocky island and **reefs**. A channel less than 300 feet (91 m) wide leads south of the island.

116 **Crooks Inlet**, with high steep shores, is entered between **Cap Colmer** *(63°00'N, 71°13'W)* and a bluff 2 miles ESE. The bluff rises from deep water to 300 feet (91 m). A **rock** with a depth of 2 feet (0.6 m) is in the entrance to the inlet. An island 5 miles within the entrance is estimated to be 150 feet (46 m) high.

117 The upper part of Crooks Inlet divides into **Noel Harbour**, with relatively low shores, and **Irving Bay**, which opens out into a broad shallow valley. Silt from the **Ramsay River** has formed a delta at the head of Noel Harbour. Cliffs rise to more than 700 feet (213 m) behind a narrow beach on the south side of the entrance to Irving Bay. A number of **shoals** lie within the bay 1 mile from its head.

*Chart 5316*

## SE shore of Big Island

118 **Reeves Harbour** *(62°32'N, 70°21'W)*, **not surveyed**, has two deep and narrow entrances. The small harbour provides **anchorage**, with good holding in 5 to 14 fathoms (9.1 to 26 m), with protection superior to that available in Ashe Inlet, 6 miles west.

119 **Ashe Inlet** is surrounded by hills 400 feet (122 m) high. **Rabbit Island** *(62°32'N, 70°34'W)* is the largest of a number of islands which protect the inlet.

120 **Caution**. — A **reef** with a depth of 21 feet (6.4 m) lies in the middle of the entrance to Ashe Inlet. A **low islet** which may cover at high water springs lies 1.6 miles east of Rabbit Island. Many **shoals** lie in the channel between this islet and Big Island.

121 **Anchorage** can be found in the middle of the inlet 1.2 miles NW of Rabbit Island. The anchorage is not safe in a SE gale.

122 The condition of the **beacon** and the **cairn** on the NE shore of Ashe Inlet is unknown *(2006)*.

*Chart 5450*

## SW shore of Big Island

123 **North Bluff** *(62°36'N, 70°46'W)* has an elevation of 50 feet (15 m) and is backed by hills rising to 400 feet (122 m). **Shoal depths** are up to 2 miles south of the bluff.

124 The bay on the SW coast of Big Island from North Bluff to the west end of the island is filled with numerous **rocks**, islets and islands. **Emma Island**, the largest of the latter, rises to over 600 feet (183 m) and is joined to Big Island by **drying ledges** and islets.

## Big Island to Fair Ness

125 **Strathcona Islands** *(63°00'N, 71°25'W)*, one large island and a group of small rocky islands, lie from 2 to 9 miles west of Cape Colmer. The north side of the larger island rises steeply in a series of ridges to 600 feet (183 m). The south side is lower.

126 **Glencoe Island** *(63°04'N, 71°28'W)* is the largest of a group of islands and rocks in front of **Canon Inlet**. The inlet is approached from SW between the islands and the mainland to the north. The entrance to the inlet is partially blocked by a large **shoal** near the NW entrance point and by

two **submerged rocks** between this shoal and the SE entrance point. Canon Inlet is bounded by rock cliffs over 1,000 feet (305 m) high. **Rapids** separate the head of the inlet from **Overflow Lake**, a short distance inland.

127 Between Canon Inlet and Fair Ness, 27 miles NW, the coast of Baffin Island rises rapidly inland to a plateau with elevations of more than 1,000 feet (305 m) cut by a series of ESE-WNW ridges and valleys. The plateau decreases in elevation towards Fair Ness where it becomes a rocky peninsula and then slopes beneath the sea to form a maze of island chains.

128 This stretch of coast, not sounded, has many islands and islets. **Spicer Island** *(63°18'N, 71°52'W)* is the largest. A number of inlets break the coast; the named ones are **Chudliasi Bay**, **Wharton Harbour**, **Akuling Inlet** and **Bedford Harbour**.

129 **Fair Ness** *(63°24'N, 72°05'W)*, named by Baffin because of the fair weather he experienced here for 10 days in 1615, is bold and rocky, rising to 500 feet (152 m) and dropping steeply on its north side. Large numbers of rocky islands lie NW of Fair Ness.

## Fair Ness to Chorkbak Inlet

130 The coast of Baffin Island between Fair Ness and Chorkbak Inlet, 90 miles NW, is a maze of very irregular inlets with archipelagos of islands and **rocks** extending almost 20 miles offshore. The highest islands are usually nearest the coast. From seaward it is very difficult to distinguish between the islands and the entrance points of the innumerable bays and inlets. Elevations near the coast are between 200 and 600 feet (61 and 183 m) but 10 to 15 miles inland there are elevations of more than 1,000 feet (305 m).

131 **Markham Bay** *(63°33'N, 71°51'W)* is filled with islands and **rocks** and has numerous bays. Most of these are full of rocky islets and **shoals** and are silted up at their heads. Access to these bays would be very difficult. Named features in Markham Bay are **George Bay**, **Blandford Bay**, **Robert Point**, **Ava Inlet**, **Aberdeen Bay** and **White Bear Bay**. **Mount Lansdowne**, on the west side of White Bear Bay, is estimated to be between 500 and 600 feet (152 and 183 m) high.

132 **Islands of God's Mercie** *(63°29'N, 72°04'W)*, on the SW side of Markham Bay, are small and rocky with elevations less than 200 feet (61 m). The four largest islands of the next group to the NW are more rugged. The two westernmost are over 500 feet (152 m) high with north-facing escarpments. **Hector Island**, **Macdonald Island** and a large island close north of the latter reach elevations of 500 to 600 feet (152 to 183 m) near their east ends. The islets NW and west of Macdonald Island are mostly low.

133 **Caution**. — The passage between the islands described above and the low islets bordering the mainland shore to the NE is filled with **rocks** and **reefs**. The **tidal streams** between the islets and in the entrances to the numerous inlets are strong; near low water there is a particularly powerful flow out of White Bear Bay.

134 **Amadjuak Bay** *(63°58'N, 72°38'W)*, the former site of a *Hudson's Bay Company* post, is surrounded by rugged hills 200 to 500 feet (61 to 152 m) high. There are several small bays; some have strips of beach at their heads. A river with foaming **rapids** enters the head of Amadjuak Bay past the foot of an isolated conical hill on the west shore. **Anchorage** near the head of the bay is good but the approach is intricate and local knowledge is recommended. Strong **tidal streams** are reported.

135 **Rawson Island** *(63°57'N, 72°56'W)* is a rounded ridge of rocks rising to 200 feet (61 m). **Bonney Island** is close north. **Chamberlain Island**, 23 miles WNW, elevation 100 feet (30 m), rises very steeply on the north side but gently on the south. A smaller island close NE is 150 feet (46 m) high. **Hobart Island** lies 8 miles to the NE.

136 The only named inlets in this region are **Korok Inlet** *(64°16'N, 73°28'W)*, **Keltie Inlet** and **Archibald Bay** *(64°23'N, 74°14'W)*. The last is entered between **Cape James** and **Julian Point**. **Jubilee Island** and **Diamond Islands** are some of the few named islands.

137 **Chorkbak Inlet** *(64°24'N, 74°28'W)*, 24 miles long, extends north and NW between rugged rounded hills of granite and gneiss 250 to 300 feet (76 to 91 m) high. **Shugba Bay** reaches east and north from a position 12 miles within the inlet. There are two bays at the head of Chorkbak Inlet; the NE of the two is **Shukbuk Bay** *(not shown on the chart)*.

138 In 1958 the *M.V. Arctic Sealer*, drawing 13 feet (4 m), entered Chorkbak Inlet. A **shoal** with a depth of 12 feet (3.7 m) was found 0.5 mile east of Julian Point and strong **tide rips** and **eddies** were encountered in this area. The bottom was very irregular in the outer part of the approaches to Chorkbak Inlet and there were several **uncharted shoals and reefs**; some of these were visible at low water.

## Chorkbak Inlet to Cape Dorset

139 The SE coast of **Foxe Peninsula** is formed by hills with elevations of 100 to 400 feet (30 to 122 m) near Chorkbak Inlet. The hills increase to nearly 1,000 feet (305 m) towards Cape Dorset, 55 miles WSW.

140 The **magnetic compass** is erratic off Foxe Peninsula.

141 **Aquiatulavik Point** *(64°22'N, 74°42'W)*, 6 miles west of Chorkbak Inlet, is the site of a former Inuit settlement.

142 **Terreoukchuk Bay** *(64°33'N, 75°34'W)* is 6 miles west of **Neakok Lake**.

143 **Andrew Gordon Bay**, with chains of rocky islets, is bounded to the SW by **Pungnertuk Point** and **Alareak Island**, rocky and mostly low. Saunders River flows into the head of the bay and the Kimmik Range of mountains extends NW from the head. **Cape Willingdon** is at the east end of Alareak Island.

144 **Caution**. — Strong **tide rips** occur in Andrew Gordon Bay. The most violent are in the passage between Alareak Island and the mainland and in the narrow entrance to Terreoukchuk Bay.

145 **West Foxe Islands**, 3 miles SW of Alareak Island, are a group of rocky islands less than 30 feet (9 m) high. The largest of this group is **Tunitjuak Island**, the farthest SE is **Ooglukjuak Island** *(neither island is named on the chart)*. Another similar group of offshore islands lies 4 miles to the WNW.

146 **Catherine Bay** *(64°23'N, 75°58'W)* and **Shartowitok Bay** are west of Andrew Gordon Bay on the mainland shore. **Pudla Inlet**, 4 miles SW, is north of **Iglukjuak Point**. **Shemia Islands** lie close SW of this point; **Neta Islands** lie 3 miles farther SW in the approaches to **Negus Bay**.

*Chart 5451*

## Cape Dorset and approaches

147 **Caution**. — Much of the area covered by *Chart 5451* is **not surveyed**; these waters should not be entered without local knowledge. The areas in which soundings are shown have not been surveyed to modern standards. **Caution** is recommended in sounded waters.

148 **Sakkiak Island** *(64°09'N, 76°33'W)* and **Okolli Island**, in the SW approaches to Cape Dorset, are relatively low and smooth. A **rock** with 6 feet (1.8 m) or less over it is 0.3 mile east of Sakkiak Island. Low rocky islets and **rocks** extend west of Okolli Island for 3 miles.

149 **Cape Dorset**, at the south end of **Dorset Island**, is a rounded rocky hill almost 800 feet (244 m) high connected by a narrow isthmus to the main part of the island. Cape Dorset was named by Captain Luke Foxe in 1631 in honour of the Earl of Dorset. Scattered rocky islets lie off the cape. **Eegatuak Hill**, 0.7 mile north of the cape, is a distinctive hill shaped like an inverted bowl. **Apalooktook Point** *(64°14'N, 76°30'W)*, the NE extremity of Dorset Island, has a low red granite summit. There are **cairns** on Eegatuak Hill and Apalooktook Point.

150 An **aeromarine radiobeacon** 1.1 miles SE of Apalooktook Point transmits on 332 kHz with identification YTE (— • — — — •).

151 **Mallik Island**, joined to Dorset Island by a **drying ridge** of sand, **rock** and **boulders**, rises over 700 feet (213 m) in the south part. **West Inlet** is on the SW sides of Dorset and Mallik Islands, and **Tellik Inlet** is on the NE side of Mallik Island and an unnamed island farther NW. Tellik Inlet divides; the west branch joins West Inlet and the east forms **Tellik Bay**. A **depth** of 4 feet (1.2 m) is in the middle of the entrance to Tellik Inlet and **drying reefs** are 0.5 mile inside the inlet. Two **rocks**, positions approximate *(1990)*, with **drying heights** of 6 feet (1.8 m) and 4 feet (1.2 m), are north of the east end of Mallik Island in the entrance to Tellik Inlet. The entrance to **Parketuk Bay**, with a **drying reef** in mid channel, is 2 miles north of Apalooktook Point.

EEGATUAK HILL, DORSET ISLAND,
FROM SE/VUE DU SE

prior to 1965

152 **Caution**. — Four **shoal patches** with least depths from 29 to 45 feet (8.8 to 13.7 m) are from 2.5 to 3 miles SE and east of Sakkiak Island. An **islet awash** at high water, with **depths** under 30 feet (9.1 m) extending east of it for 0.5 mile, lies 0.7 mile NE of Cape Dorset. **Beacon Island** *(64°12'N, 76°26'W)* and an unnamed islet with **shoal water** all around are 1.3 and 2 miles ENE of Eegatuak Hill, respectively. Both are low and are difficult to see beyond 3 miles. **Nascopie Reefs**, an area of **dangerous shoals** and **drying patches**, extend 0.4 mile SE, east and NE from Beacon Island.

153 **Cape Dorset Harbour** *(64°14'N, 76°33'W)*, between the north end of Dorset Island and Mallik Island, has irregular depths and a large **reef**, **partly drying**, in its centre.

154 **Caution**. — A **shoal area** with depths under 6 feet (1.8 m) lies 0.2 mile off the east end of Mallik Island on the north side of the harbour entrance. A **rock** with a depth of 27 feet (8.2 m) lies 0.15 mile SE and a **shoal patch** with a depth of 14 feet (4.3 m) lies 0.6 mile NE from the eastern end of **Sheep Island** *(not named on the chart)* inside the north entrance.

155 The rugged hills of the **Kingnait Range**, which reach almost 1,000 feet (305 m) a few miles north of the harbour, are prominent to the east as far away as 30 to 40 miles.

156 **Kingnait Hill** is SW of Cape Dorset Harbour.

157 The community of **Cape Dorset** *(64°14'N, 76°33'W)*, population 1,148 *(2005)*, is on the SE side of Cape Dorset Harbour. Called **Kingnait** by the Inuit, Cape Dorset is well known to ornithologists as an entry point into Foxe Basin to the nesting grounds of the Snow Goose and its colour variant, or morph, the Blue Goose. The community has a post office, health centre and RCMP detachment. There are two hotels and a bed-and-breakfast to provide accommodation. *First Air* serves Cape Dorset on week days and *Unaalik Aviation* serves Cape Dorset on week days and Sundays.

158 A sand and gravel **landing beach** with fair traction for wheeled vehicles is near the *Hudson's Bay Company* store. It can be worked for two hours before and after high water. **Conspicuous** silver-coloured **oil tanks** are near the beach.

159 The shore manifolds of the **oil pipeline** to the tank farm are on the shore 0.75 mile west of the tip of Apalooktook Point.

160 The **tidal ranges** of large tides are 25 to 28 feet (7.6 to 8.5 m). The **tidal stream** at the landing beach is 1 to 2 knots.

161 **Anchorage** in 25 fathoms (45 m), mud, can be found 0.6 mile north of Apalooktook Point. Tankers anchor 0.1 mile north of the shore pipeline manifolds, with stern lines to the shore, in 10 fathoms (18 m). A vessel 300 feet (91 m) long and drawing 18 feet (5.5 m) has anchored in 10 fathoms (18 m), 0.5 mile north of the settlement over good gravel holding ground.

162 **Caution**. — Shelter is poor in all of these berths. The prevailing winds are NW, 10 to 15 knots, but may be strong in September and October. There is sometimes a heavy swell. Fog is frequent during the navigation season.

163 The average thickness attained by level **fast ice** at Cape Dorset is 137 cm with a record maximum thickness of 183 cm *(1973)*. The area is usually free of sea ice from the end of July until the first half of November.

## Cape Dorset to Lloyd Point

*Charts 5450, 5449*

164 **Caution**. — The coastal waters described in this section have not been surveyed and should not be entered without local knowledge.

165 There is a large unnamed bay between Okolli Island *(64°10'N, 76°36'W)* and King Charles Cape, 18 miles WNW. The bay has a low, very irregular shelving shoreline with numerous islands and islets. **Shoal water** is reported off the NW shore of the bay. Rugged hills 300 or 400 feet (91 or 122 m) high are within a few miles of the sea and rise to greater elevations farther inland. **Shuke Islands**, less than 100 feet (30 m) in elevation, are the outermost islands in this area.

*Chart 7065*

166 **King Charles Cape** *(64°15'N, 77°23'W)*, named by Captain Foxe in 1631, is a low rocky point which rises gently to a rounded promontory 200 feet (61 m) in elevation. There is a group of very low **rocks** and islets close west of the cape.

167 Elevations of 400 to 500 feet (122 to 152 m) close to the shore between King Charles Cape and Lloyd Point, 20 miles NW, are backed a few miles inland by the higher ridges of the Kingnait Range. **Lona Bay** lies midway along this stretch.

168 **Schooner Harbour** *(64°25'N, 77°54'W)* affords **anchorage** for small vessels. The landlocked harbour can be entered through narrow deep channels on each side of the large island in the entrance. There are several islets in the harbour.

169 **Lloyd Point** *(64°26'N, 78°02'W)* is a low point at the end of a ridge which rises gently inland to over 300 feet (91 m). It is the SE entrance point of Foxe Channel. *(Foxe Channel is described in Chapter 8.)*

170 **Mill Island** *(63°58'N, 77°47'W)*, so named by Baffin for the great grinding of the ice in the vicinity, lies 25 miles south of Lloyd Point. A narrow channel separates **Putnam Island**, less than 300 feet (91 m) high, from the east end of Mill Island. **Hurin Throughlet** separates an unnamed island,

CAPE DORSET HARBOUR
APALOOKTOOK POINT

low except for a rounded rocky knoll along the middle of its east coast, from the west end of Mill Island. Both channels contain rocky islets. **Dangerous shoals** are reported off the NW and west coasts of the Mill Island group.

171 Most of the north coast of Mill Island is a series of remarkable terraces rising abruptly from the sea. The south coast is low. All of the islands are barren.



172 **Morrissey Harbour** *(not named on the charts)*, in the middle of the north shore of Mill Island, is an excellent harbour as described in 1927 by George Palmer Putnam. The main entrance is deep but there are strong **tidal streams** and **whirlpools** close outside. Putnam's vessel, the *Morrissey*, a 112-foot (34-m) long former Gloucester schooner, anchored in the SE part of the harbour in 7 fathoms (12.8 m), mud. There was no bottom at 30 fathoms (55 m) close by. **Anchorage** is also available at the north end of the channel between Putnam and Mill Islands; the only approach is from NE.

173 The **tidal streams** run with great strength between Mill Island and the Baffin Island coast to the north. A steep heavy sea results when the stream is opposed by the wind.

*Charts 5449, 5450*

174 **Salisbury Island** *(63°33'N, 77°00'W)*, named by Hudson in 1610, has a very bold NE coast which rises precipitously from the water to 1,500 feet (457 m) and more in places. It appears from NE as a massive wall with a smoothly rounded summit sloping gently seawards at each end. Many small bays notch the cliffs. Moss and grass grow in a number of deep valleys.

175 The SW coast of the island, with elevations of 150 to 300 feet (46 to 91 m), rises gently 5 miles inland to a plateau with elevations of 500 to 700 feet (152 to 213 m). Rivers rush down steep-sided valleys and enter the sea at the heads of narrow inlets. There are groups of **rocks** in places offshore.

176 The NW coast at Salisbury Island, with elevations of 100 to 200 feet (30 to 61 m), breaks into rugged islands of the same elevation. These islands are inhabited by large herds of walrus. The SE coast is low with islets and **rocks**; **foul ground** extends 2 miles offshore.

177 **Pricket Point** *(63°27'N, 76°32'W)*, at the east end of Salisbury Island, is low but elevations of 500 feet (152 m) occur 1 mile inland.

178 **Trinitie Rock**, elevation 40 feet (12 m), and **Minion Rock**, elevation 10 feet (3 m), lie 7 miles SE and 5 miles south of Pricket Point. **Submerged rocks**, positions approximate and doubtful, are 1.6 miles SW of Trinitie Rock and 4 miles SW of Minion Rock.

179 A long inlet can be entered between Pricket Point and a cape *(63°31'N, 76°35'W)*, 800 feet (244 m) high, 4 miles NNW. This inlet is reduced to 0.5 mile in width by an island 3 miles within the entrance. The inlet continues for 3 miles between smooth rocky shores, over 300 feet (91 m) high, almost to the SW coast of Salisbury Island.

180 An inlet with two islands in the entrance is on the north coast near the NW end of Salisbury Island. There are channels on each side of the eastern island and there is a narrow belt of **mud flats** at the head of the inlet.

181 In 1960 the *M.V. Arctic Sealer*, drawing 15 feet (4.6 m), found **anchorage** in **Edaloh Inlet** *(63°37'N, 77°24'W)* in 10 fathoms (18.3 m), mud, halfway up the inlet on the north side. Fresh water was obtained from a nearby stream. This inlet, because of its high shores, provides good shelter except to the west. Strong **tidal streams** flow through the channel between the west end of Salisbury Island and the off-lying islands and across the mouth of Edaloh Inlet. These currents presented little problem as there is ample manoeuvring room for small ships in the entrance and the flow inside the inlet is negligible.

182 **Nottingham Island** *(63°19'N, 78°00'W)* lies on the north side of the main shipping channel into Hudson Bay.

183 **Fraser Island** *(63°29'N, 78°28'W)*, 300 feet (91 m) high, is separated from the NW corner of Nottingham Island by a narrow channel. There are several islets lying offshore. The land on both sides of the channel between Fraser and Nottingham Islands is high at the NE end of the channel becoming lower towards the SW. Westerly seas break on the **reefs** and low points at the SW end near high water.

184 A small cove on the south shore at the east end of the channel described above provides **anchorage** for small vessels over mud, sand and shell, with good shelter from all except NE winds and seas. A small river flows into the head of the cove generating a strong current. **Fresh water** can be obtained here. A sandy beach provides a good landing place at all stages of the tide.

185 The north coast of Nottingham Island is low to the west, increasing in elevation towards the east where it rises abruptly in cliffs and hills to 600 feet (183 m). The NE coast is high and bold, reducing in elevation towards the east end of the island. The SE coast of Nottingham Island is 100 feet (30 m) or less in elevation and infested with rocks, shoals and islets.

186 Strong **tide rips** and **overfalls** occur in the channel between Nottingham and Salisbury islands.

187 A wide inlet *(63°26'N, 77°46'W)* at the north end of the NE coast narrows rapidly within its entrance to less than 0.2 mile in width. The inner portion has rocky islets.

188 **Barry Rock**, with 6 feet (1.8 m) or less over it, is 7 miles east of the east end of Nottingham Island; its position is doubtful.

189 **Port de Boucherville** *(63°11'N, 77°32'W)*, a small inlet near the SE tip of Nottingham Island, was the base of a Canadian Government expedition in 1884-86. The entrance is 0.25 mile wide between low rocky

peninsulas. Depths in the outer part are from 4 to 8 fathoms (7.3 to 14.6 m). A narrows is formed 0.5 mile within the entrance by **shoals** extending from both shores. **Anchorage** may be obtained in a very restricted area inside the narrows in 4 fathoms (7.3 m), mud. The inlet is reported to be unsafe to enter for a vessel of 3,500 t.

190 To the SW the low coast, bordered by a narrow belt of rocks and reefs, rises gently from the sea to elevations of 400 and 500 feet (122 and 152 m) 5 miles inland.

191 *Nottingham Island* **light** *(2554) (63°05'N, 77°57'W)* is on the south end of the island.

192 A **racon**, identification Morse code letter "N" (— •), is at the *Nottingham Island* light structure.

193 A bay entered NW of *Nottingham Island* light has a number of islets along its north shore connected to the main shore by **drying flats**. The bay divides into two inlets 0.7 mile within the entrance; the northern of these dries completely but the eastern inlet can be navigated by small craft for 0.5 mile and has a sand foreshore which has been used for landing.

194 Vessels have found unsheltered **anchorage** off the above-mentioned outer bay in from 7 to 15 fathoms (13 to 24 m).

195 A strong easterly **current** may be encountered in the vicinity of the *Nottingham Island* light-structure, even during the flood tide, and **tide rips** form off the point south of the light-structure. These appear on radar as an extension of the point.

# Hudson Bay — East Side




## General

*Chart 5002*

1 **Hudson Bay** is a large inland sea in the NE part of the Canadian mainland, accessed through Hudson Strait. This chapter covers the east coast from Pointe Taliruq to Pointe Louis-XIV.

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

2 Islands, islets and **shoals** are found more than 100 miles off the east shore of the bay. Patches with depths of 10 fathoms (18.3 m) are found between Mansel and Coats Islands; **isolated shoal areas** with depths of 14 to 20 fathoms (25 to 37 m) are in the NE and south-central parts of the bay and up to 60 miles off the SW and west shores. There are no known mid-bay depths under 10 fathoms (18.3 m).

3 **Firing practice and exercise areas** have been established in Hudson Bay for rocket-firing purposes *(for details see the annual edition of Canadian Notices to Mariners)*. Mariners are advised to contact *Canadian Coast Guard* radio station *MCTS Iqaluit (see Radio Aids to Marine Navigation — Atlantic, St. Lawrence, Great Lakes, Lake Winnipeg and Eastern Arctic)* before passage through the bay.

## Pointe Taliruq to Cape Smith

*Charts 5449, 5412*

4 **Caution**. — Much of the area covered by *Chart 5449*, particularly the inshore waters, is **not surveyed**. Much of the charted hydrographic information on *Charts 5449* and *5412* is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended in sounded waters.

5 The coast is low and regular with no outstanding features between Pointe Taliruq *(62°22'N, 78°05'W) (described in Chapter 2)*, and Kovik Bay, 43 miles south.

*Chart 5412*

### Ice Harbour to Pointe Bernier

6 **Ice Harbour**, 3 miles SSW of Pointe Taliruq, has **foul ground** off the entrance and has a **drying flat** at its head.

7 **Caution**. — **Depths** in the harbour are not known.

8 **Peck Inlet** lies 3.5 miles SSW of Ice Harbour. The inlet has not been fully surveyed but **rocks** and **shoal depths** of 2 fathoms (3.7 m) are up to 2 miles off its entrance.

9 There is good **anchorage** for small craft at the head of Peck Inlet.

*Chart 5449*

10 **Pointe de Sainte-Hélène** is a slight projection 7 miles south of Peck Inlet.

11 **Kovik Bay** *(61°30'N, 77°44'W)*, 30 miles farther SSE, has many islands and **shoals**. **Rivière Kovic**, **shallow** and rapid, flows into the bay through rounded rocky hills less than 100 feet (30 m) high. **Pointe Bernier** is a low flat point at the south entrance of Kovik Bay.

### Offshore islands

12 **Mansel Island** *(62°04'N, 79°48'W)* is 32 miles west of the mainland coast. The island is composed of limestone gravel ridges from 10 to 40 feet (3 to 12 m) high on the west side and 100 feet (30 m) high on the east side. **Swaffield Harbour**, a cove in the north side of the island, was the site of a *Hudson's Bay Company* post.

13 **Caution**. — A **boulder reef** extends 1 mile NW from the north point of Mansel Island and **dangerous rocks** are close off the north shore. Give this shore a berth of 2 miles.

14 **Caution**. — **Cape Acadia**, the south end of Mansel Island, has **rocky reefs** for 5 miles offshore and should be given a berth of at least 7 miles. For almost 20 miles NW of Cape Acadia, the shore is bordered by a **shoal bank** extending up to 5 miles offshore.

15 The **tidal ranges** of mean and large tides are 2.7 and 4.1 feet (0.8 and 1.4 m) near Cape Acadia.

16 *Mansel Island* **light** and **racon** *(2550)* are at the north end of the island.

17 *Cape Acadia* **light** *(2551)* is shown from the south end of Mansel Island.

18 **Anchorage** with good holding in a heavy SW gale was obtained off the north end of Mansel Island, in 21 fathoms (38 m), with *Mansel Island* light bearing 252° and the east side of the island bearing 144°. **Anchorage** has also been obtained 1.5 miles off the north end of the island, 1.5 miles west of the boulder reef, in 7 fathoms (12.8 m), sand.

19 **Anchorage** in NE gales may be found NW of Cape Acadia in 30 fathoms (55 m). **Anchorage** has also been found 1.5 miles east of Cape Acadia in 15 fathoms (27.4 m). Vessels have found **anchorage** off the south point of the river 24 miles NNE of Cape Acadia, in depths of 16 fathoms (30 m).

20 **Currents** along the east side of Mansel Island have a dominant southerly flow.

21 A **magnetic anomaly** exists north of Mansel Island.

22 **Coats Island** *(62°35'N, 83°00'W)*, 60 miles WNW of Mansel Island, is low and flat with elevations less than 100 feet (30 m) except near Cape Pembroke.

23 **Cape Pembroke**, at the NE end of Coats Island, rises rapidly to 500 feet (152 m) on its north side and reaches 600 feet (183 m) 2 miles inland. It makes an excellent **landmark**, visible for many miles.

24 *Cape Pembroke* **light** *(2548)* is shown from the NE end of Coats Island.

25 **Caution**. — **Isolated** 10-fathom (18.3-m) **shoal patches** are near mid-channel, 27 miles SSE and 42 miles SE of *Cape Pembroke* light.

26 **Cairn Cove**, 3 miles south of *Cape Pembroke* light, is a small cove with a **conspicuous** cairn on its SE shore. It is the only harbour on Coats Island.

27 **Anchorage** with good holding, but of restricted area, is available in 8 fathoms (14.6 m) in the middle of Cairn Cove.

28 **Caution**. — The harbour is unusable in winds from NNE to SE because of **heavy swell**.

29 **Carys Swan Nest** *(62°10'N, 83°08'W)*, the SE end of Coats Island, is composed of limestone gravel ridges, not over 50 feet (15 m) high, with many freshwater lakes. The west shore of the point is swampy above the high water line.

30 **Caution**. — The west shore is bordered by a **boulder bank** that dries for 0.5 mile offshore and has depths of less than 6 feet (1.8 m) 2 miles south of the point. The 3 fathom (5.5 m) line is 0.5 mile farther off and the point should not be approached closer than 5 miles. The east shore

of the point is much cleaner; the **boulder bank** extends only a short distance offshore.

31 *Coats Island* **light** and **racon** *(2549)* are on Carys Swan Nest.

32 **Shoran Bay** is between Carys Swan Nest and **Cape Southampton** at the low SW end of Coats Island.

33 *The west and north sides of Coats Island are described in Chapter 6.*

## Pointe Bernier to Cape Smith

34 The coast between Pointe Bernier and Kettlestone Bay *(61°12'N, 77°44'W)*, 14 miles south, is low with occasional dark ridges of rock rising a few feet above the terrain. The shores of the wide, unsheltered bays have boulder-covered points and sandy heads with the odd outcrop of rock. There are a few boulder-covered islands close offshore.

35 **Pointe du Profond** is a **conspicuous hill**, 50 feet (15 m) high, 0.5 mile off the mainland on the end of a narrow neck of boulders. This is the north entrance point of **Kettlestone Bay**. The point has been used by Inuit for seal hunting in the spring.

36 Another **conspicuous hill** is 2.6 miles NE of Pointe du Profond. This hill, 211 feet (64 m) high, is the highest in the vicinity.

37 **Shelter** for small craft can be found at the head of Kettlestone Bay in the mouth of a small river.

38 **Pecten Harbour** *(61°02'N, 77°50'W)*, small and circular, is partly protected by a ring of boulders.

39 **Cape Smith** *(60°43'N, 78°43'W)*, the west end of **Smith Island**, is a prominent landmark 32 miles SW of Pecten Harbour. Smith Island is a rugged mass of dark green to black rock rising to elevations of 800 to 1,000 feet (244 to 305 m). A few narrow sheltered valleys running parallel to the long axis of the island support an abundant growth of grasses, heather, arctic flowering plants and some arctic willows.

40 **Caution**. — **Shoals** of 14 to 20 fathoms (26 to 37 m) are 60 to 90 miles west of Cape Smith.

# Cape Smith to Akulivik

*Chart 5512*

41 **Babs Bay**, a large, well-protected bay on the south side of Smith Island, is sheltered on its south side by a narrow peninsula 3 miles long. A sand and gravel beach, at the mouth of a brook at the head of the bay, has provided a good landing place for small craft.

42 A cove on the south side of Smith Island, separated from Babs Bay by low land containing two lakes, was the site of the former *Hudson's Bay Company* post of *Cape Smith*. The head of this cove is sandy with a few stones. Small vessels can obtain **anchorage**, in 9.8 m of water, but the cove is exposed to SW winds.

43 Babs Bay provides sheltered **anchorage** with good holding in clay and sand.

44 The navigable channel from southward, between Smith Island and the mainland, ends at **Pointe Migeon**. This is the north entrance point to **Baie Akulivik** *(not named on the chart)*.

44.1 There is a strong SW ebb **current** off Pointe Migeon and a moderate to strong NE set on flood tides.

45 **Caution**. — Beyond this point, the northern section of the channel is **obstructed** by numerous **rocks** and **reefs** and is navigable only by small craft.

46 The south entrance point of Baie Akulivik is **Pointe Akulivik**.

47 **Caution**. — **Shoals**, **reefs** and above-water rocks also **obstruct** the centre of the south entrance to the channel to Baie Akulivik. A **route** between these obstructions and the east end of the peninsula on the south side of Babs Bay provides access with depths of 17 to 25 m. Follow the charted track to Baie Akulivik. The minimum depths are 12 m in the channel and 10 m in the entrance to Baie Akulivik.

48 **Caution**. — Deeper water is available elsewhere in the channel but deviation from the charted track should not be attempted without **local knowledge**.

49 The **current** in the channel is estimated to be 3 to 4 knots at all times except for periods of approximately 45 minutes at slack water.

50 The **tidal ranges** of mean and large tides at Babs Bay and Akulivik are 0.3 and 0.5 m.

51 **Monts d'Youville** is a prominent range of dark green rock, rising from nearly flat land on both sides. A number of sharp, narrow, parallel ridges start more than 40 miles inland to the NE and the range terminates on Smith Island. The highest peaks are snow-capped. **Rivière Illukotat** flows parallel to Monts d'Youville; it enters the sea in the inlet south of Pointe Akulivik.

52 The settlement of **Akulivik** *(60°49'N, 78°10'W)*, population 472 *(2001)*, was established in 1977 on the south side of Baie Akulivik. The community has a post office, police station and a health centre that provides medical and dental care. There is a store in the settlement and a *Nunavik Cooperative Hotels* facility provides accommodation. *Air Inuit* provides flights seven days a week.

52.1 Three gravel and rubble breakwaters at Akulivik provide shelter for a landing ramp and a small-craft harbour. Privately maintained lights mark the breakwaters and entrance.

## Cape Smith to Cape Dufferin

*Charts 5449, 5512*

53 Between Cape Smith and Cape Dufferin, 125 miles south, the coast is low and marshy with many bays, islands, **banks** and **shoals**.

### Pointe Akulivik to Povungnituk Bay

54 **Knight Harbour** is 1.8 miles SE of Pointe Akulivik. **Île Gobin**, elevation 30 m, forms the south side of Knight Harbour.

55 **Anchorage**, in 25 to 30 m over a mud bottom, can be found in the bay east of the NE end of Île Gobin. A channel, with numerous **shoals** on each side, leads to the anchorage. The channel has depths of 15 to 42 m and a minimum width of 0.25 mile but should not be attempted without local knowledge. There is also **anchorage** at the head of the harbour in an average depth of 13 m. Knight Harbour, except for the anchorage NE of Île Gobin, is exposed to the SW.

*Chart 5449*

56 **Pointe Morin**, a low point 3 miles east of Île Gobin, is the south entrance point of **Rivière Chukotat**.

57 **Mosquito Bay** *(60°43'N, 77°53'W)* is a ragged indentation between Île Gobin and **Pointe Demers**, 10 miles SE. **Rivière Iktotat** enters a long inlet in the east part of the bay. The mouth of this inlet is **obstructed** for 3 miles by numerous small islands that are the tops of **submerged ridges**. The depth between the ridges is a uniform 5 fathoms (9.1 m). The inlet becomes gradually shallower towards the head.

58 **Korak Bay** is obstructed by islands and **reefs**. Low rounded hills form the south shore. **Rivière Korak** flows into the head of the bay.

59 The north and south shores of **Neakongut Bay** *(60°31'N, 77°38'W)* are bordered by islets and **rocks** for up to 3.5 miles offshore. **Rivière Sorehead** is navigable by small craft as far as **rapids** 12 miles upstream from the head of the bay. **Pointe Cusson** is the south entrance point of the bay.

60 **Thompson Harbour**, filled with islets and **rocks**, is sheltered by **Magnet Island** to the north and by two unnamed islands to the west.

61 A very strong **magnetic anomaly** is reported in the vicinity of Magnet Island.

62 **Pointe Coutlée** is 5 miles south of Thompson Harbour.

63 A group of three **radar conspicuous islets** are within 7 miles NW and 9 miles WNW of Pointe Coutlée. A **rock awash** lies 5.5 miles west of Magnet Island.

*Charts 5510, 5449*

64 **Caution**. — Much of the area shown on *Chart 5510* is **not surveyed** and some of the hydrographic information is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended when navigating in sounded waters.

65 **Povungnituk Bay** *(59°55'N, 77°40'W)*, entered between **Pointe Dufrost** and **Pointe aux Écueils**, 22 miles SSW, has irregular shores mostly under 30 m in elevation. There are numerous low islands, islets and **rocks** offshore.

66 **Shallow Bay** and **Reef Bay** are on the SE and south shores of Povungnituk Bay. **Rivière Kogaluc** flows through **Lac Kogaluc** into the head of Reef Bay.

*Chart 5510*

### Approaches to Puvirnituq (Povungnituk)

67 **Uvillutuuq Islands** and **Qairtuinnaq Rock** are 5 and 8 miles NNE of Pointe aux Écueils.

68 **Caution**. — **Dangerous rocks** are up to 6.5 miles west and WNW of Qairtuinnaq Rock and **uncharted dangers** may exist.

69 **North Kopak Island**, elevation 5 m, and **South Kopak Island** *(60°00'N, 77°44'W)* lie 5 miles SW of Pointe Dufrost. **Long Reach Island**, elevation 2 m, lies 3 miles farther SE.

71 A **beacon**, elevation 22 m, is on Long Reach Island; the island has been detected at 10 miles. The condition of the Long Reach Island beacon is unknown *(2005)*.

72 **South Island**, **Rock Island** and **Inooksulik Island** lie 3, 4, and 6 miles eastward of Long Reach Island.

73 **Caution**. — The area inshore of Inooksulik Island is scattered with **dangerous rocks**.

74 **Rivière de Puvirnituq (Povungnituk)**, at the head of Povungnituk Bay, is entered between **Pointe Big Finger** *(60°01'N, 77°20'W)* and **Pointe Fish**; both points can be identified easily by their **conspicuous boulders**. **Innelatevik Island**, elevation 24 m, is the largest of three islands lying off the river mouth.

75 **Île Fat**, **Île Big (Island)** and **Île Inussuliapik (Cairn)** lie between 2 and 3 miles inside the river mouth. The river is **shoal** above these islands with many islands and **rocks**.

76 **Caution**. — **Rocks** with depths of 0.3 and 2.3 m, lying off Pointe Fish and Pointe Big Finger, **obstruct** the entrance to Rivière de Puvirnituq. A depth of 8 m can be maintained through the river entrance to the anchorage off Île Fat.

77 A series of four **leading beacon ranges** mark the approach and entrance to Rivière de Povungnituk. Each **beacon** is a square skeleton **tower** carrying a trapezoid fluorescent-orange **daymark** with a black vertical stripe.


LANDING AREAS
PLAGES DE DEBARQUEMENT
FAT ISLAND
BIG ISLAND
POVUNGNITUK

78 The front beacon of the outer range, on an island 0.2 mile SE of Innelatevik Island, is 7.6 m high with an elevation of 15 m. The rear beacon, bearing 046½°, 1.38 miles from the front beacon, is 15 m high with an elevation of 42 m.

79 The front beacon of the second range, 0.23 mile SSE of Pointe Fish, is 9.1 m high with an elevation of 15 m. The rear beacon, bearing 080½°, 0.31 mile from the front beacon, is 6.1 m high with an elevation of 24 m.

80 The front beacon of the third range, 0.38 mile NW of Pointe Big Finger, is 15 m high with an elevation of 24 m. There is a **racon** on this tower, with identification Morse code letter 'P' (• — —•). The rear beacon, bearing 026°, 0.28 mile from the front beacon, is also the rear beacon of the first range.

81 The front beacon of the inner range, on an islet close west of Île Big, is 7.6 m high with an elevation of 10 m. The rear beacon, bearing 074½°, 0.36 mile from the front beacon, is 6.1 m high with an elevation of 19 m. Both towers of the inner range are topped with radar reflectors.

82 Follow the charted tracks to enter Povungnituk Bay and Rivière de Puvirnituq.

83 The **least depths** along the tracks are 12 m in the approaches and outer part and 8.3 m in the inner part of the bay, ESE of Inooksulik Island *(59°59'N, 77°27'W)*.

84 **Caution**. — The bottom is irregular and **rocks** and **shoals** lie close on either hand.

85 **Anchorage** has been obtained in a position bearing 195°, 3 miles distant from South Island, in 30 m with good holding but with no shelter. In 1976, a vessel anchored several times in this berth in northerly winds of up to 35 knots.

86 The settlement of **Puvirnituq (Povungnituk)** *(60°02'N, 77°16'W)*, population 1,287 *(2001)*, is on the north shore of Rivière de Puvirnituq at the head of Povungnituk Bay. The community has a post office, hospital and police station. There are a variety of retail stores and accommodation is available at 3 hotels. *Air Inuit* provides flights 7 days a week.

87 **Anchorage** can be obtained between the river mouth and the settlement and also east of Île Fat.

89 SE **winds** tend to decrease the **tidal range** at Puvirnituq while SW winds increase it. The **current** in the river is strong.

90 A privately maintained **aeromarine radiobeacon** near the settlement transmits on 338 kHz with identification YPX (— • — — • — — • — • • —).

91 **Jetties** for small craft, with 0.9 to 1.5 m (3 to 5 ft) of water alongside, are near the settlement.

*Chart 5449*

## Offshore islands

92 **Ottawa Islands** *(59°30'N, 80°20'W)* are a group of bare rugged islands of black volcanic rock lying 65 miles off the east shore of Hudson Bay.

93 **Bronson Island** and **Booth Island**, at the north end of the group, have elevations of 400 and 500 feet (122 and 152 m). The unnamed island close SE of Bronson Island is 200 feet (61 m) high.

94 **Gilmour Island** rises to 1,130 feet (344 m) at **Mount Allan**. **Murray Harbour**, on the south side of the island, was frequently used by whaling ships in the 19th and early 20th centuries; it is surrounded by high hills. A stream flowing through a rounded valley empties at a sand beach at the head of the harbour. A bay on the NE side of the island is reported to be a good landing place. An islet and two dry rocks lie 2 and 5 miles west of the SW end of Gilmour Island.

95 **Perley Island** *(59°40'N, 80°16'W)*, elevation 740 feet (226 m), **Pattee Island** and **J. Gordon Island**, both 400 feet (122 m) high, lie SW of Gilmour Island.

96 **Eddy Island**, elevation 500 feet (152 m), and **House Island**, elevation 232 feet (71 m), are the largest islands of the chain extending SSW of Perley Island.

97 **Waters Island**, elevation 215 feet (66 m), is the only named island of a small group 15 miles south of House Island. The northernmost island of the group has an elevation of 200 feet (61 m).

*Charts 5705, 5449*

98 A small unnamed island *(58°52'N, 80°25'W)*, elevation 120 feet (37 m), with two dry rocks close south, lies 13 miles SE of Waters Island. Two islets, existence doubtful, are 12 miles SSE and 11 miles SSW and another unnamed island is 16 miles SW of Waters Island.

99 **Farmer Island** *(58°25'N, 80°47'W)*, of barren grey rock with a few shingle beaches, has a bay in the NE part of the island that is partly protected by smaller islands.

100 There is a **radar reflector** fitted to a skeleton **tower** 35 feet (11 m) high, with an elevation of 65 feet (20 m), on Farmer Island.

101 **Surge Islands**, actually two islets, and a **shoal rock** are 12 miles south of Farmer Island. Two **banks**, one whose position is approximate, with depths of 15 and 12 fathoms (27 and 22 m), are 14 miles NE of the island.

102 **Midbay Shoal**, with a depth of 16 fathoms (29 m), lies near the centre of Hudson Bay, 140 miles west of Farmer Island.

*Chart 5449*

## Povungnituk Bay to Cape Dufferin

103 The coastal **current** between Povungnituk Bay and Cape Dufferin, 95 miles SSW, flows constantly northward.

104 **Caution**. — A **rock** *(59°14'N, 79°00'W)* with a depth of 38 feet (11.6 m), reported in 2003, lies 24 miles offshore.

105 **Pointe Boucher** *(59°38'N, 77°48'W)*, 27 miles SW of Povungnituk Bay, is the north entrance point of **Shoal Harbour**. The harbour is filled with islets and rocks; **Rivière Polemond** flows into the head. **Pointe Bourjoli**, 14 miles SSW, is the end of a low peninsula forming the north side of **Kogaluk Bay**. This bay is also filled with islets and rocks. **Checkered Islands** are a chain of four islands extending west from Pointe Bourjoli. **Pointe Pamiuq** projects from the east shore of Kogaluk Bay.

106 **Pointe Despins** *(59°10'N, 78°11'W)* is the north entrance point of **shallow**, island-filled **Mistake Bay**. **Rivière Koktac** enters the sea 2 miles south of this bay.

*Chart 5705*

107 **Caution**. — Most of the area covered by *Chart 5705* is **not surveyed** and much of the charted hydrographic information is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended in sounded waters.

108 **Elsie Island** *(58°50'N, 78°55'W)*, 200 feet (61 m) high and composed of granite, is the largest of a cluster of islands and islets lying up to 20 miles off the mainland shore. This chain includes the two **Komaluk Islands** and **Peckham Island**. There is a good harbour for small craft in the middle of the west side of Elsie Island with depths of 15 feet (4.6 m) in the entrance and 36 feet (11 m) inside.

109 A **beacon** with three fluorescent-orange rectangular **daymarks** and a **radar reflector** on a skeleton **tower** 30 feet (9.1 m) high, with an elevation of 76 feet (23 m), is on an islet 6 miles west of Elsie Island. The north end of the islet rises to an elevation of 65 feet (20 m).

110 **Alle Harbour**, on the mainland shore, is **obstructed** by many **rocks**. The harbour is sheltered to the west by **Staff Island**. **Commodore Island** *(58°47'N, 78°40'W)* and **Inman Island** are SW and south of Staff Island; all of the islands have elevations less than 100 feet (30 m). **Levy Island** is the only named island of a large group lying between Inman Island and **Promontoire Portland** *(58°41'N, 78°33'W)*, 4 miles SSE. The promontory, with an elevation of 100 feet (30 m), separates **Beartrack Bay** from **Portage Bay**. Both bays are full of islets. **Péninsule Bates**, 200 feet (61 m) high in its south part, forms the west side of **Witch Bay**. **Captain Island**, **Ward Island**, **Cox Island** and **Whitney Island**, all with elevations of 100 feet (30 m), lie off the west side of Péninsule Bates.

111 **Five Mile Inlet** is 3 miles SE of Péninsule Bates.

112 **Anchorage** for small craft can be found in a small bay on the SE side of the entrance to Five Mile Inlet.

113 **Cape Dufferin** *(58°38'N, 78°42'W)* is the NW end of **McCormack Island**. The island has an elevation of 100 feet (30 m).

## Cape Dufferin to Nastapoka Islands

*Chart 5003*

114 The coast between Cape Dufferin and Pointe Louis-XIV, 240 miles south, forms a large semi-circular bight containing several groups of offshore islands. Belcher Islands are the largest. A series of islands, the Hopewell and Nastapoka groups, borders most of the northern two-thirds of the coast. These are totally different in origin and appearance from the mainland and, except for one 40-mile gap, provide a sheltered coastal channel for small craft. High steep land rises 1,000 to 2,000 feet (305 to 610 m) behind the mainland shore.

*Chart 5705*

### Cape Dufferin to Inukjuak

115 **Hopewell Islands**, with a maximum elevation of 200 feet (61 m), lie parallel to the coast for 50 miles SE of Cape Dufferin; the islands are long and narrow. On the east side, the larger islands have steep but often broken cliffs; on the west side they have gradual slopes. **Hopewell Sound** extends between Hopewell Islands and the mainland.

116 **Moore Island** *(58°33'N, 78°32'W)*, separated from McCormack Island by a very narrow passage, has an elevation of over 100 feet (30 m) in the central part. An islet with an elevation of 4 feet (1.2 m), existence doubtful, was reported 2 miles WSW of the south end of Moore Island.

*Chart 5471*

### Approaches to Inukjuak

117 **Caution**. — Some of the areas covered by *Chart 5471* are **not surveyed** and should not be entered without local knowledge.

118 The land behind the coast consists of low rolling hills of mostly bare rock.

119 **Young Island** *(58°30'N, 78°21'W)* is separated from **Murray Island**, close SE, by a passage suitable only for small craft. **Kit Island** is almost joined to Murray Island.

120 **Caution**. — A **rocky shoal**, with a least depth of 2 feet (0.6 m), lies in the middle of Hopewell Sound 0.8 mile ENE of Murray Island. An **isolated** breaking **rock** is 1 mile NE of Murray Island, in unsounded waters. **Shoal water** extends from **Patterson Island** more than halfway to Kit Island.

121 There is a **beacon** on the SE point of Patterson Island. The condition of this beacon is unknown *(2005)*.

122 **Bluff Island** *(58°25'N, 78°09'W)*, **conspicuous**, has high dark cliffs rising to a flat top. A **conspicuous rock** is on the west end of the island.

123 **Caution**. — **Shoals** with depths less than 6 fathoms (11 m) are in mid-channel north of Bluff Island.

124 **Algerine Channel**, between Patterson and Bluff Islands and **Harrison Island**, is obstructed on its south side by **Fairway Island** and two unnamed islands.

125 **Caution**. — **Breaker Shoal**, **obstructing** the centre of the channel with a least depth of 10 feet (3 m), is an extensive **shoal area** that breaks heavily in a moderate sea. **Shoal water** extends up to 0.2 mile west and north of Fairway Island and a 21 foot (6.4-m) **patch** lies 0.6 mile SW of the island.

126 **Palisade Cliffs**, prominent cliffs on the north coast of Harrison Island, have a **cairn** on the summit. There are several islands and shoals off the SW side of Harrison Island; vessels should remain outside the 20 fathom (37 m) line. **Fraley Island** is separated from the SE end of Harrison Island by a narrow deep channel.

127 **Hopewell Narrows** *(58°23'N, 78°04'W)*, between Harrison Island and the mainland, is only 60 feet (18 m) wide and is partly **obstructed** by large **boulders**. A transit of the narrows was made at high water by a launch drawing 3 feet (0.9 m). **Rivière Kongut** enters Hopewell Sound 2 miles ENE of the narrows.

128 **Sheep Island** *(58°26'N, 78°08'W)*, bare and rocky and bordered by **shoal water** except off its east point, lies 1 mile NE of Bluff Island.

129 **Rivière Innuksuac**, flowing at 4 knots, empties into Hopewell Sound 0.7 mile NE of Sheep Island. The river mouth is **shallow** with depths of 2 to 3 feet (0.6 to 0.9 m) and is **obstructed** by a central **drying bank**. The river flows over a series of **rapids** 2 miles upstream from the mouth.

130 **Caution**. — **Channels** in the river mouth change from year to year. **Boulders**, which could be deposited or moved by ice during break-up, are difficult to see due to discolouration of the water.

131 **Caution**. — **Seaplanes** land at the mouth of the river.

132 **Pointe du Poste** forms the NW side of the entrance of Rivière Innuksuac. A **drying sand spit** extends 0.2 mile SW and **shoal rocks** extend 0.1 mile SE of the point.

133 The **dome** of an inactive meteorological station, **radio masts** near the settlement and a **cairn** 1.3 miles east of the settlement are **conspicuous**. Red air obstruction **lights** on the masts are **conspicuous** at night.

134 The settlement of **Inukjuak (Inoucdjouac or Port Harrison)** *(58°27'N, 78°06'W)*, population 1,294 *(2001)*, is on the mainland shore of Hopewell Sound at the mouth of Rivière Innuksuac. The community has a post office, a police station and a health clinic with medical and dental facilities. There are two retail stores and a convenience store. Accommodation is provided by two hotels and *Air Inuit* provides flights seven days a week.

135 The average thickness attained by smooth **fast ice** at Inukjuak is 219 cm with a record maximum thickness of 284 cm *(1972)*. Break-up normally begins during the second half of May with the river clearing of ice by the third week of June. Freeze-up usually begins during the last week of October and complete ice cover is in place by the first of December. Three to four weeks variation in break-up and freeze-up dates can occur.

136 The **tidal ranges** of mean and large tides at Inukjuaq are 1.1 and 2.1 feet (0.3 and 0.4 m).

137 A privately maintained **aeromarine radiobeacon** near the settlement transmits on 396 kHz with identification PH (• — — • • • • •).

138 **Anchorage** can be obtained in 15 fathoms (27 m), clay and sand, 0.3 mile SE of Sheep Island and in 11 fathoms (20 m), clay, north of Sheep Island. There is little protection from southerly winds in either berth.

139 Small vessels can find **anchorage** in the bay 1 mile west of the settlement. **Fresh water** can be obtained from a nearby stream using 1,000 feet (305 m) of hose. Two substantial rubble breakwaters off the east entrance point of the bay provide shelter for a small-craft harbour with a floating wharf, a landing ramp and a concrete wharf with a small crane. There are privately maintained lights marking the breakwaters and entrance. Small craft can find good **anchorage**, out of the current, in a small cove on the west side of the point 0.3 mile NNE of the church at the settlement.

140 A good **landing beach** near the settlement can be used at all stages of the tide. Roads are sand, with poor traction. Cargo is shuttled to shore by small craft.

141 An **overhead cable** with a clearance of 20 feet (6.1 m) crosses the river 0.2 mile north of the church.

*Chart 5705*

## Inukjuak to Rivière Nastapoka

143 The southern islands of the Hopewell group are **Frazier Island** *(58°19'N, 77°53'W)*, **Drayton Island**, **Leonard Island**, **Hotchkiss Island** and **Bartlett Island**. All are similar in appearance with high east sides and elevations of 100 to 200 feet (30 to 61 m).

144 **Porpoise Cove** is on the mainland coast east of Frazier Island. **Pointe Normand** is on the mainland east of Bartlett Island.

145 **Success Island** *(58°04'N, 78°08'W)* and several islets are 17 to 18 miles west of Bartlett Island.

146 **Caution**. — A **shoal rock**, position approximate, lies 23 miles west of Bartlett Island. Discoloured water and a **shoal depth** of 7 fathoms (12.8 m) are 8 miles farther NW.

147 The coast is rugged and rocky between Pointe Normand and Cotter Island, 27 miles SSE, with ragged hills 1,000 feet (305 m) high a few miles inland.

148 **Landlocked Harbour** *(58°01'N, 77°12'W)*, 14 miles SE of Pointe Normand at the mouth of **Rivière Kikkerteluc**, offers good and sheltered **anchorage**. The river mouth is **shallow**.

149 **Bell Harbour** is 4 miles farther SSE; this inlet is **not surveyed**. An island, existence doubtful, is 10 miles WSW, and a 15 fathom (27 m) depth, reported in 1973, is 9 miles SSW of Bell Harbour.

## Offshore Islands — Marcopeet, Sleeper and King George Islands

150 **Marcopeet Islands** *(57°54'N, 79°39'W)* are a chain of barren islands lying 80 miles off the east side of Hudson Bay. The largest island is 50 feet (15 m) in elevation; half the surface is shingle, the remainder rock. Two islets lie 9 miles north of Marcopeet Islands.

*Charts 5705, 5505*

151 **Sleeper Islands**, 11 miles south of Marcopeet Islands, form a chain of islands and rocks 26 miles long.

152 **Caution**. — **Rocks** and **shoal water** lie midway between Marcopeet and Sleeper Islands.

153 **Kidney Island** *(57°33'N, 79°45'W)* is the largest of the Sleeper Islands. It has a sheltered harbour suitable for small vessels, close off the NE tip, inside a line of small islands. Small craft can find shelter among some small islands extending north of Kidney Island; the northernmost of these is 9 m (30 ft) high. **Reefs** and **drying shoals** are up to 4 miles east of Sleeper Islands.

154 A **radar reflector** on a skeleton **tower** is on the island close south of Kidney Island.

*Chart 5505*

155 **Caution**. — Some of the area covered by *Chart 5505* is **not surveyed** and much of the hydrographic information is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended when navigating in sounded waters.

156 **King George Islands** are midway between Sleeper Islands and the east shore of Hudson Bay. The group extends 25 miles SSE from the farthest north island *(57°33'N, 78°34'W)*.

157 **Beach Island** *(57°30'N, 79°03'W)*, the farthest NW of the group, is 9 m high and made of shingle beaches.

158 **Husky Island**, rocky and with a **shoal spit** extending 1.5 miles WSW, is 13 miles east of Beach Island. A narrow inlet in the north shore of Husky Island has depths of only 1.8 to 2.4 m in the entrance but has deep water inside; it is a suitable harbour for small vessels. Unnamed islands lie NW and NE of Husky Island.

159 **Driftwood Island** *(57°18'N, 78°24'W)*, the largest of the King George Islands, is formed of raised beaches, lakes, marshes and rocks. A **shoal spit** extends west from the island for almost 5 miles. The south coast has 5 m cliffs and smooth flat areas of rock; a large amount of driftwood has been found here. An excellent harbour for small craft is between two shingle beaches near the east end of the south shore.

160 Unnamed islands and islets are scattered almost 20 miles off the larger islands of the King George group.

*Charts 5505, 5707*

## Offshore islands — Belcher Islands

161 **Caution**. — Most of the waters surrounding Belcher Islands are **not surveyed** and much of the hydrographic information is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended in sounded waters.

162 **Belcher Islands** *(56°12'N, 79°19'W)*, in the SE part of Hudson Bay, are a main group of four large and many smaller islands and two smaller groups off the north end of the main group. The small group to the NW is the **North Belcher Islands** and the NE group is the **Bakers Dozen Islands**.

162.1 A **shipping corridor** has been sounded from the deep waters of Hudson Bay east past the north end of Belcher Islands, then SE to the entrance of Eskimo Harbour. This corridor has been surveyed more accurately and completely than the surrounding area.

163 **Caution**. — The west and SW shores of the main group are very irregular and bordered with **rocks** and **shoals**; they are **dangerous** to approach.

164 All the Belcher Islands are barren and rocky and have a maximum elevation of less than 152 m. White bands of quartzite, reddish masses of ores and black hills are noticeable.

165 The larger islands contain many lakes; Kasegalik Lake on Flaherty Island, elevation 12 m, is the largest. Arctic char and whitefish are found in many of these lakes. Kasegalik Lake has a resident population of harbour seals and is a breeding ground for geese in May, June and July. Walrus, polar bears, fox and various species of seals are plentiful in the area. Wood is scarce; driftwood is found only on the west coast. The only trees are arctic willows and dwarf birch.

166 The climate of Belcher Islands differs widely from that of the mainland to eastward. The islands have far more overcast skies and cloud, stronger and more constant winds, but higher and more uniform temperatures.

*Chart 5505*

## Belcher Islands — North part

167 **Split Island** *(56°50'N, 79°51'W)*, the largest of the North Belcher Islands, has an elevation of 25 m; an inlet almost divides the island in two.

168 A **radar reflector** on an aluminium skeleton **tower** 9.1 m high, with an elevation of 14 m, is on the NW point of Split Island.

169 **Caution**. — **Rocks** and **depths** less than 11 m extend 2.5 miles north of Split Island. **North Belcher Shoals** with a least depth of 2.2 m are 9 miles NNW of Split Island. **Depths** less than 11 m exist between North Belcher Shoals and Sleeper Islands to the north. The surveyed channel runs south of North Belcher Shoals.

170 The **tidal ranges** of mean and large tides at Split Island are 0.3 and 0.6 m.

171 **Tidal streams** of 3 knots flow between North Belcher and Sleeper Islands. These streams tend to set a vessel across the passage.

172 **Anchorage** in 26 m, mud, can be obtained south of Split Island.

173 **Radar Island** *(56°57'N, 79°41'W)*, **Laddie Island**, **Lukisee Islands** and **Johnson Island**, with no known deep passage between any of them, lie east of Split Island. Johnson Island, the highest, has an elevation of 58 m.

174 **Kugong Island**,with **Lillico Point** *(56°32'N, 79°33'W)* at the north end, has elevations of 15 m along its NW and west shores, 30 m along its east shore and 61 m near its SW end. The largest of the three islands between Lillico Point and Johnson Island is 17 m high.

175 **Rocks** and **shoals**, position approximate, with no known deep passage through them, join the SW end of Split Island to Kugong Island.

176 **Churchill Sound** is filled with islands, islets and **shoals**, particularly in its north end. **Moore Island** rises to 30 m.

177 **Flaherty Island**, highest in the NE, is the largest of the Belcher group. **Howard Peninsula**, elevation 30 m and terminating in **Howard Point**, forms the west side of **Coats Bay**. **The Bluff**, on the east side of the entrance to Coats Bay, is a prominent hill with an elevation of 76 m.

178 **Caution**. — **Depths** of 2.2 m lie 4 miles north and 2 miles NNW of Howard Point.

179 **Eskimo Harbour** *(56°36'N, 79°12'W)* is at the north end of Flaherty Island. **Wiegand Island**, elevation 82 m, forms the north side of the harbour. **Renouf Island**, with twin hillocks, forms the east side. The north hillock is 56 m high and the south one is 54 m high.

180 Eskimo Harbour is entered between **Claw Point** and **Mosisee Point** *(not named on the chart)*. **Blocked Passage**, at the south end of Renouf Island, has islets and **drying patches**.

181 The **tidal ranges** of mean and large tides at Eskimo Harbour are 0.9 and 1.2 m.

182 The hamlet of **Sanikiluaq**, population 684 *(2001)*, is the farthest south of the Nunavut communities. The hamlet, on the east side of a cove on the south shore of Eskimo Harbour, has a post office, a health centre and RCMP detachment. There are 3 retail stores and a gift shop. *Inns North* provides accommodation. *Air Inuit* provides flights Mondays, Wednesdays and Fridays.

183 A large **oil tank**, elevation 31 m, and a radio tower, elevation 73 m, are **conspicuous** east of the hamlet.

184 An **aeromarine radiobeacon** near Sanikiluaq transmits on 208 kHz with identification YSK (— • — — • • • — • —).

185 **Anchorage** has been obtained off the hamlet.

186 Bakers Dozen Islands are a chain of islands and islets extending 27 miles north of Cape Bartlett *(56°26'N, 78°40'W)*. **Twin Cairns Island** *(56°31'N, 78°48'W)*, **Cake Island**, **Loaf Island** and the island 2.5 miles north of Loaf Island have elevations of 30 m. **Bun Island** and the remainder of the chain, including an island 10 miles ENE of Loaf Island almost divided into two parts, are lower.

187 **Caution**. — A 4 m **shoal** is 3 miles west of Cake Island. Another **shoal**, with a depth of 7.1 m, is 1.6 miles WNW of Cake Island.

188 **Cape Bartlett**, at the north end of **Tukarak Island**, rises to southward to **Four Steps Hill**. This hill has a step-like rock formation on its south side and is a good **landmark** for approaching the north entrance of **Omarolluk Sound**.

189 **Gushie Point** *(56°25'N, 78°55'W)*, on Flaherty Island, is the NW entrance point of Omarolluk Sound. The north end of the sound is bordered to the west by Mukpollo Peninsula and to the east by Tukarak Island. Most of the shores of the sound rise steeply to hills 61 m in elevation.

190 **Range Island**, elevation 9.4 m, is in the middle of the north entrance to the sound.

191 **Burwash Point** and **Desgoffe Point** project from the east shore of the north part of the sound. **Young Point** and **Tragedy Point**, the NE end of **Gilmour Peninsula**, project from the west shore.

192 The **tidal ranges** of mean and large tides in the central part of Omarolluk Sound are 1.2 and 1.7 m.

193 **Tidal streams** of about 3 knots occur in the entrances to Omarolluk Sound with heavy **tide rips** at the change of tide. The ebb tide in the sound flows south, the flood flows north.

194 **Caution**. — **Shoal depths** under 11 m extend from both shores of the sound almost to mid-channel

and several **isolated shoal depths** between 5.5 and 9.1 m are in mid-channel north of Gilmour Peninsula.

195 **Rowatt Harbour** *(56°20'N, 78°56'W)* is **shallow**. Nothing is known of **Spence Harbour**.

196 **Meeko Point** rises to 30 m on the east side of the sound. **Salty Bill Hill**, elevation 127 m, is to the NE.

197 **Bradbury Island**, elevation 46 m, **Nero Island**, **Karlay Island** and **Mata Island** border the east side of the sound south of Meeko Point.

198 **Caution**. — A 10.1-m **shoal patch** is in mid-channel west of Bradbury Island.

199 **Dove Island**, elevation 15 m, lies between Bradbury Island and Tukarak Island. Dove Island is just north of a small bay on Tukarak Island that is the site of the abandoned Belcher Islands trading post *(see Charts 5707 and 5003)*.

200 **Anchorage** with good holding has been obtained 0.55 mile south of Desgoffe Point in mud and sand. Good **anchorage** is available in the harbour close south of Dove Island in 6.1 m, mud, with swinging room for a 30 m vessel.

201 **Laddie Harbour** *(56°15'N, 78°40'W)*, on the east coast of Tukarak Island, has a **rock** in the middle of the entrance and is **shallow**. The coast between Cape Bartlett and Laddie Harbour rises steeply to more than 122 m.

202 **Quorik Point**, 2.5 miles south of Laddie Harbour, rises steeply to 107 m. **McLeary Point**, 3 miles farther south, has twin 61-m summits.

203 **Caution**. — A shoal **depth** of 10.1 m was reported *(1986)* to lie 1.8 miles ENE of McLeary Point.

204 **Caution**. — Numerous islands and **shoals** lie in the area between Belcher Islands and Nastapoka Islands, which border the east shore of Hudson Bay 65 miles to the east. Most of the area is **not surveyed**.

205 **Salikuit Islands** *(56°21'N, 77°45'W)*, a group of several large islands and many islets and **rocks**, are midway between Belcher Islands and the mainland to the east.

206 **Caution**. — This group covers an area of 10 miles NNW/SSE and 25 miles WSW/ENE, ending within 15 miles of the mainland, and is reported to be bordered by **shoal water** for 6 miles northward and southward. A chain of islands and **rocks**, some of whose positions are doubtful, stretches NNW from Salikuit Islands for 47 miles to King George Islands.

*Chart 5707*

## Belcher Islands — South part

207 The SW entrance to Churchill Sound, bounded by Kugong Island and **Revillon Island** *(55°56'N, 80°09'W)*, is choked with shoals, rocks and islands.

208 **Robertson Bay**, in the SW part of Flaherty Island, contains numerous islets and **shoals**. **Freakly Point** *(55°46'N, 79°47'W)*, the SE entrance point to the bay, has **shoal water** extending SSW for 1 mile or more. **Kasegalik Lake** drains through **Kasegalik River** into the east side of the bay.

209 A wide bay with deep water is entered east of Freakly Point, at the SE end of Flaherty Island. The bay has a narrow inlet at its head; this is the site of an abandoned village. The inlet is entered through a deep channel between an islet and **foul ground** extending from the west entrance point.

210 **Caution**. — Inside the inlet, the bottom is irregular with several **shoal pinnacles**. With local knowledge, a depth of 3 fathoms (5.5 m) can be carried to the head of the inlet.

211 **Anchorage** in 20 fathoms (37 m), mud, can be obtained 0.5 mile SSE of the islet.

212 **Wetalltok Bay** *(56°00'N, 79°16'W)* is bound to the east by **Gibson Peninsula**. A chain of islets and **rocks** extends SW some 19 miles from the peninsula. More islets and **rocks** reach 15 miles farther SW.

213 The entrance to **Kipalu Inlet** is between Gibson Peninsula and **Mukpollo Peninsula**.

*Chart 5505*

214 Kipalu Inlet terminates in **Kihl Bay**. The inlet has **Ney Island**, elevation 61 m, near its head. **Face Channel** lies west of Ney Island.

*Chart 5707*

215 Gibson and Mukpollo Peninsulas are from 100 feet (30 m) high at the south ends to almost 400 feet (122 m) at the north.

216 **Snape Island** *(55°44'N, 79°20'W)*, 200 feet (61 m) high in its south part, forms the SW side of Omarolluk Sound. The island is separated from Mukpollo Peninsula by **Rock Passage**.

217 **Caution**. — Rock Passage is partly **obstructed** by a **ridge** with a depth of 5 feet (1.5 m).

218 **O'Leary Island** and **Broomfield Island**, with elevations of 200 and 100 feet (61 and 30 m), form the SE side of Omarolluk Sound. These islands are separated from **Innetalling Island**, to the north, by **Ridge Passage** *(55°47'N, 79°08'W)*. **Sainsbury Point** is the south end of Broomfield Island.

219 *Broomfield Island* **light** and **racon** *(2552)* are on Sainsbury Point.

220 **Narrow Passage** is the south entrance to Omarolluk Sound. The channel *(indicated on the inset on Chart 5707)* has a least width of 450 feet (137 m) and a least depth of 44 feet (13.4 m) off the south end of O'Leary Island.

221 In Omarolluk Sound, **Walton Island** *(55°58'N, 79°06'W)* and **Camp Islands** *(not named on the chart)*, to the south, are joined by a **submarine ridge** with depths of 3 to 7 fathoms (5.5 to 12.8 m).

222 **Caution**. — **Shoal spits** extend north and south from the islands.

223 Gales from SW and west have been ridden out at an **anchorage** in 15 fathoms (27 m), mud, off **Deposit Cove** *(not named on the chart)*, on the east side of the north end of Walton Island.

224 Farther north, the east side of Omarolluk Sound is bounded by **La Duke Island**, an extension of Innetalling Island.

225 **Anchorage** in 10 fathoms (18.3 m) with good mud holding ground can be obtained 1.25 miles south of Camp Islands. Good **anchorage** has been obtained in **Red Fox Cove** in the SW part of Omarolluk Sound.

226 **Fresh water** is available from a stream on Innetalling Island, SE of Camp Islands, draining Mine Lake *(not shown on the chart)* using 1,500 feet (457 m) of hose.

227 **Mavor Island**, elevation 200 feet (61 m), shelters **Fairweather Sound** *(56°06'N, 78°52'W)*. **Rainbow Point**, the north end of Innetalling Island, is the SW entrance point of the sound.

228 **Caution**. — **Depths** in Fairweather Sound are irregular, ranging between 2 and 4 fathoms (3.7 and 7.3 m) but with several deeper areas between 14 and 21 fathoms (25.6 and 38 m). There is a 16 foot (4.9 m) **shoal** in the middle of the east entrance of Fairweather Sound. **Fair Island** *(56°06'N, 78°52'W)*, in mid-sound and less than 50 feet (15 m) high, has a **rock** close north and an islet 0.2 mile SSW; **shoal water** extends 0.1 mile south of the latter. **Johnnys Island**, with a **drying rock** close NW, is just inside the west entrance. **Shoal water** extends 0.5 mile from the north side of this entrance. **Shoals** with depths of 7 and 1 feet (2.1 and 0.3 m) are in the NW approach to Fairweather Sound, east of La Duke Island.

229 **Fairweather Harbour** *(56°01'N, 78°59'W)*, entered between **Sala Point** and **Spracklin Point**, is deep and sheltered by several islands in its entrance but has limited swinging room.

230 **Caution**. — A dry rock and a **rock which covers and uncovers** are 1 mile ENE, and **shoal water** may extend north of the northern end of Spracklin Point.

231 **Camsell Island** *(56°02'N, 78°40'W)*, elevation 30 feet (9.1 m), is one of a line of islets and **rocks** that extend south for 25 miles from McLeary Point on Tukarak Island.

232 **Caution**. — More islands and **rocks**, some of whose positions are doubtful or approximate, are up to 35 miles east and SE of McLeary Point.

*Chart 5505*

## Nastapoka Islands

233 **Nastapoka Islands** are a narrow chain of islands, islets and **rocks**, 100 miles long, lying parallel to and close off the east coast of Hudson Bay. The islands have steep but often broken cliffs on their eastern sides but on the west sides they slope gradually towards the sea. Some of the islands reach an elevation of 122 m. The eastern shores of the islands have deep water close inshore.

234 **Caution**. — The west shores are **dangerous** to approach because of **shoal water** and numerous **submerged reefs**.

235 **Nastapoka Sound**, between Nastapoka Islands and the mainland, has an average width of 2 miles. The sound is deep enough over most of its length for medium-sized vessels.

236 **Caution**. — A **submerged ridge** 0.8 mile east and SE of Anderson Island has a least depth of 9.9 m.

237 The mainland coast of the sound has elevations of 305 to 610 m close inland. There is deep water close inshore except at the mouths of rivers where alluvial sand has created shoals and where **reefs** lie off the coast, in places, especially around rocky points. There are no safe large harbours on the mainland. The mouths of Rivière Longland and Rivière Nastapoka are the only shelter for small craft.

238 **Cotter Island** *(57°46'N, 77°01'W)*, the farthest north of the Nastapoka group, has a greatest elevation of 61 m in its NE part. High and steep at each end and low in the middle, it appears from a distance to be two islands.

239 **McTavish Island** *(57°33'N, 76°53'W)* is 61 m high; it offers no safe anchorage. On the mainland, **Rivière Boniface** enters the sea 4 miles NNE of the island.

240 **Caution**. — There is a 16.3 m **sounding** 6.5 miles west of the river mouth.

241 The **tidal ranges** of mean and large tides are 0.7 and 1.1 m at McTavish Island.

242 **Broughton Island**, separated from McTavish Island by a passage with a least depth of 24 m, is the largest of the Nastapoka Islands chain; it rises to 122 m. Two small bays at the north end and two more at the south end of the east shore provide good shelter. The bays at the south end contain a number of islets lying 0.1 mile offshore.

243 **Caution**. — A **sounding** of 14.4 m is 7 miles west of the south end of Broughton Island.

244 **Rivière Longland** *(57°28'N, 76°45'W)*, on the mainland 3.5 miles ENE of the north end of Broughton Island, enters Hudson Bay close south of **Pointe Pamialluk**.

245 **Caution**. — The river entrance is **obstructed** by a **bar** with a depth of 1.2 m. Inside the bar, a basin 0.05 mile wide, **obstructed** by **shoals**, extends inland 0.5 mile to a **waterfall** 18 m high.

246 **Pointe au Canon** is 1.5 miles SE of Rivière Longland.

247 **Nicholson Island** has a good **small-craft harbour**, protected by a small rocky island, midway along the east coast.

248 **Davieau Island** is 61 m high in the middle of its rugged east side. There is small craft **anchorage** in a small bay near the SE end of the island.

249 **The Throat** *(57°04'N, 76°41'W)*, a navigable passage between Davieau and Christie Islands, runs between straight cliff walls that gradually lower towards the west entrance where they fall away to rocky points. The Throat is frequently visited by Inuit in the winter because of the abundance of seals found here. **Pointe de la Baleine Blanche** is on the mainland to eastward.

250 **Christie Island** is over 91 m high on its east side. A long sand **spit** projects south from the south end of the island and forms a sheltered bay. The bay provides a good harbour for small craft.

251 **Mowat Island**, separated from Christie Island by a deep but narrow channel, has a good harbour on the north side.

252 **Caution**. — A **shoal** *(56°59'N, 76°36'W)*, with a least depth of 0.7 m, lies 1.8 miles east of Mowat Island.

253 **Rivière Nastapoka** *(56°55'N, 76°33'W)*, on the mainland 5 miles SE of Mowat Island, can be entered only by small craft. **Nastapoka Falls**, with a vertical drop of 30 m, are close to the river mouth.

254 **Caution**. — A **dangerous drying rock**, reported in 1992, lies close north of the mouth of Rivière Nastapoka, 1.5 miles offshore, and there may be other **shoals** in the vicinity.

## Rivière Nastapoka to Le Goulet

255 A chain of islets and rocks stretches between Mowat Island and **Gordon Island**, 4 miles to the south.

256 **Caution**. — Two **dangerous rocks**, reported in 1973, are 3 miles WNW of Gordon Island.

257 **Miller Island** *(56°47'N, 76°39'W)* is one of several islands and rocks extending 3 miles north of **Taylor Island**. A **small-craft** harbour is close east of two small islands at the north end of Taylor Island. A bay 1 mile long and 0.5 mile wide midway on the east side provides a safe and spacious harbour.

258 **Gillies Island** is separated from Taylor Island by a narrow navigable channel. The east side of Gillies Island has a number of wide bays offering shelter from all but easterly winds; the best is 1 mile north of the south end.

259 The **tidal ranges** of mean and large tides at Gillies Island are 1.2 and 1.6 m.

### Approaches to Umiujaq

260 **Curran Island** *(56°31'N, 76°39'W)* and **Armstrong Island** are south of Gillies Island.

261 **Umiujaq** *(56°33'N, 76°33'W)*, population 348 *(2001)*, is on the mainland opposite the south end of Gillies Island. The settlement was founded in 1986 by Inuit from Kuujjuarapik. The community has a post office, a health centre offering medical and dental care and a police station. There are 3 retail stores and a *Nunavik Cooperative Hotels* facility. *Air Inuit* provides flights every day except Wednesday.

262 A low-lying rock point extending out into Nastapoka Sound at Umiujaq has been used for loading and unloading supplies and equipment from a barge. North and south of the settlement there are low sloping beaches. The **landing beach** is south of the settlement.

263 **Anchorage** may be obtained 0.3 mile offshore opposite the landing area in 29 m over a sandy bottom, with fair holding.

264 A weak and variable **tidal stream** of 0.35 knot has been recorded at the anchorage.

265 **Clarke Island**, 0.5 mile south of Armstrong Island, rises to over 61 m in its central and SE parts. Two low gravel islands, scattered with large boulders and joined by a **bar**, lie off the SW part of Clarke Island.

266 **Luttit Island**, 3 miles farther south, is steep with deep water inshore at the north end.

267 The **surveyed channel** through the Nastapoka Islands to Umiujaq lies between Clarke Island and Luttit Island. The channel is 1.8 miles wide and has a least depth of 19.5 m.

### Umiujaq to Le Goulet

268 **Anderson Island** *(56°18'N, 76°42'W)* is separated from Luttit Island by a navigable channel 0.1 mile wide. A small bay, landlocked by two islets, near the north end of the east shore affords secure **anchorage**. The west coast of Anderson Island is low and sandy; the south shore and the south half of the east shore are steep and rugged.

269 The west coast of **Ross Island** forms a wide bay ending in two low rocky points.

270 **Caution**. — The NE coast is formed of steep cliffs but has **shoal water** and an islet within 1 mile of shore.

271 Secure **anchorage** for larger vessels is found in the bay formed on the east side of two small islands between Anderson Island and Ross Island.

*Chart 5707*

272 A deep channel separates **Bélanger Island** *(56°08'N, 76°45'W)* from Ross Island. **Tidal streams** from Le Goulet *(56°10'N, 76°37'W)* rush with great force through the channel and keep it free of ice long after the rest of Nastapoka Sound has frozen over. The west shore of Bélanger Island is low with sandy bays between rocky points.

273 **Caution**. — **Reefs** lie parallel to the shore and **shoal water** extends a considerable distance offshore; to approach Bélanger Island from seaward is **dangerous**. Deeper water is found close under the cliffs on the east side of the island.

274 **Flint Island**, the farthest south of Nastapoka Islands, is small and rocky.

275 **Caution**. — A **rock** 0.15 mile NW of Flint Island has a depth of 3 feet (1 m). A 10 foot (3 m) **patch** lies 0.5 mile west of the island. A **rock** 1.5 miles SSW of Flint Island has a depth of 29 feet (8.9 m). A **rock** 13 miles WNW of Flint Island has a depth of 44 feet (13.4 m). A **ridge** of **rock** 6.6 miles SW of Flint Island dries 6 feet (1.8 m).

*Charts 5505, 5002*

276 **Lac Guillaume-Delisle** is a large estuary of Hudson Bay with jagged shores formed of steep cliffs. A settlement, now abandoned, is on the SE side of the brackish lake.

277 **Le Goulet**, the entrance channel to Lac Guillaume-Delisle, is 0.15 mile wide. Le Goulet leads between perpendicular cliffs that increase in height, west to east, from 30 to 457 m.

278 The water in Le Goulet is deep but the **tidal streams** rush in and out of the channel with great velocity and create **whirlpools**.

279 **Caution**. — It is **dangerous** for **small craft** to transit Le Goulet except at slack water.

280 **Presqu'île Castle** is on the north side of Le Goulet. Prominent peaks are 3 miles north and 3 miles south of the peninsula.

## Le Goulet to Pointe Louis-XIV

*Chart 5707*

281 **Caution**. — Most of the area covered by *Chart 5707* is **not surveyed** and much of the hydrographic information shown is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended when navigating sounded waters.

### Le Goulet to Grande rivière de la Baleine

282 **Petite rivière de la Baleine** enters the sea 11 miles SSW of Le Goulet. **Pointe Qilalugarsiuvik** *(56°00'N, 76°47'W) (not named on the chart)*, with clumps of trees and a variety of vegetation, forms the north side of the river mouth. Steep hills close south of the river rise to 1,000 feet (305 m).

283 **Caution**. — A **bar** with a depth of 6 feet (1.8 m) lies across the river mouth; 20 feet (6.1 m) is found inside the bar. A **drying rock** lies 5 miles WSW of Pointe Qilalugarsiuvik.

284 **Duck Island** *(55°45'N, 77°12'W)*, 19 miles SW of Pointe Qilalugarsiuvik, is 52 feet (16 m) high and flat. The island, composed of gravel, makes a poor radar target.

285 **Caution**. — A **small-craft harbour** on the SW side of Duck Island offers little protection.

286 **Manitounuk Islands** lie parallel to the shore for 25 miles and form the west side of **Manitounuk Sound**. The main islands of the chain are **Castle Island** *(55°36'N, 77°18'W)*, **Merry Island**, **Neilsen Island** and **Bill of Portland Island**. The islands have high cliffs and are similar in appearance to Nastapoka Islands.

287 **Caution**. — A **reef that dries** 5 feet (1.5 m) forms part of a **shallow ridge** parallel to and 1.5 miles off the SW part of Merry Island. Very **shoal water** lies a farther 2 miles offshore. A **rock ridge** 6 miles offshore has a least depth of 35 feet (10.8 m). **Depths** of 20 and 26 feet (6.1 and 7.9 m) lie 5 miles WNW of the SW end of Merry Island. An area of **shoals** and **drying rocks** lies from 1 to 3.3 miles NW of the NE part of the island. **Reefs** and rocky islets extend 11 miles SSW from Duck Island; two of these islets are 31 feet (9.3 m) high.

288 **Caution**. — There are no good **radar targets** in this area.

289 **Boat Opening**, north of Castle Island, is **shallow** and suitable only for small craft. **Schooner Opening**, between Castle and Merry Islands, is narrow with a least depth of 4 fathoms (7.3 m).

290 **Paint Islands** *(55°29'N, 77°27'W)*, a group of several small islands, lie midway between Merry Island and the mainland.

*Chart 5476*

### Approaches to Kuujjuarapik (Poste-de-la-Baleine)

291 **Gillies Island** *(55°20'N, 77°52'W)*, a rocky boulder-strewn islet, lies 4.5 miles NNW of the mouth of Grande rivière de la Baleine. A **spit** with a depth of 16 feet (4.9 m) extends 0.3 mile WSW of the island. **Depths** of 6 fathoms (11 m) or less are 1 mile SW, 2.4 miles north and 3.7 miles NNW of Gillies Island.

292 **Caution**. — A **hydrographic survey** in 1985 indicated that **depths** over the shoals in the vicinity of Gillies Island are **less than charted**.

293 **Maver Islands** lie close off the mainland shore 4 miles NNE of the river mouth.

294 **Caution**. — A **shoal patch**, a **rock** with 6 feet (1.8 m) or less over it, position approximate, and a **drying rock** are 0.7, 2.7 and 3.3 miles NE of Maver Islands.

295 **Pointe Walton**, 100 feet (30 m) high, lies 1 mile WSW of the river mouth.

296 **Grande rivière de la Baleine** *(55°16'N, 77°48'W)* is entered south of **Pointe au Sable**. The river **current** varies from 1.5 to 2 knots.

297 **Caution**. — The charted track leads over a **bar**, off the river entrance, with a least depth of 2 feet (0.6 m). At high water large tides, a draught of 9 feet (2.7 m) can be carried over the bar.

298 **Caution**. — Mariners are cautioned that with any **swell** the bar becomes an area of broken and confused water.

299 The Inuit settlement of **Kuujjuarapik (Poste-de-la-Baleine)** *(55°17'N, 77°46'W)*, population 555 *(2001)*, is at the mouth of Grande rivière de la Baleine. The location is shared with the Cree Indian settlement of **Whapmagoostui**, population 778 *(2001)*. Each community has a post office and police station; Kuujjuarapik has a heath centre with medical and dental facilities while Whapmagoostui has a dispensary. There are 4 retail outlets and a convenience store between the two communities and there are 4 hotels. *Air Inuit* provides flights 7 days a week; *Air Creebec* offers flights every day except Saturday. There is no road access to Kuujjuarapik/Whapmagoostui.

300 The average thickness attained by smooth **fast ice** at Kuujjuarapik is 148 cm with a record maximum thickness of 220 cm *(1983)*. Break-up on Grande rivière de la Baleine normally begins by the third week in May with the river clear of ice by the end of the month. Freeze-up usually begins the middle of November with complete ice cover forming by the early days of December. Two to four weeks variation in dates of break-up and freeze-up can occur. Freeze-up and break-up on Hudson Bay at Kuujjuarapik are, on the average, two weeks later.

301 The **tidal ranges** of mean and large tides are 4.7 and 6.5 feet (1.4 and 2 m) at Bill of Portland Island. Offshore **currents** usually flow north and are reported to be strong off Bill of Portland Island. **Tidal heights** at Kuujjuarapik can be affected by **wind**.

302 An **aeromarine radiobeacon** near the settlement transmits on 371 kHz with identification GW (— — • • — —).

303 **Oil tanks** on Pointe au Sable, a **hangar** on the airfield and several radio **masts** are **conspicuous**.

304 An aeronautical rotating **light** is on the airfield. The radio masts and the oil tanks carry red aircraft obstruction **lights**.

305 A floating **Public wharf** is on the north side of the river SW of the tank farm. The *Hudson's Bay Company* wharf no longer exists.

306 **Caution**. — There is a **sea-plane landing area** on the river east of the Public wharf.

307 Unsheltered **anchorage** in 17 fathoms (31 m), mud, can be obtained 1.2 miles WNW of Pointe au Sable. This berth is not recommended in winds over Beaufort force 5. Small vessels can find **shelter** from westerly gales in **Laverock Bay** *(55°24'N, 77°41'W)* on the east side of Neilsen Island.

308 **Caution**. — **Anchorage** may not be possible in Manitounuk Sound in strong **winds**; vessels should stay well offshore in these circumstances.

*Chart 5707*

## Grande rivière de la Baleine to Long Island

309 The coast has only minor indentations, with little shelter, between Pointe Walton *(55°15'N, 77°51'W)* and Pointe Louis-XIV, 76 miles WSW.

310 **Caution**. — Sparse **soundings** 1 to 2 miles off the coast between Pointe Walton and Pointe Vauquelin, 40 miles WSW, show **depths** between 3 and 20 fathoms (5.5 and 37 m). There are a number of islets; **uncharted dangers** may exist.

311 Lines of **soundings** from 2 miles off Pointe Walton to between 8 and 11 miles off Pointe Vauquelin indicate a fairly even bottom with a **least depth** of 19 fathoms (35 m).

312 **Black Whale Harbour** *(55°09'N, 78°08'W)* and **Otaska Harbour** lie 11 and 17 miles SW of Pointe Walton; nothing is known about anchorage in these inlets.

313 **Bear Islands** is a group of islands and islets 2.5 miles NW of Otaska Harbour; the largest has an elevation of 138 feet (42 m).

314 **Caution**. — A **shoal depth** of 29 feet (8.8 m) is NE of the Bear Islands, 3.4 miles NW of the west entrance point of Black Whale Harbour.

315 **Pointe Vauquelin** *(54°55'N, 78°50'W)*, wooded, is less than 100 feet (30 m) high. **Rivière Vauquelin** enters Hudson Bay 2 miles to the east. The coast in this area has a foreshore of wide **drying flats**.

316 **Caution**. — An **islet**, elevation 29 feet (8.8 m), lies 7.5 miles NE of Pointe Vauquelin. Other islets have been reported 3 and 4 miles farther east but these were not found by a hydrographic survey in 1987. **Depths** of 3 to 9 fathoms (5.5 to 16.5 m) are 1 to 2 miles off this stretch of coast. Islets and **shoal water** lie up to 2 miles off Pointe Vauquelin and **soundings** of 3 and 6 fathoms (5.5 and 11 m) are 4 miles NNW of the point.

*Charts 5801, 5476*

## Long Island and Long Island Sound

317 **Caution**. — Much of the area covered by *Charts 5801* and *5476* is **not surveyed** and some of the charted hydrographic information, indicated by sloped figures on *Chart 5801*, is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended in sounded waters.

*Chart 5801*

318 **Long Island** *(54°52'N, 79°25'W)*, with a greatest elevation of 30 m at its east end, has low limestone cliffs separated by wide valleys along its south shore. A bay on the south shore, 10 miles WSW of the east end of the island, affords good shelter for small craft. This bay, protected by a low or **shoal spit** on its south side, has a **drying rock** in its entrance and a **depth** of 5.5 m inside. A **depth** of 9.1 m is farther in.

319 A **beacon**, consisting of a rectangular **daymark** and a **radar reflector** mounted on a steel skeleton **tower** with an elevation of 42 m, is on an island close SW of Long Island.

320 **Anchorage** in depths of 24 to 38 m can be found close south of the SSW end of Long Island in a position 2.3 miles NE of the island with the beacon.

321 The **tidal ranges** of mean and large tides in this area are 1.5 and 2.1 m.

322 **Caution**. — **Dangerous obstructions**, extending as far as 9.2 miles SW of the island with the beacon, are in the SW approaches to Long Island Sound.

323 **Long Island Sound**, between Long Island and the mainland, has a least mid-channel depth in the east half of 11.9 m but the west half is **obstructed** by **shoals** and long narrow islands. A passage suitable for small vessels runs between the islands in the central part of the sound.

324 **Pointe Tikirakallaaluk**, **Pointe Tupialuviniq**, **Pointe Majuriarvik**, **Pointe Nasissaturarvik** and **Pointe Aquttutalik** *(54°45'N, 79°27'W)* are features on the mainland shore of the sound.

325 **Caution**. — A **drying reef**, position approximate, is 2 miles NW of Pointe Majuriarvik. A **reef drying** 1.2 m, 3 miles NNE of Pointe Aquttutalik, is in the east entrance of the channel through the west half of the sound.

*Chart 5476*

326 **Caution**. — Two **reefs**, only **just dry**, lie 0.8 mile SSE and 1.3 miles ESE of the anchorage.

327 **Pointe Louis-XIV** *(54°38'N, 79°45'W)*, the east entrance point of James Bay, has an elevation of less than 100 feet (30 m) but can be identified by two **conspicuous domes** 115 feet (35 m) high on the north part. An abandoned airstrip and buildings are near by.

328 **Anchorage** can be found in depths of 16 fathoms (29 m) in a position 2.2 miles north of the radar domes on Pointe Louis-XIV.

329 **George Bay**, between Pointe Louis-XIV and **Pointe Shave** , is mostly **shallow** and has numerous **rocks**, **shoals** and islets.

330 **Caution**. — The approaches to George Bay for 2 miles and farther offshore are strewn with islands, islets and **rocks**, rising from a very uneven bottom. **Cape Jones Island** is the largest of the islands.

# James Bay

## General

*Chart 5800*

1 **James Bay** is entered between Pointe Louis-XIV *(54°38'N, 79°45'W)* and Cape Henrietta Maria, 95 miles WNW. James Bay extends south some 240 miles from Hudson Bay and is generally shallow with many offshore dangers. Depths along the routes followed by shipping are frequently less than 10 fathoms (18.3 m). The shores of the bay are mostly low and flat and the foreshore is wide **mud flats**.

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

2 **Caution**. — Much of James Bay is not surveyed and much of the charted hydrographic information is of a reconnaissance nature. Unsounded waters should not be entered without local knowledge. Caution is recommended in sounded waters.

## James Bay — East shore

3 The east coast is very irregular and is bordered by innumerable islands and islets and **shallow water** for many miles offshore. The elevation inland is so low that **hills** rising from 100 to 200 feet (30 to 61 m) form **conspicuous landmarks**. The tree line is confined to the shores and interior on the north part of the coast; the islands and outer points

are barren, but farther south they too are wooded. There are several fair harbours on the east shore suitable for vessels drawing up to 12 feet (3.7 m). The west shore is even, almost free of islands and has few harbours.

*Chart 5801*

## Pointe Louis-XIV to Fort George (Fort-George) and Chisasibi

4 **Bare Island** *(54°26'N, 79°56'W)*, 13 miles SSW of Pointe Louis-XIV *(described in Chapter 4)*, is composed of pink and white granite with a scant covering of moss and grass; the summit resembles a dome.

5 There is a **beacon** consisting of fluorescent-orange rectangular **daymarks** and a **radar reflector** on a skeleton **tower** on Bare Island.

6 **Roggan River** is a seasonal fishing camp available for emergency shelter at the mouth of **Rivière Roggan (River)**, on the mainland east of Bare Island. **Rivière au Phoque** enters James Bay 8 miles to the north; **Rivière Kapsaouis** enters 5 miles to the south.

7 **Pointe Attikuan (Attiquane)** *(54°18'N, 79°29'W)* is low and bare. **Pointe Kakassitug**, 8 miles to the SSE, rises to 30 m (100 ft) and is bare. **Pointe Kakachischuan (Kakachischuane)**, 14 miles farther SE, rises to 30 m (100 ft) and is wooded. The point forms the north side of **Paul Bay**, a **shoal** bay not navigable even by small craft. **Rivière Piagochioui** flows into Paul Bay.

8 **Wastikun Island** *(53°57'N, 79°09'W)*, black and cone-shaped, is the north entrance point of the **shallow Goose Bay**. The island, with an elevation of 41 m, is the most prominent landmark in this vicinity. **Rivière Guillaume** enters the head of Goose Bay.

9 **Grey Goose Island** *(53°54'N, 79°53'W)*, boulder-strewn, rises in a gentle slope. **Depths** under 10 m extend 1 mile NE of the island and a **shoal rock**, existence doubtful, is 3 miles SSW. **Depths** of 11 and 8.4 m are up to 6 miles south of the island.

10 A **beacon** consisting of a fluorescent-orange rectangular **daymark** and **radar reflector** are on a skeleton **tower** on Grey Goose Island.

11 **Caution**. — **North Star Shoal** *(53°57'N, 79°57'W)*, with a depth of 3.4 m, lies 3 miles NW of Grey Goose Island.

12 **East Cub Island** is a low rocky islet 12 miles NW of Grey Goose Island.

13 **Caution**. — A **dangerous rock** with a depth of 2 m or less is 3.2 miles east of East Cub Island. **Shoal depths** of 9.8 and 8.4 m are 11 and 15 miles NE of East Cub Island.

*Charts 5720, 5801*

## Approaches to Fort George (Fort-George) and Chisasibi

14 **Caution**. — **Egg Rock** *(53°54'N, 79°21'W)* and another **drying rock** 2 miles west lie in the NW approaches to La Grande Rivière. **Depths** of less than 10 m are 5 miles WSW and 8 miles SW of Egg Rock.

*Chart 5720*

15 **Anik Islands** *(53°50'N, 79°18'W)*, on the south side of the approaches, are low and surrounded by **reefs** and **shoal water** to distances of up to 1 mile.

16 A **radar reflector** mounted on a square skeleton **tower** is on the south Anik Island.

17 **Caution**. — **Qairulik Reef**, 1.5 miles NNW of Anik Islands on the north side of Narwhal Passage, breaks in most sea states but is **not visible in calm conditions** at high water. A 7.2 m **patch** is 2 miles WNW of the reef.

18 **Peril Island** is 1 mile SSW of Anik Islands. **Wicked Reef** *(53°46'N, 79°23'W)* and **Hiding Rock** lie 3.5 miles SW and 3 miles south of Peril Island; **Blind Rock** lies 2.8 miles farther south.

19 **Caution**. — This area is scattered with **depths** under 10 m.

20 **Caution**. — **Loon Islands** are an extensive group of low, moss-covered or bare islands and **drying rock ledges** surrounded by **shoal water**. **Turning Island** *(53°51'N, 79°13'W)* is on the north side, and **Double Island**, elevation 7 m, is on the NE side of the group.

21 There is a **radar reflector**, mounted on a skeleton **tower**, on Turning Island.

22 **Marker Island** is in the SW part of Loon Islands and **Umiak Island** is in the SE part.

23 Private **beacons** on these two islands mark the north side of a narrow channel leading to Fort George Anchorage. Local knowledge is recommended if this channel is to be used.

24 **Caribou Island**, **Duckling Island**, **Slate Island**, **Grass Island** and **Tiny Island** are named islands of a large group of islands and **reefs** lying south of the Loon Island group and extending to the mainland shore.

25 **Anchorage**, open to NW, can be obtained 2 miles east of Turning Island.

26 **Fort George Anchorage** and **Narwhal Anchorage** *(53°49'N, 79°10'W)* are entered through a passage, with **depths** under 5 m near mid-channel, between Double Island and **Seal Islands**. Fort George Anchorage is frequently used by supply vessels but is exposed to NW gales. Narwhal Anchorage offers better protection but moderate holding in soft clay; CCGS *Narwhal*, a 2,100 tonne ice breaker, dragged both anchors here in 60-knot NW winds.

27 **Caution**. — A **rock** with a depth of 1.6 m is in the SW part of Fort George Anchorage.

28 **Stromness Island** *(53°52'N, 79°08'W)* and **Boat Island**, NW of the mouth of La Grande Rivière, are in the entrance to **Stromness Harbour**. The harbour, **not surveyed**, has many islets and **drying flats**.

29 *Boat Island range* **leading beacons**, established on Boat and Stromness Islands, in line astern bearing 356½°, lead into Fort George Anchorage in a least depth of 7.9 m. The front and rear beacons are fluorescent-orange **daymarks** shown from square skeleton **towers** 7 and 13.4 m high.

30 **Caution**. — Strong **tidal streams** in the Loon Islands area tend to set a vessel northward or southward.

31 **La Grande Rivière**, one of the largest rivers entering James Bay, has a large **shoal delta**, **partly drying**, in its mouth. A hydro-electric complex is 60 miles upriver. **Pointe Skidoo** *(53°51'N, 79°04'W)* is on the north side of the river entrance; **Black Island** is on the south side. **Monkey Hill**, rising to 27 m 1 mile ENE of Black Island, is a good **landmark**.

32 The channel into the river, prior to changes in river flow due to the *James Bay Hydro-electric Project*, ran north of **Sam Island** and **Governor Island** *(53°50'N, 79°05'W)* and south of **Barge Shoal**.

33 **Caution**. — A **depth** of 3 m could be carried through this channel at high water for 5 miles up river; it is **not known** if the **channel** or **depths** have changed. Local knowledge is essential.

34 **Caution**. — There are **strong currents** in this area, especially at ebb tide. Wind **against** tide in the shoal waters of the delta creates sea conditions **dangerous** to **small craft**.

35 **Caution**. — **Channels** change frequently due to **silting** and erosion. The river bed is mostly gravel or sand but there is a possibility of **isolated boulders**.

36 The settlement of **Fort George (Fort-George)**, on **Île de Fort George** 4 miles east of Governor Island, was virtually abandoned in 1981 because of concerns that changes in the currents in La Grande Rivière due to the *James Bay Hydro-electric Project* would scour away Île de Fort George. Only a handful of families still live on the island.

37 The Cree settlement of **Chisasibi** *(53°48'N, 78°53'W)*, population 3,467 *(2001)*, was established on the south shore of the river 8 miles upstream of Governor Island to house the displaced population of Fort George. The community has a post office, a 30-bed hospital and a police station. There are two banks, 4 retail stores and two restaurants. A hotel provides accommodations and *Air Creebec* offers flights daily, except Saturdays. Chisasibi is accessible by paved road from the *James Bay Highway*.

38 The **tidal ranges** of mean and large tides at the mouth of La Grande Rivière are 1.5 and 2.1 m.

39 A **wharf** is located on the south shore 2 miles downstream of Chisasibi.

40 **Caution**. — A mariner **without local knowledge** is cautioned to make the passage between Pointe Louis-XIV and Fort George Anchorage in **daylight** with **good visibility** of at least 3 miles.

*Chart 5800*

## Fort George and Chisasibi to Wemindji

41 The coast from La Grande Rivière past Wemindji to Eastmain, 100 miles south, has many small bays and wooded points and has numerous islands, islets, **reefs** and **shoals**. Most of the islands are hard to distinguish against the shore and there are few good landmarks.

42 The coastal route to Wemindji and Eastmain follows a lane of sounded water running 5 to 30 miles offshore with depths mostly under 15 fathoms (27 m) and in places as little as 4 fathoms (7.3 m).

43 **Big Island** *(53°44'N, 79°09'W)*, 7 miles SSW of the entrance to La Grande Rivière off the mouth of **Tees Bay**, and **Walrus Point**, to southward, are under 100 feet (30 m) high and treeless.

44 **Earthquake Island**, treeless and 100 feet (30 m) high, lies off **Pointe du Morse**. The point separates **Akwatuk Bay** from **Dead Duck Bay**. A cluster of islets *(53°37'N, 79°13'W)* off Akwatuk Bay stands out well visually and on radar.

45 **Caution**. — Two **shoal rocks**, position approximate, are 7 miles WNW of Earthquake Island. A chain of islets and **rocks** extends 6 miles westward from a point on the mainland shore 6 miles south of Earthquake Island.

46 **Burnt Island**, **Brae Island**, elevation 30 feet (9 m), **Hook Island** *(53°26'N, 79°07'W) (not named on Chart 5800)* and **Black Whale Island** are some of the numerous islands and islets along the coast near the mouth of **Rivière au (du) Castor**. The easternmost of **Comb Islands** rises to 112 feet (34 m).

47 The **tidal ranges** of mean and large tides in this area are 3 and 4 feet (0.9 and 1.2 m).

48 **Goose Islands**, with a maximum elevation of 37 feet (11 m), and **Black Island** lie in a chain of islands extending 5.5 miles off the south entrance point of **Grimmington Bay**.

49 **Pointe au Héron (Huard)**, elevation 100 feet (30 m), is 11 miles south of Goose Islands. There is a chain of islands extending 6 miles NW of Pointe au Héron.

## Offshore islands

50 **Spencer Island** *(53°30'N, 79°43'W)*, a series of gravel ridges covered with moss, grass and scrub brush, is a

prominent landmark on the coastal route. Numerous ducks and geese nest on the island. An islet is 2 miles north.

51 **Caution**. — A **shoal rock** and a **shoal area** with a depth of 3 fathoms (5.5 m), position doubtful, are 6 and 10 miles NNW of Spencer Island.

52 **North Twin Island**, elevation 188 feet (57 m), is moss covered with sloping north and west sides and sandy grass-covered bluffs on its east and south sides; a few trees stand out clearly.

53 **Caution**. — An islet, position approximate, a **shoal reef** and **depths** of 5 to 39 feet (1.5 to 11.9 m) are in the passage between North Twin and Spencer Islands. A large 3-fathom (5.5-m) **shoal**, existence doubtful, is 2.5 to 7 miles NNW of **Cotter Point**, the NW point of North Twin Island.

54 **Anchorage** with good holding in 7 fathoms (12.8 m), mud, has been obtained 1.5 miles off the beach on the north side of North Twin Island; good **anchorage** has also been obtained close off the SE side.

55 **Emily Rock** is one of three above-water rocks lying midway between North Twin Island and **Walter Island** *(53°18'N, 79°40'W)*. Walter Island, treeless and moss covered, is 103 feet (31 m) high with bluff shores. The **island** is **conspicuous** both visually and on radar.

56 **Caution**. — **Shoal depths** of 5 fathoms (9.1 m) are 8 and 11 miles east of Walter Island.

57 **South Twin Island**, a sand and gravel island covered with grass and moss, rises gradually to 140 feet (43 m) and is not a strong radar target. **Lucy Point** is the SW end of the island. A **shallow** cove on the east side of the island contains a wide, **boulder-strewn mud flat** flanked by a beach.

58 **Caution**. — **Shoal water** extends 1 mile off the north, east and south shores of the island.

59 Good **anchorage** has been obtained close off the south side of South Twin Island.

60 **Caution**. — A breaking **reef**, position approximate *(1972)*, is 11 miles ENE of South Twin Island. A 7-fathom (12.8-m) **depth** is 1 mile farther east. An extensive area of possible **shoals** 11 miles SE of South Twin Island is probably joined to an area of **depths** under 10 fathoms (18.3 m) 5 miles farther WSW.

61 **Caution**. — A **shoal reef** and a 29-foot (8.8-m) **depth** are 10 miles west and 16 miles WSW of Pointe au Héron.

## Approaches to Wemindji

62 **Caution**. — The charted **depths** are from reconnaissance soundings. Special care is recommended.

63 **Caution**. — **Local knowledge** is recommended to approach the outer and inner anchorages.

64 **Solomons Temple Islands** is a group of islands and islets 12 miles SW of Paint Hills Bay; the highest has an elevation of 100 feet (30 m). A second group of islands lies 2 miles to the north.

65 **Pebble Island**, 4 miles south of Solomons Temple Islands, rises to 100 feet (30 m) on the north side.

66 **Caution**. — A number of islets and **rocks** and **shoal depths** of 3 fathoms (5.5 m) or less are among the islands described above and between the islands and the mainland shore.

67 **Paint Hills Islands** *(52°57'N, 79°00'W)* and **Walrus Islands** are two chains of rust-coloured rocky islands with elevations of 100 to 200 feet (30 to 61 m). The largest Walrus Island is divided into two parts; **North Walrus Island** and **South Walrus Island**. These are prominent, rising to 250 feet (76 m), and are usually the first landmark to be sighted when approaching the coast from South Twin Island.

68 **Caution**. — A **rock**, 3 feet (0.9 m) high, is 2 miles SW of South Walrus Island.

69 **Pointe Bourlamaque**, at the tip of **Pointe Apiskutikutasich**, is the south entrance point of Paint Hills Bay.

70 The settlement of **Wemindji** *(53°00'N, 78°49'W)*, population 1,095 *(2001)*, is on the NE shore of **Paint Hills Bay** on the north side of the mouth of **Maquatua River**. The community has a post office, bank, medical and dental services and a police station. There are two retail stores, 5 restaurants and 1 hotel in the settlement. *Air Creebec* provides flights daily except Saturdays. Wemindji is accessible by gravel road from the *James Bay Highway*.

71 Vessels drawing 8 feet (2.4 m) or less can find **anchorage** off the settlement. Vessels of greater draught can find **anchorage** in 4 to 5 fathoms (7.3 to 9.1 m), sand and clay, 1.5 miles NW of Pointe Apiskutikutasich. A depth of 21 feet (6.4 m) can be carried to this anchorage.

72 The landing beach is flat and **boulder-strewn**.

## Wemindji to Eastmain

73 **Moar Bay** has **Monkey Islands** *(52°49'N, 78°50'W)*, a group of islands and **rocks**, in its central part. The largest island has an elevation of 100 feet (30 m). **Rivière Sabascunica**, **Rivière Clergue** and **Rivière du Peuplier** flow into the bay.

74 **Sheppard Island** is wooded and has an elevation of 100 feet (30 m). It is the largest island of a chain of islands and **rocks** extending 5 miles off **La Longue Pointe**.

75 **Black Stone Bay** *(52°40'N, 78°46'W)* lies 6 miles SSE of La Longue Pointe.

76 **Caution**. — This stretch of coast has islets and **rocks** up to 8 miles offshore.

77 **Old Factory Bay**, filled with islets and **shoals**, lies at the mouth of **Rivière du Vieux Comptoir**. The large island in the river mouth is the site of an abandoned settlement.

78 **Historical note**. — The *Hudson's Bay Company* established a trading post on the island at the mouth of Rivière du Vieux Comptoir, or Old Factory River, in 1939. A Cree settlement, Old Factory, grew around this post. The *Hudson's Bay Company* relocated to a more favourable location on the mainland at Paint Hills Bay in 1959 and the community followed, becoming Nouveau Comptoir, or New Factory. The name became Wemindji in 1984.

## Offshore islands

79 **Weston Island** *(52°33'N, 79°36'W)*, composed of sand and gravel, is covered with moss and grass. It is low except for a **conspicuous** sand **bluff** rising to 100 feet (30 m) at its south end.

80 **Caution**. — **Depths** of 4 to 6 fathoms (7.3 to 11 m) are along the sounded track that passes between Weston Island and Pebble Island *(previously described)*, 19 miles NE.

81 **Anchorage** is available off the south side of Weston Island, and also off a neck of land on the west side of the island, 2 miles off in 19 fathoms (35 m), mud.

82 An unnamed cluster of islands and **rocks**, the two largest islands 100 feet (30 m) high, lies 15 miles east of Weston Island; scattered islets lie between this cluster and the mainland shore.

83 The largest of **Cape Hope Islands** *(52°26'N, 78°46'W)*, elevation 300 feet (91 m), is **conspicuous**. The mainland shore rarely exceeds 200 feet (61 m) in elevation.

84 **Gull Island** is 10 miles SW of Cape Hope Islands. There are widely spaced islets and rocks up to 6 miles NW.

85 **Caution**. — A **rock** with a depth of 19 feet (5.8 m) lies 8 miles NNW of Gull Island.

86 **Trodely Island** *(52°15'N, 79°25'W)* is wooded and rises to 200 feet (61 m) in its central part. **Tiders Islands** are 4 miles to the NW.

87 **Caution**. — **Drying reefs** are between Trodely and Gull Islands.

88 **High Rock Island** and **Spit Island**, close off the mainland shore with elevations of 100 and 200 feet (30 and 61 m), are the largest of the numerous islands between Cape Hope Islands and the coast. **Conn River** enters James Bay 3 miles SE of Spit Island. The river has a chain of islets extending 7 miles WSW from its mouth.

## Approaches to Eastmain

89 **Caution**. — The charted **depths** are from reconnaissance soundings. Special care is recommended.

90 **Caution**. — **Eastmain River** is **shallow** and its mouth is scattered with **boulders** and is obstructed by **shoals** and rocky islets.

91 The outermost of numerous islets and **rocks** extending westward from the river mouth for almost 10 miles are known as **Flock Geese Islands** *(52°14'N, 78°48'W)*.

92 **Caution**. — A **rock** awash, position approximate, is close north.

93 **Inner Flock Geese Islands**, existence doubtful, are 5 miles south.

94 **Caution**. — **Dangerous rocks** are north of Inner Flock Geese Islands.

95 Several unnamed islands bordered by **drying flats** are 6 to 12 miles WSW of Flock Geese Islands. **Anchorage** in 40 feet (12.2 m), clay and sand, with good holding and some protection can be obtained 2 miles east of the easternmost of the unnamed islands in 52°10'N, 78°54'W.

96 **Caution**. — **Shoal depths** exist between this berth and the river mouth; **anchorage** can be found closer in, in shallower water, if desired.

97 **Caution**. — The **approach** to Eastmain River was difficult even for small craft; however, it could be navigated at high water large tides, for 6 miles upstream by craft drawing up to 8 feet (2.4 m). The outflow of the river has been reduced by 90% as a result of the *James Bay Hydroelectric Project*. Local knowledge is essential.

98 The settlement of **Eastmain** *(52°15'N, 78°30'W)*, population 613 *(2001)*, is 2 miles within the entrance of Eastmain River on the south shore. The settlement has a post office, health clinic and police station. There is a general store, a grocery store, a restaurant and a hotel in the community. *Air Creebec* provides flights daily except Saturdays. Eastmain is accessible by gravel road from the *James Bay Highway*.

99 The **tidal stream** is reported to attain a rate of 5 knots at the settlement.

100 A small **pier** at the settlement has a depth of 5 feet (1.5 m) at its end *(1972)*.

## Eastmain to Waskaganish (Fort-Rupert)

101 The coast is low and marshy with no prominent features from the entrance of Eastmain River to Pointe Goyeau (Snape Point), 33 miles SW. There are a number of islands and islets offshore.

102 **Rivière au Mouton (Sheep River)** and **Rivière Jolicoeur**, with **Pointe Loon (Point)** *(52°03'N, 78°42'W)* at its north entrance point, enter James Bay 8 and 14 miles SSW of the Eastmain River mouth.

103 **Caroline Island** is the outermost of a group of islands and rocks lying off the NE entrance point of **Boatswain Bay**. **Cormorant Rock**, position doubtful, elevation 14 feet (4 m), lies 3 miles to the SW.

104 **Strutton Islands**, 9 miles WNW of Pointe Loon, are wooded with spruce; the west island rises to 100 feet (30 m), the east to 200 feet (61 m).

105 **Strutton Harbour** *(52°06'N, 78°59'W)*, the channel between Strutton Islands, has been used by supply vessels and offers good shelter from most winds. The harbour has steep sides with deep water inshore and an average depth of 7 fathoms (12.8 m).

106 **Caution**. — The **tidal streams** flow strongly through Strutton Harbour.

107 **Charlton Island** *(51°59'N, 79°27'W)*, with **Wolf Islet** 1.9 miles off its NE shore, is a wooded island with a maximum elevation of 100 feet (30 m).

108 **Caution**. — **Rocks** and **shoal water** may extend for a considerable distance off the west shore; a 3-fathom (5.5-m) **depth** is 10 miles west of the island.

109 **Caution**. — **Lisbon Rocks** are 9 miles SW of Charlton Island. All are **submerged or drying** except for a **rock** 35 feet (11 m) high, position doubtful, near the NW end of the group. This rock is a good visual and radar target; there is breaking water for some distance SE.

110 **Carey Island** is separated from Charlton Island by a wide channel with a least mid-channel depth of 4 fathoms (7.3 m).

111 **Caution**. — A **shoal spit** with a depth of 4 feet (1.2 m) extends 2 miles from the east tip of Charlton Island, the NW entrance point of the channel.

112 **Charlton Harbour** *(51°58'N, 79°18'W)*, the site of the abandoned *Hudson's Bay Company* post of **Charlton Depot**, lies between Charlton Island and **Danby Island**. The harbour is approached from NE through a channel with a depth of 25 feet (7.6 m). **Anchorage** off the site of the former post provides good shelter from all winds and has been used by vessels drawing 24 feet (7.3 m).

113 **Caution**. — Danby Island has a **spit** with a depth of 7 feet (2.1 m) extending 1 mile from its north point and an extensive **drying flat** off its NE side. A **bar** across the south entrance to the harbour is reported to have a **depth** of 18 feet (5.5 m) at high water. **Depths** of 10 feet (3 m) and less are up to 4 miles south of the south entrance.

*Charts 5414, 5800*

## Rupert Bay

114 **Rupert Bay** is entered between **Pointe Goyeau (Snape Point)** *(51°46'N, 79°02'W)* and **Pointe Saouayane**, a low point 12 miles SW on **Péninsule Ministikawatin**. **Colline Sherrick** is a **conspicuous hill** behind Pointe Goyeau.

115 **Caution**. — Rupert Bay is **obstructed** by **banks** and **shoals** and the only navigable channels are narrow passages kept open by river currents.

116 **Caution**. — **Tent Island** *(51°49'N, 79°06'W)*, in the approaches to Rupert Bay 3.5 miles NW of Pointe Goyeau, has **depths** under 12 feet (3.7 m) extending 1.7 miles north and 1.4 miles south. A **drying spit** with **rocks awash** at its end extends 1.8 miles west of the island.

117 **Caution**. — **Jacob Island**, 3 miles SW of Tent Island, has **depths** under 12 feet (3.7 m) extending 1 mile off its south side.

118 The **tidal ranges** of mean and large tides in this area are 6 and 8.5 feet (1.8 and 2.6 m).

## Approaches to Waskaganish (Fort-Rupert)

119 The track usually followed into Rupert Bay leads through **Emelia Passage**, entered between Tent and Jacob Islands, with depths of 13 to 60 feet (4 to 18 m).

120 **Dixon Island**, **McNab Rocks**, **Moss Island**, **Gushue Island** and **Dufourmentel Rocks** lie on a long **shoal area** that extends south from Tent Island for 9 miles along the east side of the passage to **Stag Island** *(57°39'N, 79°04'W)*. **Stag Rock** lies 6 miles SE of Stag Island; both are reported to be good radar targets. There is a **conspicuous rock** on the NE part of Stag Island.

121 **Caution**. — **Ten Foot Patch** is on the west side of Emelia Passage, 2 miles SE of Jacob Island. Farther SE, the west side of the passage is formed by a long **spit** with **depths** under 12 feet (3.7 m).

122 **Chrissie Thomey Passage** *(51°50'N, 79°00'W)* cuts through the long shoal area between Tent and Dixon Islands and is bordered on its east side by **Perkins Rock**, **Maloney Islands**, **Fredericks Island** and a number of **rocks**.

123 **Caution**. — **Isolated** 14 and 17-foot (4.3 and 5.2-m) **shoal patches** are in mid-channel in Chrissey Thomey Passage.

124 **Boat Passage** runs south from Chrissie Thomey Passage along the east side of the long shoal area and is bordered on its east side by **Bossard Island**, **Prophet Island**, **Moore Island**, **Nicolson Rock**, **Hallé Rock**, **Stevens Island**, **Draulette Island**, **Lefaivre Island** and **Barboteau Rock**. With local knowledge, a depth of 14 feet (4.3 m) can be carried through Boat Passage past Stag Rock to the outer end of Rivière Rupert approach channel.

125 **Mallet Cove** *(51°44'N, 78°59'W)*, **shallow**, and **Hall Cove**, probably **shallow**, indent the east shore of Rupert Bay. **Pointe du Bois Brûlé**, the south entrance point of Hall Cove, has an elevation of 100 feet (30 m).

126 **Rivière à la Truite**, with a **conspicuous rock** at its entrance, and **Rivière Pontax (River)**, with **Jolly Islands** in its mouth, enter Rupert Bay 3 and 6 miles SE of Pointe du Bois Brûlé.

127 **Caution**. — **Rivière Nottaway** and **Rivière Broadback (River)**, at the head of Rupert Bay, are **obstructed** by **rapids**. **Île Lemoine** and **Île Middleton** lie off the mouths of these rivers. **Rivière Octave** enters the west

shore of the bay 8 miles from the head. The SW portion of the bay is **not surveyed**.

128 **Inenew Passage**, down the west side of Rupert Bay, becomes very narrow in its inner part; it has only been sounded as far as **Pointe à l'Ours Noir (Black Bear Point)**. The **least** known **depth** to the point is 19 feet (5.8 m).

129 **Caution**. — **Depths** under 12 feet (3.7 m) extend up to 2 miles off Pointe Saouayane and a **shoal**, **depth not known**, is reported to lie 4 miles NW of this point.

130 **Cabbage Willows Bay** *(51°32'N, 79°13'W)*, believed to be very **shallow**, indents the west side of Rupert Bay between **Pointe de la Consolation** and Pointe à l'Ours Noir.

131 **Caution**. — The outer end of the approach channel to Rivière Rupert is 2.8 miles SW of **Pointe du Peuplier**; the channel has **depths** of only 3 to 6 feet (0.9 to 1.8 m). The water is deeper in the river entrance. At high water, the river is navigable for 4 miles by craft drawing up to 8 feet (2.4 m).

132 The approach channel is marked by privately maintained **beacons**. Port-hand beacons consist of bush-tipped stakes; those on the starboard hand are stakes with crosspieces.

133 The settlement of **Waskaganish (Fort-Rupert)**, population 1,699 *(2001)*, is near the head of Rupert Bay on the south bank of the mouth of **Rivière Rupert** *(51°29'N, 78°45'W)*. The community has a post office, a bank, a police station and a medical clinic. There are a variety of retail stores and restaurants and a hotel. *Air Creebec* provides flights daily except Saturday. Waskaganish is accessible by gravel road from the *James Bay Highway*.

134 **Caution**. — The settlement is on a point with deep water inshore, but there are swampy shores east and west of the point with **shoal water** extending off for 0.1 mile and more. **Shoal water** extends off the north shore for 0.4 mile.

135 An **aeromarine radiobeacon** near the settlement transmits on 351 kHz with identification YKQ (— • — — — • — — — • —).

*Chart 5800*

### Waskaganish to Hannah Bay

136 The shoreline of the head of James Bay between **Pointe de la Fougère Rouge** *(51°39'N, 79°21'W)* and **Netitishi (Nattabisha) Point**, 36 miles SW, is low and marshy and has **drying flats** stretching up to 3 miles offshore.

137 **Caution**. — All the points are low and inconspicuous. The only relatively high ground is inland between **Pointe Cachechu** and **Pointe Mésaconane** where the terrain rises to 100 feet (30 m).

138 **Chiyask (Gull) Bay**, a shoal bay lying between Pointe Mésaconane and **Chiyask (Gull) Point**, is on the boundary between the provinces of Québec and Ontario.

139 **Iskoyaskweyau (East) Point** *(51°24'N, 79°41'W)* is the east entrance point of **Hannah Bay**. **Missisicabi River**, **Piscapecassy River**, **Harricanaw River** and **Kesagami River** flow into Hannah Bay. Netitishi Point, the west entrance point of Hannah Bay, is low and inconspicuous.

140 **Caution**. — Hannah Bay is **not surveyed**.

## James Bay — West shore

141 The west coast of James Bay is generally low and swampy and, unlike the east coast, is regular with very few islets. There are no prominent or easily identifiable land features. Trees on the shoreline can usually be seen at 8 miles.

142 **Caution**. — Most of the coastal waters of the west side of James Bay are **not surveyed** and should not be entered without local knowledge.

### Cape Henrietta Maria to Albany River

143 **Cape Henrietta Maria** *(55°09'N, 82°20'W)*, the WNW entrance point of James Bay, is a narrow peninsula 15 feet (5 m) high composed of disintegrated limestone.

144 **Caution**. — Sparse soundings indicate that the area NW of the cape is very **shoal**.

145 The **tidal ranges** of mean and large tides near Cape Henrietta Maria are 7.2 and 9.8 feet (2.3 and 3 m).

*Charts 5476, 5800*

146 **Hook Point**, 17 miles SSE of Cape Henrietta Maria, is low, swampy and treeless.

147 **Caution**. — **Depths** under 6 feet (1.8 m) extend 1 mile offshore in this area and **dangers**, position approximate, are up to 8 miles offshore 12 miles south of the point.

148 An air defence **radar site**, abandoned in 1965, with parabolic **antennae** standing 120 feet (36.5 m) high, is 7 miles SW of Hook Point *(2005)*.

### Offshore islands

149 **Bear Island** *(54°21'N, 81°06'W)*, the largest of a group of islands in the north part of James Bay, is the site of an **abandoned airstrip** and military installation; there is only one small building left standing *(1979)*. The island is highest at the north end, black in appearance and devoid of vegetation.

150 **North Bear Island**, **South Bear Island** and **Two Cubs Islands** are other islands in the group. **Sunday Island** *(54°19'N, 80°40'W)*, 15 miles eastward, is low and treeless.

151 **Caution**. — **Sheldrake Shoal**, with a depth of 4 feet (1.2 m), lies 1 mile east of the south end of

Bear Island. **Whale's Back Rock**, an above-water rock, position approximate, lies 1.4 miles SSW of Bear Island. **Shoals** extend NNE of South Bear Island 1.8 miles towards Sheldrake Shoal.

152 **Anchorage** can be obtained in the berth close off the SE part of Bear Island but holding is poor over a bottom of flat glaciated rock.

153 A landing beach in a cove west of **Polar Point** is usable only by small landing craft for 2 hours either side of high water.

154 **Caution**. — Many **reefs** and **boulders** make the approach to the beach hazardous, particularly **rocks** extending 0.5 mile north of Polar Point.

*Chart 5800*

155 **Caution**. — **Gasket Rock** *(54°07'N, 81°30'W)*, with a depth of 6 feet (1.8 m) or less, lies 19 miles SW of Bear Island. A similar **rock**, existence doubtful, is 12 miles farther SSW.

156 The coast continues to be low and swampy and is bordered by **drying flats** between Hook Point and Ekwan Point, 97 miles south. **Big Owl Creek**, **Lakitusaki River**, **Opinnagau River**, **Patchepawapoka River**, **Nowashe Creek** and **Swan River** are the named of many creeks and rivers that enter the bay along this stretch. The abandoned buildings of the former *Hudson's Bay Company* post of Lake River are on Lakitusaki River.

157 **Akimiski Island** *(53°00'N, 81°25'W)* is swampy, mostly low, partly wooded and is composed of gravel, sand and boulders arranged in low rolling ridges. The island reaches an elevation of 100 feet (30 m) along its south coast but is said to be a poor radar target. The shores are bordered by **drying flats**.

158 **Houston Point** and **Cape Duncan**, the NE and SE extremities of Akimiski Island, are low and flat. **Gullery Island** and several unnamed islets lie close SE of Cape Duncan.

159 **Caution**. — **Drying shoals** and possible **shoals** are up to 19 miles off the north and east shores of Akimiski Island and up to 17 miles SW and SE of Cape Duncan, including **Albert Shoal** and **Bare Banks**. From sparse surveys in the area, it appears that **shoal water** extends a considerable distance off the north and east sides of Akimiski Island.

160 **Gasket Island** *(52°25'N, 80°15'W)*, a sandy island 23 miles SE of Cape Duncan, has **drying flats** on the north side.

161 **Caution**. — A **rock awash** lies 3 miles NNE of Gasket Island.

162 **Akimiski Strait** *(53°08'N, 82°05'W)* is **obstructed** by islets, **rocks** and **drying flats** and is reported to be **not navigable**.

## Approaches to Attawapiskat

163 **Attawapiskat River** discharges through a large delta divided by several channels into large grassy islands bordered by extensive **tidal flats**. The north channel is the deepest and a draught of up to 7 feet (2.1 m) can be carried for 6 miles at high water. The water is deepest along the north shore of the river but the clay banks are eroding and care should be taken to avoid fallen trees.

164 Attawapiskat River is approached from SE only. During the navigation season, the channel is marked by **buoys** and **beacons** placed and maintained by *Moosonee Transportation Ltd*. The buoys are white 45 gallon oil drums; the beacons are poles topped by clusters of branches. Local knowledge is required.

165 The **tidal range** varies from 5 to 6.6 feet (1.5 to 2 m).

166 **Caution**. — Because of the **shoal water** extending far out from the shore, the **tidal range** is greatly affected by the **wind**. The river **current** reverses on a rising tide.

167 The settlement of **Attawapiskat**, population 1,293 *(2001)*, is on the north shore 6 miles within the north channel of Attawapiskat River. The community has a post office, a police department and a hospital with visiting doctors and dentists. A *Northern Store* in the settlement has an automated bank machine and there are several local retail businesses and a motel. *Air Creebec* provides flights daily except Saturday and *Keeshig Airlines* offers fixed-wing aircraft charters. A winter road connects Attawapiskat with Moosonee and other communities on the west shore of James Bay.

168 The Roman Catholic **church** is the most prominent building in the settlement. A radio **tower** near the settlement is 150 feet (46 m) high; it displays red aircraft obstruction **lights**.

169 An **aeromarine radiobeacon** transmits on 260 kHz with identification YAT (— • — — • — —) from the tower.

170 The mainland coast SW of Akimiski Island, between the Attawapiskat and Albany Rivers, continues to be low, featureless and fronted by **drying flats**. Numerous rivers enter this stretch; the named ones are **Lawashi River**, **Kapiskau River** and **Big Willow River**.

171 A **conspicuous** microwave **tower**, elevation 365 feet (111 m) with red aircraft obstruction **lights**, is near the mouth of Big Willow River.

*Charts 5800, 5476*

## Approaches to Kashechewan and Fort Albany

172 **Albany River** enters James Bay 50 miles SE of Attawapiskat. The river splits into 3 main channels 19 miles

from the coast; these are **Chickney Channel**, **North Channel** and **South Channel**.

173 **Albany Island** and **Fafard Island** lie in the mouth of Albany River. **Ball Island**, with **Anderson Point** *(52°14'N, 81°28'W)* at its SE end, is separated from Albany Island by **The Gutway (Cutaway Channel)**. **Clark Island** lies in South Channel 4 miles west of Anderson Point. **Sinclair Island** lies 8 miles WSW of Anderson Point. **Anderson Island** lies close east of Sinclair Island.

174 **Caution**. — Albany River can be approached only from east or SE as the north approach is **obstructed** by **shoals**.

175 **Caution**. — Clay **tidal flats** extend more than 2 miles off the mouth of Albany River and **depths** of less than 6 feet (1.8 m) are found 6 miles off the river mouth. Sand and gravel **bars**, with only 1 foot (0.3 m) over them, lie across North and South Channels. At high water, a draught of 7 feet (2.1 m) can be carried through both channels.

176 **Caution**. — Large **boulders** 5 to 6 feet (1.5 to 1.8 m) in diameter are scattered over the tidal flats. At **high water**, these boulders are only inches below the surface. They are **invisible** in the muddy water and are a serious **danger to navigation**.

177 **Caution**. — The clay **banks** of the river are **eroding** and care must be taken to avoid fallen trees.

178 **Caution**. — Because of the **shallow** coastal **waters**, **tides** are greatly affected by **winds**. The river **current** reverses on a rising tide.

179 North Channel is marked by private **buoys** and **beacons**. The buoys are spar buoys and spherical styrofoam buoys. The beacons are poles with wreaths on crosses. The outer two beacons mark a **bar** and should be kept to starboard; the buoys should be kept to port. A **beacon** at the river mouth should be kept to port. The innermost buoy is on the north side of the channel well upstream *(1976)*. From the innermost buoy, the route leads close along the north shore to Kashechewan where there is a small floating **wharf**. Local knowledge is required.

180 The settlement of Kashechewan *(52°17'N, 81°39'W)* is on the north side of North Channel, NW of **Kakago (Iserhoff) Island**. **Linklater Island** is close east of Kakago Island.

181 South Channel is also marked by private **buoys** and **beacons**. The buoys are spar buoys and spherical styrofoam buoys. The beacons consist of poles with horizontal bars forming crosses. In the entrance to South Channel, beacons are generally kept to starboard and buoys to port but local knowledge is essential. The buoy farthest upstream is 2 miles west of Anderson Point *(1976)*. From this buoy, the route leads along the north side of the channel to east of Clark Island. From here, the route crosses to the south shore and continues as far as the east point of Anderson Island, the head of barge navigation. There is a large floating steel **wharf** and a wooden **seaplane wharf** here.

182 The site of Fort Albany *(52°12'N, 81°41'W)* is 3 miles farther WSW, on the south shore of South Channel, abreast of the east end of Sinclair Island.

183 An **aeromarine radiobeacon** near Fort Albany settlement transmits on 216 kHz with identification YFA (— • — — • • — • • —).

184 The settlements of **Kashechewan** and **Fort Albany** have a combined population of 2,949 *(2001)*. Each community has a post office and there is a shared police department. Kashechewan has a nursing station; Fort Albany has a 17 bed hospital with visiting doctors and dentists. Kashechewan has a *Northern Store* with an automated bank machine. There are several retail stores and restaurants between the two settlements and accommodation is available. *Air Creebec* provides flights daily except Saturdays.

*Chart 5800*

## Albany River to Moosonee

185 Between Albany River and Moose River, 60 miles SE, the coast continues to be low and featureless. **Drying flats** border the shore.

186 Named points on this coastline are **Nomansland Point** *(52°03'N, 81°05'W)*, **Cockispenny Point**, **Halfway Point**, **Longridge Point**, **Paskwachi Point** and **Big Piskwanish Point**. Some of the many rivers entering James Bay along this stretch are **Kinosheo (Kinoje) River**, **Nettichi River**, **Kabiskaubakau River** and **Lawabiskau River**.

187 **Conspicuous** microwave **towers** are on Cockispenny Point and 4 miles west of Big Piskwanish Point. Both towers are 310 feet (94 m) in elevation and show red air obstruction **lights**.

*Chart 5860*

## Approaches to Moose River

188 **Northbluff (North) Point** *(51°30'N, 80°27'W)*, 7 miles north of the mouth of Moose River, rises only a few feet above the level of the surrounding flat terrain but is the first object definable on radar when approaching from northward.

189 **Ship Sands**, on the NW side of the river mouth, is a **drying flat** composed of firm sand and mud with scattered **rocks** and **boulders**; **The Elbow** is its NE end. **East Bar**, covered with scattered **boulders** 3 to 6 feet (0.9 to 1.8 m) high, and **Nielson Bar** form the SE side of the river entrance.

190 **Ship Sands Island** *(51°21'N, 80°27'W)*, in the mouth of **Moose River**, is separated from **Sandy Island** to the west by **Wavy Creek**.

191 **Caution**. — Extensive **drying flats** of mud or sand, peppered in places with **boulders**, extend 1 to

5 miles offshore in the approaches to Moose River. **Depths** under 12 feet (3.7 m) reach a further 1.5 miles offshore.

192 **Sand Head** *(51°25'N, 80°20'W)*, the outermost of the **flats** and devoid of boulders, dries from 1 to 6 feet (0.3 to 1.8 m).

193 The **tidal ranges** of mean and large tides are 7.2 and 9.8 feet (2.2 and 3 m) in the vicinity of Sand Head.

194 **Long Point**, the south entrance point of Moose River, is low and inconspicuous.

195 This is a resting area for geese and there are several **bird sanctuaries** near the river mouth.

196 **Le Moyne Passage**, the eastern and recommended entrance passage, has mid-channel depths of 6 to 11 feet (1.8 to 3.4 m).

197 **Caution**. — The passage has relatively calm water in northerly winds but heavy breakers frequently occur in the **shoal water** close south.

198 **Caution**. — **Duncan Passage**, not buoyed and no longer used, has **depths** of 1 to 3 feet (0.3 to 0.9 m). **The Bar** *(51°26'N, 80°20'W)*, a **drying shoal** in the mouth of Duncan Passage, causes breakers and a confused sea at any stage of the tide in north winds.

199 The approach to Le Moyne Passage is marked by a **lighted buoy**. The main entrance channel upstream of the junction of Le Moyne and Duncan Passages is marked by **lighted** and **unlighted buoys**. The positions of the buoys are approximate; they may be moved to mark the best channels.

200 Unsheltered **anchorage** can be found in the approaches to Le Moyne Passage outside the outer buoy in 4 to 5 fathoms (7.3 to 9.1 m), mud, with good holding.

201 Le Moyne and Duncan Passages converge into one main channel 1 mile SW of Sand Head.

202 **Sand Head Beacon**, position approximate, is on the SE side of Sand Head; it consists of a **radar reflector** fitted on a single **pole**. **Shears Beacon**, on the east side of Ship Sands 2.5 miles SW of Sand Head Beacon, is a **radar reflector** mounted on poles in the form of **sheer legs**. Shears Beacon is not readily visible because of its small size but the radar reflectors here and on Sand Head Beacon have been detected at 8 to 10 miles. Both beacons are privately maintained; their condition is unknown *(2006)*.

203 A bird watch **tower** *(51°20'N, 80°27'W)* on the SE shore of Ship Sands Island is topped by a **conspicuous spherical structure** *(1988)*.

204 **Anchorage** with good holding in 14 feet (4.3 m), mud and sand, but no shelter from NE winds can be obtained in the berth 0.9 mile ENE of the bird tower on Ship Sands Island.

*Chart 5861*

205 South of Ship Sands Island, the entrance channel divides into North Channel and South Channel, separated by a chain of islands and **drying flats**. These include **Horseshoe Islands**, **Tomisidenik Island**, **Moose Flats**, **Little Duck Island**, **Big Duck Island**, **Butler Island**, **Charles Island**, **Moose Factory Island**, **Sawpit Island** and **Bushy Island**.

206 **Caution**. — **South Channel** is **obstructed** at its NE end by **Horseshoe Shoals** *(51°19'N, 80°27'W)*; the channel has a **depth** of 1 foot (0.3 m) and is navigable only by canoes.

207 **North Channel** has a least depth of 4 to 5 feet (1.2 to 1.5 m) in its narrowest part, south of **Little Duck Bar** *(51°19'N, 80°32'W)*.

208 North Channel is marked by **lighted** and **unlighted buoys**; these may be moved to mark the best channel.

209 **Moosonee**, population 1,916 *(2001)*, is on the NW shore of the river between Butler Creek and Halfway Creek. The community has a post office, bank, police department and a health care clinic. *Purolator Couriers* offers document and small package expediting. There are a variety of retail stores and restaurants and a liquor store. Accommodation is available in 4 hotels. *Air Creebec* provides daily air service except Saturdays and there are helicopter and fixed-wing aircraft for charter at *Moosonee Airport*. A passenger and freight railway service, operated by *Ontario Northland Railways*, connects Moosonee to Cochrane, Ontario. *Moosonee Transportation Ltd.* provides freight and tanker barge service to communities on James Bay and southern Hudson Bay.

210 **Moose Factory**, population 1,430 *(2001)*, is a First Nations Reserve on the island of the same name. The community has a post office that also offers some banking services, an automated bank machine, a police department and a regional hospital that serves the west shore of James Bay. There are several retail stores and restaurants and accommodation is available in 2 hotels. Travellers must take the local ferry in summer or the local taxi in winter to get to the mainland airport or train station.

211 The settlements, 10 miles within the entrance of Moose River, can be reached at high water by craft drawing 8 feet (2.4 m).

212 Near Moosonee are **conspicuous** microwave and radio **towers**, fitted with red aircraft obstruction **lights**, and a church **spire** that is sometimes **illuminated**.

213 *Charles Island* **light** *(2632)* is on the NE end of an unnamed island just SSW of Charles Island.

214 An aeronautical rotating **light** is 0.5 mile NE of Butler Creek.

215 An **aeromarine radiobeacon** near the settlement of Moosonee transmits on 224 kHz with identification MO (— — — — —).

216 **Anchorage** with limited swinging room can be found off Moosonee. There is a **seaplane anchorage**, marked by buoys, off Butler Island.

BIG DUCK ISLAND
MOOSONEE

217 *Moosonee Transportation Ltd.* sets up a floating **wharf** at Moosonee during the navigation season. The wharf consists of a ramp extending to a moored barge. Barges 170 feet (52 m) long drawing 6 feet (1.8 m) berth at this wharf, near the end of the railway spur line.

218 **Caution**. — Several small **wharves** are farther upstream but there is limited turning space due to the extensive **shoal** extending NE from **Maidmans Islands**.

219 A **submarine power cable** and an **overhead power cable** with a clearance of 50 feet (15.2 m) cross the channel between Moose Factory Island and Sawpit Island. An **overhead power cable** with a clearance of 40 feet (12.2 m) runs from Bushy Island westward across the Moose River to the shore.

220 The average thickness attained by level **fast ice** at Moosonee is 86 cm with a record maximum thickness of 130 cm *(1983)*. Break-up normally begins during the third week of April with the river clearing of ice early in the second week of May. Freeze-up usually begins during the second week of November with a complete ice cover forming by the last week of the month. Two to four weeks variation in break-up and freeze-up dates can occur.

*Charts 5800, 5860*

221 **Caution**. — The land around Moose River estuary is flat and **featureless**. Northbluff Point is the first return on radar, and has been detected at 9 miles. Good visual bearings cannot be observed until 4 miles from the fairway buoy.

# Southampton Island (South Side) and Chesterfield Inlet

## Southampton Island (South Side) — General

*Chart 5449*

1 The south coast of **Southampton Island** *(64°30'N, 84°00'W)* forms the north side of Hudson Bay. The coast is mostly low and marshy, backed farther inland by gently rounded plateaus. These plateaus reach elevations of 600 to 800 feet (183 to 244 m) in places and stand out clearly as horizontally bedded limestone on a base of darker crystalline rock. Parts of the coast have a shore of sand bars and sand spits with flights of raised beaches that end inland at the limestone plateaus. The raised beaches are gradually created as the earth's crust rebounds from the last ice-age. In the west the coast is backed by wide tracts of flat marshland. **Bell Peninsula** is the SE part of Southampton Island.




1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

2 **Caution**. — **Drying flats** and **shoal water** border most of the shore and there are **shallow mud flats** at the heads of the bays.

3 Coral Harbour is the only refuge for craft drawing more than 3 or 4 feet (0.9 or 1.2 m). Anchorages that may be suitable for small craft are found at the mouths of some of the rivers; only a few of these can be used at low water.

4 **Caution**. — Except for Coral Harbour and approaches, the coastal waters of the south side of Southampton Island are **not surveyed**.

5 **Caution**. — There are *National Research Council* **firing practice and exercise areas** in Hudson Bay. Mariners are advised to contact a *Canadian Coast Guard* radio station before entering the bay. *(For details see the annual edition of Canadian Notices to Mariners.)*

## Seahorse Point to Coral Harbour

6 **Seahorse Point** *(63°47'N, 80°10'W)*, the east tip of Bell Peninsula, was named in 1616 by Baffin and Bylot for the many walruses they saw here. The point, which separates high land on the north from low land on the south side of Southampton Island, has steep gneiss cliffs 100 feet (30 m) high; low rocky islets lie off the point. **Back Peninsula**, 2 miles SW of Seahorse Point, is a low rounded hill joined to the mainland by a narrow sand **bar**. Three islets lie off Back Peninsula and there are reported to be **rock banks** and small islets almost awash at high water.

7 **Expectation Point** *(63°44'N, 80°22'W)*, 3.5 miles to the west, is low. **Junction Bay**, 3 miles farther west, has a broad shallow valley in its NW part, and many raised beaches extend several miles inland. A few miles north of the bay are two broad rounded hills of dark crystalline rocks, 300 to 400 feet (91 to 122 m) high. These hills contrast with much of the land to the westward.

8 **Leyson Point** *(63°27'N, 80°58'W)* is the south point of Bell Peninsula and the NW entrance point of Hudson Bay. The point is low at its outer end but rises to 100 feet (30 m) 1.5 miles inland. **Anderson Brook** is on the east shore, 4 miles north of the point.

9 **Caution**. — **Shoal water**, over a gradually shelving bottom, borders most of the south coast of Bell Peninsula and extends as far as 5 miles off Leyson Point.

## Evans Strait

10 **Evans Strait** lies along the SW side of Bell Peninsula.

11 The coast of Bell Peninsula between Leyson Point and Native Point, 46 miles to the WNW, forms the north side of Evans Strait. The coast is low with raised beaches, marshes and many ponds for 7 or 8 miles inland and then rises to a rounded limestone plateau. The coast near Native Point is particularly low with many sand bars, lagoons and marshes.

12 **Caution**. — The shore is bordered by **drying flats** and **shoal water** extends offshore.

13 **Native Point** *(63°45'N, 82°31'W)* is said to offer good landing and a safe small-craft shelter in a lagoon on its south side but landing may be possible only near high water.

14 The south side of Evans Strait is bounded by Coats Island *(described in Chapter 4)*. **Cape Prefontaine** *(62°59'N, 82°16'W)*, the north end of the island, is made of raised beaches with an elevation of 200 feet (61 m). The north coast of Coats Island is bordered by **drying flats**. Cape Pembroke *(described in Chapter 4)* is the NE end of Coats Island.

15 **Bencas Island**, 82 feet (25 m) high, off the north shore of Coats Island, is said to have a good harbour for small craft at its north end with a depth of 5 feet (1.5 m). There is a 12-fathom (22-m) patch 3 miles NE of Bencas Island.

16 **Caution**. — The passage south of the island has a reported **depth** of 5 fathoms (9.1 m) and a fossilized coral bottom with very **poor holding**.

17 **Calanus Bay**, on the north shore of Coats Island SW of Bencas Island, is **shoal**. There are many ponds behind the shores of the west half of the bay.

18 **Cape Netchek** *(62°55'N, 83°17'W)*, the NW point of Coats Island, is only 5 feet (1.5 m) high at its outer end. The land behind the cape, with raised beaches and many lakes, reaches an elevation of 100 feet (30 m) 4 miles inland.

19 **Walrus Island** *(63°16'N, 83°39'W)*, 22 miles NNW of Cape Netchek, is rock and rises abruptly from the water; it contrasts sharply with the low flat shore of Southampton Island and is a good radar and visual target.

20 *Walrus Island* **light** *(2537)* is in the middle of the island.

21 The west side of Coats Island is a low plain with many ponds. Raised beaches rise to 100 feet (30 m) 3 to 5 miles inland. **Santianna Point** is the low west end of Coats Island.

22 **Caution**. — **Shoal water** extends off Santianna Point and probably most of the west coast of the island. **Banks** with depths of 12 and 15 fathoms (22 and 27 m) lie 12 miles NNW and 18 miles west of the point.

## Fisher Strait

23 **Fisher Strait**, NW of Coates Island, is entered from SW between Santianna Point and **Cape Low** *(63°06'N, 85°18'W)*, at the south end of Southampton Island. **Ranger Brook** empties over a shore of sand and gravel west of Cape Low.

24 **Caution**. — The NW shore of Fisher Strait shelves gradually and is bordered with **drying flats** and **shoal water** for 5 miles or more offshore. Even small craft must keep several miles offshore to avoid striking **rocks** or running aground, especially at low water. An **isolated** 10-fathom (18.3-m) **bank** lies 11 miles south of Cape Low.

25 The south coast of Southampton Island between Cape Low and **Ruin Point**, 62 miles to the NE, is low and marshy for several miles inland, rising more than 20 miles inland to limestone plateaus 400 to 500 feet (122 to 152 m) high.

26 **Hut Point** *(63°18'N, 84°34'W)*, **Bear Cove**, **Bear Cove Point** and **Maurice Point** are named but inconspicuous features along this stretch of coast. **The Points** is a range of steep-sided hills NW of Hut Point; from the east, they look like five peculiar shed-like hills. **Bursting Brook**, which flows

through a great expanse of marshland, and **Sutton River** are two of numerous brooks and rivers entering Fisher Strait.

27 There is a **magnetic disturbance** in Fisher Strait.

*Charts 5449, 5410*

## Coral Harbour and approaches

28 **South Bay** *(64°08'N, 83°10'W)*, entered between Native Point and Ruin Point, has low shores; 15 miles to the north, the land rises to 1,000 feet (305 m). Coral Harbour is at the head of the bay; the hamlet of Coral Harbour is on the north shore.

29 **Caution**. — South Bay has **foul ground** on both sides.

30 **Caution**. — South Bay is **incompletely surveyed**; there may be **uncharted dangers** even in sounded waters.

31 Prevailing winds are north and NW, but in summer sea breezes from the south become quite pronounced. Visibility is poorest during the summer; however, this region is not especially foggy.

32 **Native Bay** *(63°52'N, 82°40'W)*, on the east side of South Bay, has a low coastline backed inland by a flat expanse of marshes and lakes. **Prairie Point**, NW of the bay, is flat with a low, rounded limestone plateau rising 2 miles to the east. The shores of Native Bay shelve gently.

33 **Caution**. — **Drying flats** extend 3 miles and more offshore; further offshore there is **shoal water**.

34 On the west side of South Bay, the land rises gradually over flights of raised beaches to low, rounded limestone hills.

35 The **magnetic compass** is erratic in this area.

36 **Bear Island** *(64°00'N, 83°13'W)*, 1.7 miles NW of Prairie Point, is near the outer end of a wide, **drying**, **gravel** and **boulder foreshore**; Bear Island has been described as "a low uninteresting pile of gravel". The coast is composed of angular stones cemented by lime and has a whitish appearance. It is backed by wide marshland.

37 *Bear Island* **light** *(2545)* is on the north part of the island.

38 **Caution**. — **Depths** of less than 6 fathoms (11 m) extend up to 0.8 mile NW and north of Bear Island; **similar depths** are more than 2 miles off the mainland coast from Bear Island to Coral Harbour. **Patches** with depths of 6 to 10 fathoms (11 to 18.3 m) are scattered from Bear Island northward to Munn Bay. On the west side of South Bay, the shore is bordered by **drying flats** of sand and gravel up to 1 mile in width; **depths** of less than 10 fathoms (18.3 m) are found 2 miles off the south part and more than 3 miles off the north part of this shore.

39 **Renny Point** *(63°55'N, 83°36'W)*, with a small island offshore, is on the west coast 9 miles north of Ruin Point. **Mount Scotch Tom**, 20 miles NW of the head of South Bay, is a large rounded ridge at the south end of a range of mountains with elevations over 1,000 feet (305 m).

*Chart 5410*

40 **Rocky Brook**, 6.5 miles north of Renny Point, has a small **bar** off its mouth as do most of the streams along this stretch of coast. **Kirchoffer River**, in the NE part of the bay, is navigable by small craft at high water as far as a **waterfall** 1 mile upstream. East of the river mouth, the north shore of the bay above the high water line is rocky cliffs 20 to 40 feet (6 to 12 m) high.

41 **Munn Bay**, between **Seal Point** *(64°06'N, 83°11'W)* and an unnamed point 5 miles to the west, is **shallow** over most of its inner part. The NW foreshore is a **drying flat** of bedrock, **boulders** and mud. The NE shore is steep rough cliffs up to 25 feet (7.6 m) high.

42 *Munn Bay* **light** *(2546)* is on the NE side of the bay.

43 An **anchorage** 1.2 miles south of *Munn Bay* light, in 10 fathoms (18.3 m), has moderate holding over a bottom of sand, rocks and clay; vessels have dragged in strong southerly winds. There is a better **anchorage** in Coral Harbour.

44 **Caution**. — The NW **shores** of South Bay and Munn Bay, as shown on *Chart 5410*, are **unreliable** for position fixing by radar.

45 **Tern Island** is near the middle of Munn Bay on a **drying flat** surrounded by **shoal water**; it is difficult to distinguish from a distance.

46 **Caution**. — The **beacon** on Tern Island and the **cairn** and **beacon** on the points 1 mile WNW and 2.5 miles WSW of Tern Island, as shown on the 1977 edition of *Chart 5410*, were not in place in July 2003.

47 A prominent sand and gravel **wharf** has been built around a beached hulk at **Snafu Beaches** in Munn Bay; this wharf extends 100 feet (30 m) from the shore and has a depth of 3 feet (0.9 m) along its outer end. Supply barges berth bows-to at the end of the wharf 1 hour before high water. Freight, only, is handled at this wharf.

48 Radio **towers** charted north of Munn Bay and **buildings** at the airfield 3.5 miles NNW of the bay are **conspicuous**. Aircraft obstruction **lights** on the towers and a rotating aeronautical **light** at the airfield are shown when aircraft are in the area.

49 **Coral Harbour** *(64°08'N, 83°04'W)* is at the NE end of South Bay; it was named for the red coral frequently brought up by the lead when taking soundings. The west shore is low and rocky; ridges continue into the bay as reefs and islets, especially near Seal Point. To the north, the land rises very gradually to a low limestone plateau. The east shore is low and marshy from east of Bear Island to the head of the harbour, where **Ford River** enters through a wide

delta. The foreshore of the bay is an extensive **drying flat** of **boulders**, gravel and mud; **drying patches** lie up to 2 miles offshore.

50 The hamlet of **Coral Harbour**, population 712 *(2001)*, is on the west shore of the harbour. The community has a post office, an RCMP detachment and a health centre. There is a *Northern Store* and *Co-op* store. *Inns North* operates a small hotel; other businesses offer lodgings as well. *Kivalliq Air* and *Calm Air* provide daily flights except Saturdays.

51 The *Canadian Coast Guard* radio station "*Coral Harbour*" is 3 miles WNW of Snafu Beaches. This is a remotely controlled station operated by *MCTS Iqaluit*. *(See Radio Aids to Marine Navigation — Atlantic, St. Lawrence, Great Lakes, Lake Winnipeg and Eastern Arctic.)*

52 A privately maintained **aeromarine radiobeacon** *(64°09'N, 83°22'W)* transmits on 362 kHz with identification YZS (— • — — — — • • • • •).

53 The average thickness attained by level **fast ice** at Coral Harbour is 171 cm with a record maximum thickness of 206 cm *(1983)*. Break-up normally begins towards the end of June with the harbour clearing of ice by the middle of July. Freeze-up usually begins by the end of the first week of October with complete ice cover developing by the end of the month. These dates can vary by two to three weeks.

54 The **tidal ranges** of mean and large tides at Coral Harbour are 8 and 13 feet (2.5 and 3.9 m). The maximum **tidal stream** at the anchorage in Munn Bay is reported to be 2 knots.

55 **Caution**. — **Guard Rock** *(64°06'N, 83°08'W)*, a **drying rock** in the mouth of Coral Harbour 1.2 miles ESE of Seal Point, is surrounded by **shoal water**, and **isolated shoals** of less than 3 fathoms (5.5 m) lie up to 0.8 mile to the SW and NE.

56 A channel with a least depth of 23 feet (7 m) leads eastward past the south side of Guard Rock and NNW to the hamlet. A **pilot** is recommended and can be arranged through *MCTS Iqaluit*.

57 The usual **anchorage** in Coral Harbour is 1 mile off the settlement in a small area of more than 6 fathoms (11 m). Holding is good but the berth is exposed.

58 The **harbour** at the hamlet of Coral Harbour is entered from the south of the settlement. This cove, 3 feet (0.9 m) deep in its entrance, is well-sheltered to the east by a **breakwater**. There are two small-craft **wharves** and a wide graded **ramp**. The small-craft wharf on the west side of the cove has less than 1 foot (0.3 m) alongside. Tankers deliver petroleum products through a floating hose to a shore connection at the west entrance point of the harbour. Care is necessary to avoid the **reefs** and any **rocks** moved into the channel by ice.

59 The south entrance point of the cove is marked by a fluorescent-orange **beacon**.

*Chart 5533*

### Coral Harbour to Cape Kendall

60 **Bay of Gods Mercy** *(63°30'N, 86°20'W)*, a large open bight in the SW part of Southampton Island, was named in 1824-25 by Captain Lyon, of HMS *Griper*, because of his narrow escape there from striking a rock. The bay, **not surveyed**, is reported to be **shallow** with many **shoals**. The shores are low and the north coast is bordered by wide **drying flats**. The east shore of the bay, past **Gibbons Point** and as far north as **Manico Point**, is slightly higher than the other parts; there are distinct raised beaches and there is a low limestone plateau 1 to 2 miles inland.

61 **Unhealing Brook** and **Boas River** flow through marshy flats into the head of Bay of Gods Mercy. The mouth of Boas River has depths of less than 2 feet (0.6 m).

62 A flat peninsula of marshy land forms the north side of Bay of Gods Mercy. **Cape Kendall** *(63°36'N, 87°13'W)*, at the SW end of the peninsula, is slightly higher than the low land nearby.

63 **Caution**. — Limestone islets and **reefs** lie 6 miles to the SSW and other **shoals** are reported 5 to 6 miles offshore. A **bank** with a depth of 7 fathoms (12.8 m) is 17 miles south of the cape.

## Hudson Bay — NW shore — Cape Fullerton to Chesterfield Inlet

64 **Cape Fullerton** *(63°58'N, 88°47'W)*, the west entrance point of Ne Ultra Strait and Roes Welcome Sound, has an elevation of 100 feet (30 m) *(Ne Ultra Straight and Roes Welcome Sound are described in Chapter 8)*.

65 **Caution**. — The coast between Cape Fullerton and the entrance to Chesterfield Inlet, 60 miles to the SW, is bordered by **drying flats**, **reefs**, islets and **rocks**. A **shoal** is reported to extend 10 miles SE from Cape Fullerton; several **dangerous rocks** lie within a few miles of the SE end of the shoal.

66 **Bernheimer Bay** lies between Cape Fullerton and **Poillon Point**.

67 **Fullerton Harbour** *(64°00'N, 88°59'W)*, a small **anchorage**, is entered from the west through a passage 150 feet (46 m) wide with a depth of 14 feet (4.3 m). The harbour is sheltered to the south by **Store Island**; the depth in the harbour is 6 fathoms (11 m).

68 **Caution**. — A **shoal spit** extends WNW from the NW point of the island for 750 feet (229 m). The east entrance is narrow and difficult.

69 The coast is broken and bordered by numerous islands, islets and **rocks** between Poillon Point and the east entrance point of **Daly Bay**, 14 miles to the west. **Lorillard**

**River** enters the NW part of Daly Bay. **Bailey Islands** are off the west entrance point of the bay.**Walrus Island** *(63°54'N, 89°36'W)* is the outermost of the islands and islets in Daly Bay.

70 **Caution**. — **Dangerous submerged rocks** lie 2 miles west of Walrus Island.

71 **Winchester Inlet**, SW of Bailey Islands, is surrounded by low, rounded and bare hills separated by wide valleys. Boulders are scattered over the hills and there is little vegetation anywhere. The valleys are boggy and filled with lakes and ponds.

72 There is reported to be a good **anchorage**, well-sheltered by islands, on the NE side of the inlet 3 miles from the entrance.

73 **Caution**. — **Submerged rocks** are scattered across the mouth of Winchester Inlet.

74 The coast between Winchester Inlet and Chesterfield Inlet, 30 miles to the SW, is low and filled with lakes and ponds. The land slopes up from the coast gradually and there are no hills higher than 50 feet (15 m).

75 **Caution**. — The coast is bordered in most places by a wide belt of low rocky islands; **submerged rocks** extend for several miles seaward. Beyond the rocks the bottom is uneven; **shoal water** extends well offshore. There is danger of grounding even if out of sight of the land.

76 **Depot Island** *(63°47'N, 89°53'W)*, 4 miles SE of Winchester Inlet, was the site of a whaling station. **Whitney Inlet**, NW of Depot Island, has many **submerged rocks** off the entrance.

77 **Cape Silumiut**, elevation 49 feet (15 m), and the coast north and south are bordered by **drying flats**. **Rockhouse Island**, 16 miles to the SW, is 140 feet (43 m) high and joined to **Pintail Island** by a **drying bank**. Between Cape Silumiut and Rockhouse Island, the coast is broken with many bays and inlets.

78 **Caution**. — Islands, islets and **rocks** lie up to 6 miles offshore.

## Approaches to Chesterfield Inlet

79 **Chesterfield Inlet** *(63°24'N, 90°45'W)*, on the SW side of Rockhouse Island, is a corridor of tidal waters joining Hudson Bay to Baker Lake. The distance along the usual track through the inlet is 124 miles from the open waters of Hudson Bay to the entrance to Baker Lake at Chesterfield Narrows. The offshore approaches to Chesterfield Inlet were surveyed in 1981.

80 **Caution**. — There are **shoals** and **rocks** and several **shoal depths** of 33 feet (10 m) or less in the area north and west of *63°20'N, 90°00'W*. There is a **rock reef** with a depth of 8 fathoms (14.6 m) 11.5 miles SE of Cape Silumiut, and there are other **shoals** to the west and SW. There are **rock reefs** with a depth of 10 fathoms (18.3 m) 10.7 miles ESE of Promise Island and a **shoal depth** of 9 fathoms (16.8 m) 10 miles SE of the island. The 4-fathom (7.3-m) patch charted 8.2 miles ESE of the island was not found in the 1981 hydrographic survey.

*Chart 5620*

81 Most of the shores of the islands and mainland coast in this area are bordered by **drying rock** and **boulder flats**.

82 **Promise Island** is a wedge-shaped island with a high west side off the entrance to Chesterfield Inlet; **Wag Islands** are low islands joined to Promise Island by a **shallow**, **partly drying bar**. The islands are difficult to identify from more than 5 miles. **Akreavenek (Sandpiper) Island**, elevation 5 m, lies north of Wag Islands and is joined to them by a **drying ledge**.

83 A **beacon**, consisting of a black and white **tripod** topped with a **mast**, is on the SW side of Promise Island. Promise Island beacon is not maintained; its condition is unknown *(2006)*.

84 Chesterfield Inlet is entered between Promise Island and **Jaeger Point**.

85 **Anchorage** in 15 to 20 m, sand and gravel, with fair protection except from easterly winds can be found 1 mile south of Akreavenek Island. CCGS *N.B. Maclean*, an icebreaker 79.3 m in length, rode out 70-knot westerly winds here in 1973.

86 On the south side of the approaches to Chesterfield Inlet, **Fairway Island** *(63°15'N, 90°34'W)*, elevation 11 m, appears from offshore to be three distinct mounds.

87 **Caution**. — The west side of the island has deep water but a **drying spit** extends from the NW point for 1 mile.

88 A **beacon**, consisting of a **mast** with a **barrel** on top, is on the NW part of Fairway Island. Fairway Island beacon is not maintained; its condition is unknown *(2006)*.

89 **Sakpik Island**, **Sakpik Channel** and **Sakpik Bay** are NW of Fairway Island. Sakpik Island has two hills joined by a narrow isthmus; the western hill is 12 m high.

90 **Caution**. — **Isolated shoals** with depths of 4.9 and 12.3 m lie 0.6 mile ESE and 0.9 mile NNE of the NE end of Sakpik Island.

91 **Aulatsivik Point** *(63°16'N, 90°43'W)*, SW of Sakpik Island, has a **conspicuous** dark rock **ridge**, 15 m high, in its centre.

92 **Fox Trap Island** is on the north side of Sakpik Bay. There are rock cairns at the north end of Fox Trap Island; these have been used by the Inuit for trapping fox. **Fish Bay** is NW of Fox Trap Island. Fish Bay, used by the Inuit for netting arctic char, has low rocky shores.

93 **Caution**. — There are **shoal depth**s of 3 to 4.5 m in the entrance to the bay.

94 On the NE side of Fish Bay, **Clay Island**, elevation 1.8 m, is attached to **Thibert Point**.

95 **Caution**. — There are **shoal depths** of less than 1 m 0.35 mile ESE of the island.

96 **Chesterfield Anchorage** *(63°20'N, 90°42'W)* is a sheltered bay between Thibert Point and **Finger Point**, 1.3 miles NE.

97 The hamlet of **Chesterfield Inlet**, population 345 *(2001)*, is on the north shore of Chesterfield Anchorage. The **buildings** are prominent; the most **conspicuous** are homes with **aluminium siding** on high ground. There is a post office, a health centre, a *Co-op* store and an *Inns North* hotel in the community. Other businesses offer retail sales. Police services are administered from the RCMP detachment at Rankin Inlet. *Kivalliq Air* provides daily flights except Saturdays and *Calm Air* provides flights on weekdays.

98 The average thickness attained by level **fast ice** at Chesterfield Inlet is 185 cm with a record maximum thickness of 226 cm *(1975)*. Ice thickness measurements have not been made since 1981. Break-up usually begins in mid-June with the inlet clearing of ice a month later. Freeze-up usually begins during the first week of November with complete ice cover forming a week later. These dates can vary by two to four weeks.

99 The **tidal ranges** of mean and large tides are 3.2 and 4.6 m at Akreavenek Island.

100 **Caution**. — There are **tide rips** off Finger Point in large tides. There may be cross **currents** between Fairway Island and Promise Island.

101 A privately maintained **aeromarine radiobeacon** *(63°20'N, 90°44'W)* transmits on 341 kHz with identification YCS (— • — — — • — • • • •).

102 *Mission Lake* **light** *(2600)* is NE of the settlement.

103 A **conspicuous** white rotating aeronautical **light** at the airport is not visible in all directions.

104 **Anchorage** can be found, in 15 m, 0.5 mile south of the charted tanks and 0.2 mile off the NE shore.

105 **Caution**. — The anchorage has only **fair holding** in sand and gravel and it is exposed to **winds** from south through SE to east. If strong winds arise from these directions, vessels should seek shelter in Chesterfield Inlet or ride out the wind in open water.

106 There is a **landing beach** of clay, gravel and stones near the end of the charted pipeline; shelter is poor. The supply barge berths here 1 hour before high water.

## Chesterfield Inlet — General

107 Depths of 29 m can be found along the route as far west as Cross Bay *(63°54'N, 93°30'W)*, and 20 m from there to Chesterfield Narrows, where there is a **rock shelf** with depths of 2.1 to 3 m. At high water levels the narrows have been navigated by vessels drawing up to 4.6 m. Depths along the route through Baker Lake are from 31 to 84 m, decreasing to 9.1 m near the hamlet.

108 The **tidal range** of large tides in Chesterfield Inlet varies from 4.6 m at the mouth, to 5.2 m at Deer Island, to 2 m at Primrose Island and to 2.5 m at Norton Island, 2 miles east of Chesterfield Narrows. The time lag of the progression of the tide, from the entrance of the inlet on Hudson Bay to Norton Island, is 5 hours.

109 **Caution**. — The **tidal streams** are strong and cross **currents** can set a vessel across the channel. The ebb stream, which reaches a maximum rate at low water, runs for 8 hours; the flood for 4 hours.

110 There are several good **anchorages** over a soft clay bottom and free of strong tidal streams. The best of these are at Moor Island, Robin Hood Bay, Sculpin Island and Cross Bay *(all described later in this chapter)*.

111 The shores of the inlet are mostly rock slopes rising gently from the water to elevations of 50 m and covered with moss, lichens and dwarf shrubs. High points are often marked by rock cairns built by the Inuit. Islands and headlands blend into the background and are difficult to distinguish, and there are few prominent features useful for navigation. The rock formations are shades of black and brown broken occasionally by splashes of white.

112 The only regular traffic are small fuel tankers and the *Northern Transportation Company* tug *Keewatin*, which tows two barges, drawing up to 2.4 m, from Churchill to the hamlet of Baker Lake twice a year.

### Chesterfield Inlet entrance to Ellis Island

113 The maximum **tidal range** of large tides in this stretch is 4.9 m.

114 **Caution**. — The ebb **tidal stream** runs at up to 4 knots and there are cross **currents**.

115 **Black Rocks Point** *(63°23'N, 90°46'W)*, **False Inlet** and **Ptarmigan Island** are on the SW side of the inlet. A dark steep **cliff** 0.7 mile NW of Black Rocks Point is **conspicuous**. **Ellis Island** is off the SW shore of Chesterfield Inlet, 5 miles NW of Ptarmigan Island. **Observation Point**, on the mainland south of Ellis Island, is low.

116 **Caution**. — **Shoal depths** of less than 1 m extend up to 1 mile off the SW shore of the inlet.


CHESTERFIELD ANCHORAGE
LANDING BEACH
PLAGE DE DÉBARQUEMENT
CHURCH
ÉGLISE
POWER STATION
CENTRALE ÉLECTRIQUE
1988


CHESTERFIELD INLET
SETTLEMENT
AGGLOMÉRATION
SCHOOL
ÉCOLE
HOSPITAL
HÔPITAL
CHURCH
ÉGLISE
1988

117 On the NE side of the inlet, **Demon Point** *(63°32'N, 90°55'W)* is an extension of **Hanbury Island**, a large island with an elevation of 30 m. **Severn Harbour** is at the NW end of Hanbury Island.

118 **Caution**. — A **reef** 0.7 mile SW of Demon Point **breaks conspicuously** in heavy seas; **rocks** and **shoals** lie up to 1.3 miles off the SW shore of the point.

*Chart 5621*

## Ellis Island to Centre Island

119 The maximum **tidal range** of large tides in this stretch is 5.4 m at Deer Island. Between Hudson Bay and Deer Island, the lag between tidal events is 45 minutes.

120 **Caution**. — On the ebb, a **tidal stream** of up to 4 knots, and up to 5 knots near Deer Island, can be expected; **tide rips** are frequent.

121 **Black Boulder Point** *(63°30'N, 91°01'W)*, the north point of Ellis Island, is named for a **conspicuous** black **boulder** here. **Ephemeral Cove**, **Inukuk Point** and **Ikalupilinak Point** are on the mainland SW of Ellis Island.

122 **Anchorage** can be found over a mud bottom in the berth north of Black Boulder Point.

123 Midway between Ellis Island and **Moor Island**, 1 mile farther WNW, there is a **rock** with a depth of 7.8 m.

124 A vessel has lain safely in a Beaufort force 10 SE storm at a good **anchorage** south of Ellis Island, in 12.8 m, approached between Ellis and Moor Islands.

125 **Caution**. — The area south of Ellis Island is **not surveyed**; local knowledge is necessary.

126 The two **Imilit Islands** are NW of Ellis Island.

127 **Caution**. — **Rascal Rock**, a **conspicuous drying patch** 0.7 mile NE of South Imilit Island, can usually be seen on radar but covers at large tides. There are **boulders** in the area west of Imilit Islands.

128 **Anchorage** with protection from all but NE winds can be found in the berth midway between Ellis Island and South Imilit Island over a bottom of soft mud.

129 An **anchorage** 2 miles WNW of Severn Harbour, off **Apqusiurniq Island**, offers good protection from northerly winds.

130 **Iripajuk Island** is 8 miles WNW of Severn Harbour; **Poston Point** is off the NE shore of Chesterfield Inlet 3 miles farther NW. **Illusive Islands** are in an offshore shoal area 1.2 miles west of Poston Point; **Merles Harbour** is 3.5 miles NNW of the point.

131 On the south side of the inlet, **Merry Headland** *(63°36'N, 91°21'W)* is the NE end of **Big Island**, elevation 30 m. **Camp Cove Island** lies midway between Merry Headland and **Deer Island**, 3 miles to the NW.

132 **Caution**. — **Adversary Bank** is a **shoal area** off the east end of Deer Island.

133 An **anchorage** 1 mile west of Camp Cove Island offers protection from all winds with moderate holding in gravel.

134 **Caution**. — The ebb **current** here reaches 3 knots.

135 **Deer Island Channel**, between Deer Island and **Centre Island**, is 0.5 mile wide. **Ragged Island** is west of Deer Island.

136 There are two pairs of **leading beacon ranges** marking the route around Centre Island. Each **beacon** is a fluorescent-orange **daymark**, black vertical stripe, mounted on a lattice **tower**. Both front towers are 3 m high.

137 Deer Island beacons, with the front tower on an islet north of Illusive Islands, in line bearing 071° leads through Deer Island Channel.

138 Big Island beacons, on the NW part of Big Island, in line bearing 150½° leads between Centre Island and Ragged Island.

*Chart 5622*

## Centre Island to Farther Hope Point

139 The maximum **tidal range** of large tides in this stretch is 5.2 m; at Farther Hope Point it is 3 m.

140 **Caution**. — **Currents** reach 5 knots on the ebb and there are often **tide rips**.

141 **Dangerous Point** *(63°43'N, 91°34'W)* is on the north shore 2 miles NW of Centre Island.

142 **Caution**. — **Christopher Rocks** are in a **shoal area** on the east side of the route, west of Centre Island.

143 On the SW and west shores, **Steep Bank Bay** is west of Big Island, and **Boulder Island** is west of Centre Island. **Ujagasukjulik Point** is the north end of Boulder Island. **Fish Bay** is on the south shore 4.6 miles NW of Boulder Island.

144 **Caution**. — **London Rock**, with a depth of 1.6 m, and a **dangerous area awash** are 0.25 mile off the south shore near Fish Bay.

145 On the north shore, **Ranger Seal Bay** is NNE of Fish Bay. **Pelletier Bay**, 2 miles west of Ranger Seal Bay, lies between **Pelletier Point** and **Tattiggaq Point**. **Rubble Rock**, 0.2 mile SW of Pelletier Point, is 3 m high.

146 **Caution**. — **Shoal water** reaches up to a mile or more off the north shore for 2 miles each side of Dangerous Point and up to 0.5 mile offshore west of Ranger Seal Bay and across the mouth of Pelletier Bay.

147 An **anchorage** SE of the east entrance point of Ranger Seal Bay offers excellent holding over a mud, gravel and boulder bottom. A **rock** with a depth of 7.6 m is 0.3 mile south of the anchorage.

148 **Ekatuvik Point**, on the south shore, is 1.5 miles WNW of Fish Bay. **Needle Point** is a narrow point 2 miles farther WSW.

149 **Caution**. — **Shoal water** lies up to 0.6 mile off the south shore west of Needle Point.

150 Four pairs of **leading beacon ranges** mark this difficult part of the route. Each beacon is a lattice **tower** 3 m high with a fluorescent-orange **daymark**, black vertical stripe.

151 Ranger Seal beacons, on the north shore SE of Ranger Seal Bay, are in line bearing 089°.

152 Fox Point beacons, on Pelletier Point, are in line bearing 057°.

153 Ekatuvik beacons, on the south shore SW of Ekatuvik Point, are in line bearing 128½°.

154 Bittern Point beacons, on Tattiggaq Point, are in line bearing 062½°.

155 On the south shore, **Reference Island** is 1.8 miles WSW of Needle Point; **Headwind Point** is 3 miles farther SW. **Barbour Bay** is a 15-mile long inlet entered west of Headwind Point. **North Midway Island** and **South Midway Island** are large islands in the mouth of Barbour Bay. **Oaqulluk Rock**, in mid-channel 0.9 mile NW of North Midway Island, is an **isolated rock** with a depth of 8.8 m.

156 On the north shore NW of Reference Island are **East Point**, **Robinhood Bay** and **Patch Island**. **West Point** is 3 miles west of Robinhood Bay.

157 An **anchorage** between shoals in the mouth of Robinhood Bay is free of strong currents and offers good holding in 15 m, soft clay, with shelter from northerly winds. This anchorage, midway between Hudson Bay and Baker Lake, is one of the best in Chesterfield Inlet.

158 **Farther Hope Point** is on the south shore 2.5 miles west of West Point.

*Chart 5623*

## Farther Hope Point to Terror Point

159 The maximum **tidal range** of large tides in this stretch is 3.5 m.

160 **Caution**. — **Currents** are estimated to be up to 5 knots, especially north and east of Little Big Island *(63°51'N, 92°51'W)*.

161 On the south shore, **Tent Bay** *(63°45'N, 92°25'W)* is 4.7 miles west of Farther Hope Point; **Conway Point** is 3.4 miles farther NNW. **Promise Point** is 1.8 miles NW of Conway Point; **Akunak Bay** is 3.6 miles SW of Promise Point.

162 **Anchorage** with good room and moderate shelter can be found in Akunak Bay, free of strong currents.

163 **Caution**. — The north shore from opposite Promise Point to 2 miles NW of **Ragged Point** is bordered by **shoal water** for up to 0.4 mile offshore.

163.1 Mariners are advised that they may encounter a sweeping current phenomenon abeam Promise Point that pushes their vessel when manoeuvering the course change rounding Promise Point. This may be the result of the bulging coast line and the narrowing channel at the point.

164 **Eider Island** is off the SW shore 2.5 miles west of Ragged Point. A large bay between Eider Island and **Little Big Island** appears to be mostly **shallow**.

165 **Caution**. — **Monark Reef**, a **dangerous drying shoal** just awash at high water large tides, is in the outer part of this bay.

166 **Caution**. — An **anchorage** 1.2 miles east of the south point of Little Big Island should be used only with local knowledge as the area is **shallow** and large portions are **not surveyed**.

167 On the NW shore, **Low Point** *(63°52'N, 92°45'W)* is opposite Monark Reef. **Uvauk Inlet** is north of Low Point.

168 **Caution**. — **Shoal water**, an above-water rock and a **drying patch** extend up to 0.9 mile offshore in the bay. **Shoal rocks** lie 1 mile off the north shore opposite the NW end of Little Big Island.

169 **Stony Point** and small but **conspicuous Orbit Rock**, 1 m high, lie off the NE end of Little Big Island. **Target Rock**, 2 m high, and **Skua Reef** lie off the north shore.

170 **Caution**. — The **channel** here **narrows** to 0.23 mile between the 20 m lines.

171 **Caution**. — The north shore of Little Big Island is bordered by an area of **shoal water**.

172 **Anchorage** with good shelter over sand bottom and currents of no more than 2 knots can be found in the bay between Little Big Island and **Sculpin Island**, to the west.

173 **Riot Rock**, on the west side of the route 0.6 mile NW of Sculpin Island, is a **conspicuous** pile of large **boulders** 2 m high. There is a prominent bluff on the east shore 0.5 mile NNE of Riot Rock.

174 **Primrose Island**, with **Bold Point** at the NE end, is west of Riot Rock. **Lemming Island** lies off the north shore of Primrose Island 0.5 mile NW of Bold Point.

175 **Caution**. — **Shoal water** extends 0.5 mile off the southern two-thirds of the east side of Primrose Island. On the north shore NE of Primrose Island, **Big Bay** has **rocks** with depths of 3.8, 7.2 and 10.2 m across the entrance, and the inner part of the bay appears to be **shoal**.

176 **Caution**. — A **rock** with a depth of 4.8 m lies 0.3 mile off Bold Point, and there are islets and **shoal water** off Lemming Island.

177 **Peril Point** and **Terror Point** *(63°55'N, 93°06'W)* are on the north shore WSW of Big Bay.

178 **Caution**. — **Drying banks** and **shoal depths** of less than 10 m extend up to 0.4 mile off the north shore between Big Bay and Terror Point.

179 Four pairs of **leading beacon ranges** mark the route east and north of Little Big Island and Primrose Island; each

beacon is a lattice **tower** 3 m high with a fluorescent-orange **daymark**, black vertical stripe.

180 Monark Reef beacons, leading east of Monark Reef and Orbit Rock, are in line bearing 330°.

181 Skua Reef beacons, leading NW of Skua Reef, are in line bearing 068°.

182 Riot Rock beacons, on Riot Rock and Sculpin Island, are in line bearing 158½°.

183 Big Bay beacons, on the SE side of Big Bay, are in line bearing 072°.

*Chart 5624*

## Terror Point to Baleen Island

184 The maximum **tidal range** of large tides in this stretch is 2.9 m.

185 **Caution**. — **Currents** are estimated to be up to 4 knots, and there are **tide rips** between Terror Point and Big Point, 8 miles to the WNW.

186 **Bowser Island** *(63°56'N, 93°09'W)*, in mid-channel 1 mile NW of Terror Point, has a **conspicuous bluff** on its NW end. **Walker Island** is off the SE end of Bowser Island.

187 **Caution**. — **Shoal water** borders the east and SE shores of Bowser Island. **Isolated rocks** with depths of 10 and 4.6 m lie off the north shore 2 miles WNW of the NW end of Bowser Island. **Horizon Islands** are low flat islands west of Bowser Island; **some** of them **cover** at **high water**.

188 **Anchorage** over a sand bottom can be found south of Walker Island.

189 There is a **conspicuous** rock **bluff** at the north end of **Big Point**, on the south shore 5 miles west of Bowser Island; **Duncan Island** lies 0.1 mile offshore near the bluff.

190 **Caution**. — A **rock** with a depth of 4.6 m is on the north side of the channel 1.2 miles east of Duncan Island.

191 **Twin Pack Island** is off the north shore north of Duncan Island. **Flat Point** is 1.5 miles WNW of Twin Pack Island. **Quoich River** is west of Flat Point.

192 **Caution**. — There is a 1-m **shoal** in the mouth of the river, 0.7 mile west of the point.

193 **Caution**. — There is reported to be a strong **current** from the river into the channel.

194 **Anchorage**, over a soft clay bottom, can be found SW of Flat Point.

195 On the south side of the route west of Big Point, **Cross Bay**, over 6 miles wide, reaches south and SSE for more than 10 miles. **Long Island**, **Round Island** and **Strivewell Island** lie across the mouth of the bay. The north point of Round Island is a sheer bluff. **Etuksit Point** is on the south shore of the bay. **Helicopter Island** *(63°57'N, 93°39'W)*, 2.3 miles west of Round Island, is the largest of a group of islands and islets; **White Rock** is the SW island.

196 **Caution**. — An area of **shoal water** extends up to 1 mile north and east of Helicopter Island.

197 **Brant Island Channel** is a deep narrow passage along the north side of the shoal area off Helicopter Island; **Borealis Reef** and **Brant Island** lie on the north side of the channel.

198 **Cross Bay Channel** passes north of Cross Bay; it is a deep passage south and west of the Helicopter Island group.

199 Vessels can pass north or south of the Helicopter Island group; the southern route is wider.

200 **Anchorage** can be found south of Helicopter Island, mud bottom. This location is better, for swinging room, shelter from northerly winds and freedom from strong currents, than the anchorage off Flat Point.

201 **Bowell Islands** are two large islands that form the north shore of the 18 miles of Chesterfield Inlet west of Cross Bay. **Baleen Island** is 3 miles inside this more restricted stretch of the passage.

*Chart 5625*

## Baleen Island to Chesterfield Narrows

202 Between Baleen Island and Eddy Point, 1 mile east of Chesterfield Narrows, channel depths are mostly over 20 m, with a depth of 15.2 m in the west part of Strivewell Narrows. There is a limiting depth of 6.7 m in mid-channel 0.25 mile west of Eddy Point, and 4.2 m in Chesterfield Narrows. Vessels drawing up to 4.6 m have passed through the narrows at high water levels.

203 There is a **tidal range** of 2.5 m at large tides as far west as Norton Island *(64°00'N, 94°13'W)*.

204 **Caution**. — The height of the tide and the strength of the **tidal currents** in Chesterfield Narrows depend on the **water level** in Baker Lake. The lake level varies by 0.6 to 0.9 m from the high levels in late June and early July to the lower levels in September and October. The tidal information given below is for summer conditions.

205 The **tidal ranges** of mean and large tides at Chesterfield Narrows are 1.4 and 2 m, respectively. High water at Norton Island, 2 miles east of the narrows, follows high water at Churchill by ½ to 1 hour. High water at Chesterfield Narrows can be expected to begin 1 to 1½ hours after high water at Churchill and to last for 3 to 4 hours.

206 **Caution**. — **Tidal currents** flow westward for the 3 to 4 hours of flood and can reach rates of up to 4 knots, with ½-hour periods of slack water before and after. The eastward ebb flow lasts some 8 hours, reaching maximum rates at low water. Ebb tide flows of up to 8 knots have been reported.

207 **Schooner Harbour** *(63°56'N, 93°54'W)* is on the north shore 1.5 miles WSW of Baleen Island.

208 A well-protected **anchorage** SW of Schooner Harbour offers excellent holding in soft clay and sand.

209 **Caution**. — Due to the strong **currents**, the area from the anchorage SW of Schooner Harbour to Chesterfield Narrows is suitable only for daytime navigation in good visibility.

210 **Ippijjuaq Bay** *(63°55'N, 93°57'W)* is on the south shore of Chesterfield Inlet, 2 miles SW of Schooner Harbour. There are two rocks with depths of 8 and 9 m in mid-channel between Schooner Harbour and Ippijjuaq Bay. **Auk Island** is off the north shore 0.8 mile NNW of Ippijjuaq Bay.

211 **Caution**. — **Ice Hunter Rock** *(63°59'N, 94°06'W)* is in mid-channel, 4.3 miles NW of Auk Island. This is a great **danger**, **drying** 1 m and covering 2 m. It can be passed on either side; the south channel is deeper and more direct. A passage leads north from Ice Hunter Rock between the two Bowell Islands; the passage is **not surveyed**.

212 **Strivewell Narrows** leads west from Ice Hunter Rock. On the south shore of Strivewell Narrows, **Cone Hill** is prominent 2.5 miles west of Ice Hunter Rock. **Slippery Point** is 0.4 mile west of Cone Hill.

213 **Caution**. — The bay west of Slippery Point has several **dangerous rocks**.

214 Farther west, **Norton Island** and **Moses Island** are two distinctive islands on the south side of the channel, 2 miles west of Slippery Point. There are Inuit inukshuks on Moses Island; these are **conspicuous** rock **cairns** resembling persons.

215 **Caution**. — **Shoal water** extends 0.2 mile from the north shore opposite Moses Island.

216 **Eddy Point** *(64°00'N, 94°16'W)*, 1 mile west of Moses Island, is a sheer bluff, **conspicuous** from east and west.

217 The south shore of the inlet, from Ice Hunter Rock past Slippery Point to Eddy Point, rises steeply from the water with dark rock bluffs, particularly near Ice Hunter Rock. The north shore slopes gently, and in summer is covered with moss, numerous arctic flowers and dwarf shrubbery.

218 **Schooner Cove**, with a **submerged rock** in its entrance, and **Beyts Cove** lie 0.3 and 0.8 mile west of Eddy Point.

219 **Caution**. — Anchorage between Ice Hunter Rock and Chesterfield Narrows is not recommended because of the narrow channel and strong **currents**.

### Chesterfield Narrows

220 **Twist Point** and **Ice Breaker Point** are on the north side of **Chesterfield Narrows**. **Ice Cutter Point** is on the south side of the narrows; there is a **conspicuous cairn** south of the point and **Big Swallow Hill** rises farther south to a height of 61 m. **Burial Point** is on the SE shore of Baker Lake, 0.8 mile SW of Ice Cutter Point. **Ice Breaker Islet**, on the north side of the entrance, is prominent from both the lake and the inlet.

221 **Caution**. — A **rock** in mid-channel, 0.15 mile NE of Ice Cutter Point, has a depth of 2.8 m.

222 Two pairs of **leading beacon ranges** mark the route through Chesterfield Narrows in a least depth of 4.2 m. Each **beacon** is a lattice **tower** 3 m high with a fluorescent-orange **daymark**, black vertical stripe.

223 Schooner Cove beacons, on the SE side of Schooner Cove, in line bearing 110½°, lead through the east part of the narrows to the intersection with Twist Point range, on Twist Point.

224 Twist Point beacons, in line bearing 079°, lead from the intersection to a position south of Ice Breaker Islet.

225 These ranges are used by the *Northern Transportation Co.* tug *Keewatin*.

## Baker Lake

*Charts 5625, 5626*

226 **Baker Lake** is a freshwater lake extending west for 50 miles from Chesterfield Narrows to the mouth of Thelon River and the hamlet of Baker Lake. The shores of the lake are mostly gentle slopes with pronounced ridges or rock hills; small craft can land almost anywhere. Most of the terrain is covered by a heavy carpet of moss. The lake supports populations of lake trout, arctic char, whitefish and grayling. Duck, goose, fox, rabbit and caribou are hunted near here.

227 The northern two-thirds of Baker Lake is comparatively deep; the southern one-third, not completely sounded, appears to be **shallow** and scattered with **shoals**.

228 The average thickness attained by level **fast ice** at Baker Lake is 221 cm, with a record maximum thickness of 248 cm *(1969)*. Break-up normally begins in mid-June, with the lake becoming clear of ice by the end of July. Freeze-up usually begins in mid-October, with complete ice cover before the end of the month. These dates can vary by two to three weeks.

229 The effect of **tides**, measured at the east end of the lake north of Ice Breaker Islet, is negligible.

*Chart 5625*

### Chesterfield Narrows to James Point

230 The east end of Baker Lake is filled with islands. The largest of these, **Christopher Island**, is separated from the shores of the lake by South Channel and North Channel; **Shell Island** lies SE of Christopher Island. **Grebe Point** *(64°00'N, 94°20'W)* is the SE tip of Shell Island; this point and Ice Cutter Point mark the entrance to **South Channel**.

231 **Caution**. — **Grebe Shoals** and other **shoals** and **dangerous underwater rocks** south and SW of Grebe Point obstruct the east end of South Channel; further west, the channel is wide and deep. The passage is frequently swept by strong NW **winds**. This channel is not recommended without local knowledge; **shoals** have not been examined and many **depths** will be less than charted.

232 **Severn Point** is on the south shore 5 miles NW of Burial Point. **Camp Bay** and **Deceptive Bay** are on the south shore of Christopher Island. **Camp Islet** is in the middle of Camp Bay.

233 **Caution**. — Camp Bay has a **shallow** NW arm and a 2.7-m **shoal** in the middle of the entrance but is otherwise free of dangers. Deceptive Bay is **shallow**.

234 The usual route from Chesterfield Narrows to the hamlet of Baker Lake leads around the east side of Christopher Island and through **North Channel**. This is a sometimes narrow route, but it is deeper and more sheltered than South Channel, with ranges leading through the more hazardous sections.

235 **Kennedy Point** is on the east side of the route, 0.6 mile NNW of Ice Breaker Point. **Monument Bay**, on the NE side of Shell Island, is bordered by sand beaches with good landing places; **Top Hill** is on Shell Island west of the bay. **Bertrand Point** *(64°02'N, 94°20'W)* is the SE end of an island NE of Shell Island; **Knob Hill**, 0.8 mile to the NNW, is **conspicuous**.

236 Islands NE of Shell Island include **Bannerman Island**, 35 m high, **Rio Island** and **Pilon Island**.

237 There are pairs of **leading beacon ranges** on Bertrand Point and Bannerman Island. Each **beacon** is a fluorescent-orange **daymark**, black vertical stripe.

238 Bertrand Point beacons are in line bearing 358½°; the front beacon is on a lattice **tower** 3 m high; the rear beacon is on a lattice **tower** 9 m high.

239 Bannerman Island beacons are in line bearing 027°; the front beacon is on a lattice **tower** 3 m high; the rear beacon is on a lattice **tower** 6 m high.

240 **Caution Point** is the south end of Pilon Island; **Barbour Point** is the NW end of the island. **Regina Narrows**, a passage between Caution Point and **Dean Islet**, is 200 m wide between the 5-m contours. Dean Islet is low but gives a good radar response and makes a better mark than Caution Point for navigating Regina Narrows.

241 **Caution**. — **Depths** may be less than charted between the 2-m contour and Caution Point.

242 **Low Point** is the NW end of an island SW of Dean Islet; **McGill Islet** and **Ptarmigan Islet** lie 0.6 and 1.3 miles NW of Low Point.

243 Low Point **leading beacon range**, in line bearing 174°, is on Low Point and an island to the south. Each **beacon** is a lattice **tower** 3 m high with a fluorescent-orange **daymark**, black vertical stripe.

244 **Peck Point** *(64°06'N, 94°20'W)* is the north tip of Rio Island; a **conspicuous** black **hill** with a square top, 0.8 mile south of the point, is 67 m high. **Red Point** and **Bowser Point** are the SE and NE points of an unnamed island 2 miles NW of Rio Island. **Jessiman Islet** and **Chain Islet** *(64°08'N, 94°26'W)* are NE and north of Bowser Point.

245 **Polaris Narrows** is a passage between reefs extending 0.4 mile east of Red Point and other reefs 0.3 mile farther NE.

246 Barbour Point **leading beacon range** is on Pilon Island near Barbour Point. The **beacons** are lattice **towers** 3 m high, each with a fluorescent-orange **daymark** and a black vertical stripe. Barbour Point range, in line bearing 156°, leads through Polaris Narrows.

247 A **conspicuous** white **boulder**, on the mainland shore north of Chain Islet, is a good steering mark for passing through Polaris Narrows.

248 **Kanangnaaqslirjuaq Island** and **Wedd Islet**, elevation 21 m, are on the north side of North Channel, west of Chain Islet.

249 **Lunan Point** *(64°07'N, 94°39'W)*, the WNW end of Christopher Island, is 15 m high. There are cliffs along the north shore of the island; **Terrace Hill**, 1 mile ESE of Lunan Point, is 81 m high and **conspicuous**.

250 **James Point** *(64°08'N, 94°38'W)* is the north entrance point of North Channel; **Jeffers Islet**, off the NNW end of Christopher Island, is the south entrance point.

251 Polaris Narrows can be avoided by passing north of Ptarmigan Islet, then WNW and NW parallel to the NE shore of Christopher Island, to join North Channel 1.5 miles ENE of Terrace Hill.

252 **Caution**. — This route is **not marked** with aids to navigation.

*Chart 5626*

## James Point to Baker Lake hamlet

253 Along the south shore of Baker Lake, **Lofthouse Point** *(64°07'N, 94°59'W)* is 9 miles west of James Point. **Lofthouse Hill**, a prominent hill SSE of Lofthouse Point, is the highest of the **Manimaniit Hills**. The coast west of Lofthouse Point is irregular with many bays and is bordered in places by islets. **Qulaituijarvik River**, **Clear Water River** and **Kazan River** are on the south shore west of Lofthouse Point.

254 **Tanataluk Islands**, 4 to 14 m high, and **Big Hips Island**, 50 m high, are on the south side of the lake, 10 and 16 miles west of Lofthouse Point. **Takijuq Island**, off the south shore SW of Big Hips Island, is a pair of islands each 5 m high.

255 **Caution**. — A **boulder shoal** with a depth of 1.2 m lies 2.2 miles NW of the north end of the west Tanataluk Island, and **shoal patches** of less than 5 m lie up to 2.1 miles north of the islands.

256 **Sugarloaf Mountain** *(64°00'N, 95°52'W)*, on the mainland SW of Big Hips Island, is 180 m high and **conspicuous**. **Kingatnaaq Hill**, 8 miles NW of Sugarloaf Mountain, is 80 m high. Sugarloaf Mountain and Big Hips Island are clearly visible on the horizon from Lofthouse Point.

257 The black dome of **Akilahaarjuk Mountain**, on the north shore 8 miles east of Baker Lake hamlet, is **conspicuous**. Along the north shore of Baker Lake NW of James Point, **Jigging Point** *(64°12'N, 94°47'W)* and **Tingaujaqtujut Islands**, 2 miles south of Jigging Point, are **conspicuous**. **Tasiujaq Bay** is a river mouth east of the islands. **Ketyet River** enters Baker Lake north of Jigging Point; **Aulatsivittuaq Bay** is west of the point.

258 **Helix Point**, **Ingilik Point**, **Akilahaarjuk Point** and **Nuvuttuaq Point** are other named features along the north shore of Baker Lake. **Prince River** enters a **shallow** bay north of Akilahaarjuk Point.

259 **Caution**. — There is a **rock awash** 1 mile off the north shore 5 miles NW of Helix Point.

260 In the west part of Baker Lake, **Nunagiak Point** *(64°13'N, 95°49'W)* is the east end of **Arlug Island**. Arlug Island rises to a **conspicuous bluff** 34 m high; this is the largest island of a group which includes **Little Islands** and **Nicholls Island**.

261 **Sagliq Island** is in a wide bay SW of Arlug Island. On the mainland south and SW of Sagliq Island are **Tikirakuluk Point**, **Aniguq River** and **Qikiqtaujaq Island**.

262 **Thelon River** enters the west end of Baker Lake between **Iglujat Hills** and **Paunraqtuuq Hill**; channels flow each side of Nicholls Island. **Hornet Point** is the north side of the river mouth; the Baker Lake airstrip is north of the point.

263 An **aeromarine radiobeacon** ENE of Paunraqtuuq Hill transmits on 403 kHz with identification BK (— • • • — • —).

## Baker Lake Harbour

264 The waters of Baker Lake Harbour are free of shoals except for **sand bars** extending from the mouth of Thelon River. The shores, mostly sand and boulder, slope gently. The SW part of the harbour abreast of the airstrip is **shallow**.

265 The usual **anchorage** is 0.5 mile offshore in depths of 6 to 12 m, soft clay with good holding.

266 **Caution**. — The **current** is strong in the river entrance but negligible off the north shore of the harbour.

267 **Caution**. — The harbour is sometimes busy with **seaplane traffic**.

268 A **satellite dish**, 62 m in elevation, and a weather station **dome**, 19 m in elevation, 1.1 miles and 0.75 mile east of the NW corner of the harbour, make good **landmarks**. Aircraft obstruction **lights** are shown from the receiver dish and from radio **towers** 0.2 mile SW of the dish.

269 A cluster of radio **towers** on the west side of the harbour is prominent; the highest tower has an aircraft obstruction **light**. There is a white aeronautical rotating **light** near the north end of the airstrip.

270 There is a rubble **jetty** with a depth of 4 m at its outer end, abreast of Department of Transport buildings, 1 mile east of the NW corner of the harbour.

271 Baker Lake **leading beacon range** is on the west side of the harbour near the north end of the airstrip. Each **beacon** is a lattice **tower** 3 m high with a fluorescent-orange **daymark**, black vertical stripe. These beacons, in line bearing 258½°, lead to a beach used mainly for landing drums of fuel.

272 The hamlet of **Baker Lake**, population 1,507 *(2001)*, is on the north shore north of the mouth of Thelon River. The community has a post office, health centre, dental clinic and RCMP detachment. There are several retail stores in the settlement and accommodations are available at hotels, lodges and a bed-and-breakfast. *Calm Air International* provides daily flights; *Keewatin Air* provides daily flights except Saturdays. There are fixed-wing aircraft available for charter.

# Hudson Bay — West Side




## General

1 There are *National Research Council of Canada* **firing practice and exercise areas** in Hudson Bay. *(For details see the annual edition of Canadian Notices to Mariners.)*

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

## Chesterfield Inlet to Rankin Inlet

*Chart 5449*

2 From Chesterfield Inlet to the entrance of **Rankin Inlet**, 40 miles to the SSW, the coast is irregular and mostly low; the terrain rises to 100 feet (30 m) 2 to 4 miles inland. Long gravel ridges run parallel to the many rivers and streams entering this stretch.

*Chart 5630*

3 **Josephine River** *(shown on Chart 5449)* is on the mainland 13 miles SSW of Fairway Island *(described in Chapter 6)*.

4 **Baker Foreland** *(62°55'N, 90°49'W)* is easily identified; its two hills are the highest land in the area. The north point, a narrow bare ridge of grey rock, contrasts sharply with the surrounding shore of sand and boulders.

5 **Caution**. — The coastal waters between Josephine River and Baker Foreland are **shoal** for a long distance offshore.

6 **Baird Bay**, on the SW side of Baker Foreland, has mostly low shores with many red and grey boulders. A ridge of terraced grassy hills rises behind the bay to 30 m.

*Chart 5629*

7 **Hazy Islet** *(62°48'N, 90°57'W)*, 2 m high, is the highest part of a wide **rocky patch**. **Rabbit Island**, 7.5 miles west of Hazy Islet, is 20 m high.

8 **Caution**. — There are **rocks** and small islets around Hazy Islet and there are other **reefs** between the islet and the shores of Baird Bay.

9 **Scarab Point**, on the mainland 3 miles west of Rabbit Island, is the NE entrance point of Rankin Inlet; **Pangertot Peninsula**, 17 miles to the SW, is the south side of the inlet. Pangertot Peninsula is 30 m high.

## Rankin Inlet and approaches

10 **Caution**. — **Local knowledge** is necessary to navigate to the head of Rankin Inlet.

11 **Cairns** are usually on high points but many are reported difficult to identify.

12 The **tidal ranges** of mean and large tides at Marble Island are 2.5 and 3.7 m. At Panorama Island, near the head of Rankin Inlet, they are 3.2 and 4.6 m.

13 **Caution**. — Strong **cross-currents** have been experienced in the entrance to Rankin Inlet. These usually flow SW at 1 knot on the flood but sometimes flow in the opposite direction. There are also **tide rips**.

14 It is reported *(1995)* that ships approach and leave Rankin Inlet 2 to 3 hours before high tide.

15 **Marble Island** *(62°40'N, 91°07'W)*, whitish grey in appearance, is the largest offshore island and is the highest land in the approaches to Rankin Inlet. **Quartzite Island** is a smaller island off the east end of Marble Island; **Mittilik Island** is joined to the north shore of Marble Island by **drying flats**. **Nauja Cove** is on the NW side of Marble Island. **Deadman Island** *(62°40'N, 91°12'W)*, composed of rock, gravel and piles of boulders, protects **Knight Harbour** on the south side of the west end of Marble Island.

16 There is a **magnetic disturbance** south of Marble Island.

17 **Caution**. — There are many **rocks** with depths of less than 10 m across the passage between Marble Island and the mainland to the NW, making it suitable only for small craft. Several **rocks** up to 5 miles SW of Marble Island also have depths of less than 10 m.

18 **Anchorage** with good holding and protection from southerly winds can be found north of Quartzite Island, NW of Mittilik Island and off Nauja Cove. **Anchorage** with shelter from all but southerly winds can be found off the south coast of Marble Island, south of Deadman Island. Small craft can find shelter north of Deadman Island or in Knight Harbour.

19 On the south side of the entrance to Rankin Inlet, **Mirage Islands** lie in unsounded waters up to 8 miles east of Pangertot Peninsula. These islands include **Crane Island**, **Nedlik Island** and **Isle of Cairns**.

20 **Caution**. — It is **dangerous** to use **fixes** based on Mirage Islands; because of the wide tidal flats, large tides and low shores, sight or radar fixes give **inaccurate** positions relative to Position Rock *(62°42'N, 91°41'W)*.

21 The east tip of Pangertot Peninsula is **Papik Point**, 7 m high. The NE shore of the peninsula is bordered by **drying reef**s, islets and islands; the named ones are **Kind Islet** *(62°40'N, 91°56'W)*, **Broken Islands** and **Sandy Islets**.

22 **Twin Knolls** *(62°48'N, 91°36'W)* appear as a dark knob when seen from near Marble Island. **False Knoll**, 4 miles to the WNW on the east side of **Dry Cove**, is similar in appearance to Twin Knolls and is sometimes mistaken for them. **Falstaff Island** is a **conspicuous island** 3 miles farther west; from the SE, the island looks like an isolated cone-shaped mound. **Outer Shoals** lie 3 miles SW of Twin Knolls. **Hidden Rock** and **Middle Shoals** lie 4 to 5 miles west of Outer Shoals.

23 **Caution**. — The north shore of Rankin Inlet is bordered by **drying ledges** and **reefs** up to 3 miles offshore.

24 The east tip of Falstaff Island is reported to provide a good radar target.

25 In the middle of the inlet 12 miles west of Marble Island are **Fairway Shoals**; **Position Rock** *(62°42'N, 91°41'W)*, which dries 1 m, usually breaks when covered. **Pin Rock**, one of a string of **shoals** and **rocks** 2 miles WSW of Position Rock, dries 1.6 m. **South Shoals** lie 4 miles WNW of Position Rock.

26 A slight easterly **set** has been reported on the **flood tide** between Fairway Shoals and Middle Shoals.

27 **Pod Rock**, **Little Pod Rock** and **Big Pod Rock** lie 3 miles NW of South Shoals along the SW side of **Separation Shoals**.

28 **Caution**. — A **rock** near the SE end of Separation Shoals has a depth of 1.5 m. **Tiny Rock**, 1.5 miles SW of Pod Rock, dries 2.4 m.

*Chart 5449*

29 **Diana River** flows into the NW end of the west arm of Rankin Inlet. **Smooth Island** *(62°44'N, 92°08'W)* is in the entrance to this arm. Islands NW and west of here include **Longspur Island**, **Ground Squirrel Island**, **Barrier Islands** and **Ahigik Island**. **Buttress Islands** *(62°45'N, 92°10'W)*, in

the bay NW of Smooth Island, are cone-shaped from eastward.

30 **Caution**. — The west arm of Rankin Inlet is **not surveyed**.

*Chart 5629*

31 **Prairie Bay** is entered between **Fist Point** *(62°48'N, 92°04'W)*, on **Kudlulik Peninsula**, and **Siskin Point**, 5 miles to the ENE.

32 **Caution**. — Prairie Bay is bordered by **drying flats** and has islands, islets, **reefs** and **shoal water**.

33 **Thomson Island** lies on the north side of the entrance of Prairie Bay. **Horseshoe Deep** is the basin to the south of Thomson Island. **Dark Point**, the east end of the island, can be identified by a **cairn** 0.3 mile inland. **Penny Islet** lies on extensive, partly **drying shoal**s extending 1.5 miles ESE and SE and 0.8 mile south of Dark Point. The larger of **Gravel Islets** *(not named on the charts)*, 1 mile NW of Dark Point, has a **cairn**.

34 **Thomson Passage** is **shoal** at the west end but **anchorage** can be found in the east part. **Swan Island** is at the west end of Thomson Passage.

35 **Caution**. — Thomson Passage is **obstructed** by **shoals**.

*Chart 5628*

36 **Sanderling Island** *(62°51'N, 92°06'W) (not named on Chart 5628)* lies on a **drying flat** near the head of Prairie Bay. **Rightfoot Islet** is 0.7 mile east. **Mittik Island**, marked with a **cairn**, is 1.2 miles SE of Sanderling Island.

37 The channel to Prairie Bay leads from east of Separation Shoals between **Guillemot Bank** *(62°46'N, 91°55'W)*, with a least depth of 2.8 m, and the NE and north sides of a chain of islands, islets and **rocks**. Some of these rocks are 5 m high at low tide. The named features in this chain are **Harp Rock**, **Kelp Rock**, **Guillemot Island**, **Mannik Islet**, **Crag Rock** and **Guillemot Rocks**.

38 The channel leads north of Guillemot Rocks and is bordered on the west by **Bag Island** and **Cur Island**, and on the east by **Kresik Island** and an unnamed islet 1 m high.

39 **Caution**. — There are many **shoals** and there are **rocks** with depths of 2.3 m in this passage.

40 There is a **cairn** with a privately maintained orange daymark on Cur Island. A **cairn** on Bag Island was reported *(1995)* to be in good condition.

41 **Bunting Island**, **Leftfoot Islet** *(62°48'50"N, 92°00'34"W)*, elevation 2 m, and **Suluk Islet** *(62°48'48"N, 92°00'48"W)*, 3 m high, lie off the SW part of Thomson Island. **Pikuk Rock**, with a **drying height** of 2 m, lies midway between Suluk Islet and Kresik Island.

42 **Johnston Cove** is north of Fist Point. **Esker Island** *(not named on the charts)* is the point of land that forms the NE side of Johnston Cove.

43 **Caution**. — The waters between Fist Point and Cur Island are **obstructed** by islets, **drying patches** and **submerged boulders**.

44 **Caution**. — **Drying banks** are 0.3 mile NE of Fist Point; **drying banks** with **boulders** and **shoal water obstruct** Johnston Cove and extend 0.2 mile east of Esker Island.

45 Vessels have used an **anchorage** 0.4 mile east of Esker Island in 12.8 m.

46 **Caution**. — The anchorage off Esker Island offers little shelter and is not recommended for extended use.

47 Vessels waiting for a pilot have found **anchorage** 1.25 miles ESE of Kresik Island in 33 m.

48 **Caution**. — **Tidal streams** of 2 to 3 knots have been reported in these anchorages.

49 Supply barges off-load fuel to nearby storage tanks from a **landing beach** on the south side of Johnston Cove. A small-craft **wharf**, constructed in two tiers to compensate for the tidal range, extends from the NW side of the cove.

50 A **conspicuous** galvanized metal **warehouse** near the oil tanks on the south side of Johnston Cove is **floodlit** around the clock. Close west of the oil tanks there is a **conspicuous tower** with red **lights** and white **satellite dishes** near its base.

51 On the west side of Kudlulik Peninsula, **Melvin Bay** *(62°48'N, 92°07'W)* is sheltered to the SW by **Tudlik Peninsula**. The bay is very **shallow** in the NW half but has a deep, well-sheltered basin in the SE.

52 **Kango Island**, **Slab Island**, **Hump Island** and **Hillock Islet** lie in the south approaches to the bay. **Silent Cove** *(not shown on Chart 5628)* is a small bay on the SW side of an inlet on the SW side of Tudlik Peninsula.

53 The route into Melvin Bay leads south of Pod Rock, Little Pod Rock and Big Pod Rock. South of the route there is a chain of **reefs** and islands; named islands are **Net Island**, **Stickle Islet** and **Aukpik Island**. To the north lie Guillemot Island and Guillemot Rocks *(previously described)*.

54 Net Island is reported to be a good radar target.

55 **Caution**. — Only islands and land on the north side of Rankin Inlet should be used for radar fixing as **land** to the south is **very low**.

56 From NE of Aukpik Island, the route leads through **Access Passage** between **Buff Island**, to NE, and **Theron Island** and **Panorama Island**, to SW and west.

57 **Caution**. — **Rocks** with depths of 0.1 and 3.6 m lie near mid-channel 0.1 mile west and 0.2 mile

NW of the north part of Buff Island, and **shoal water** extends up to 0.2 mile east of Panorama Island.

58 **Anchorage** with good shelter in 20 to 31 m, mud, can be found in the berth west of **Survey Point**.

59 Supply barges off-load dry cargo on the east side of Melvin Bay, NE of Panorama Island.

60 The hamlet of **Rankin Inlet**, population 2,177 *(2001)*, is on the SE end of Kudlulik Peninsula. There is a post office, RCMP detachment and a regional health centre in the community. A variety of retail stores and accommodations are available. *Calm Air* provides daily flights, *First Air* and *Kivalliq Air* provide daily flights except Saturdays and *Canadian North* provides flights on Mondays, Wednesdays and Fridays.

61 A privately maintained **aeromarine radiobeacon** near the hamlet of Rankin Inlet *(62°50'N, 92°07'W)* transmits on 284 kHz with identification RT (• — • —). A privately maintained **aeronautical radiobeacon** *(62°49'N, 92°07'W)* transmits on 112.4 MHz with identification YRT (— • — — • — • —).

62 **Historical Note**. — The settlement at Rankin Inlet was first established in 1955 to provide a work force for a nickel mine which was closed in 1962. In recent years, helped by the establishment of a fish cannery, an arts and crafts program, the development of Rankin Inlet Airport as a transportation hub and the relocation here of Nunavut Government offices for the Kivalliq region, the hamlet has recovered from the closing of the mine and made good economic progress.

*Charts 5628, 5629*

63 The following route from Marble Island, to a position in Horseshoe Deep north of Guillemot Island, is followed by the *Northern Transportation Company* tug *Keewatin*, towing supply barges. From a position 1.4 miles SW of Deadman Island, set a course about 300° on Falstaff Island, passing close NE of three patches with 6.1, 7 and 6.7 m over them 3 miles south of Twin Knolls near the NE edge of Outer Shoals. When north of Outer Shoals, alter course westward, proceeding as required to pass north of Middle Shoals, Guillemot Bank and Guillemot Island and into Prairie Bay. This route leads over a least depth, as far as Horseshoe Deep, of 7.9 m.

*Chart 5449*

64 The *Northern Transportation Company* tug *Keewatin*, towing a barge whose tow cable reaches a depth of about 90 feet (27 m), sets course from Churchill direct for a position 10 miles east of Marble Island.

## Rankin Inlet to Eskimo Point

*Charts 5630, 5631*

65 The coast between Rankin Inlet and Whale Cove, and farther SW to Eskimo Point, is mostly under 30 m in elevation and is strewn with innumerable lakes and ponds.

66 **Caution**. — Coastal features are difficult to identify visually or by radar. Mariners must therefore rely for fixes upon the **navigational aids** near Dunne Foxe Island and on Walrus and Sentry Islands.

67 **Caution**. — **Shoals**, islands and **reefs** extend many miles to seaward; vessels must stay well offshore.

68 **Caution**. — The inshore waters between the entrance of Rankin Inlet and Term Point *(62°08'N, 92°28'W)*, 35 miles SW, are **not surveyed** and should not be entered without local knowledge.

### Rankin Inlet to Whale Cove

69 **Cape Jones** *(62°34'N, 91°51'W)* is the low east tip of Pangertot Peninsula, previously described.

70 **Corbett Inlet** and **Pistol Bay**, separated by **Pork Peninsula**, appear to contain many **drying flats**. **Igloo Point** is the east extremity of Pork Peninsula.

71 **Dunne Foxe Island**, elevation 9 m, has **drying patches** and islets extending ESE for 4.5 miles.

72 *Dunne Foxe Island* **light** *(2601)* is on the easternmost of the islets extending from Dunne Foxe Island.

73 **Dunne Foxe Shoal**, with a depth of 2.1 m, lies 5.3 miles ESE of *Dunne Foxe Island* light.

*Chart 5631*

74 **Whale Cove** *(62°10'N, 92°34'W)*, 13 miles SW of Dunne Fox Island, is at the SE end of an unnamed peninsula. **Wilson Bay** *(62°15'N, 92°43'W)* and **Akuuniq Bay** lie west of this peninsula.

*Chart 5642*

### Whale Cove and approaches

75 **Walrus Island** *(61°58'N, 92°28'W)*, 12 miles SSE of Whale Cove, is a prominent island with an elevation of 17.4 m; it is an important landmark when approaching the cove.

76 **Caution**. — **Vessels** proceeding along the coast should pass no less than 4 miles to seaward of Walrus Island.

77 *Walrus Island* **light** and **racon** *(2602)* are on the highest point of the island.

78 **Morso Islands**, 5 miles NW of Walrus Island, reach a maximum elevation of 9.1 m in their SW part; there is a stone **cairn** on the summit. An inconspicuous **beacon**, 6.4 m in height, located on the SW end of the largest of the Morso Islands, consists of a wooden **mast** with a forty gallon **drum** for a base.

*Chart 5631*

79 The largest islet of the group lying 2.5 miles NNW of Morso Islands has an elevation of 7 m; the eastern islets in this group are very low.

80 **Caution**. — **Mistake Bay**, NW of Morso Islands, is filled with islands and **shoals**.

*Chart 5642*

81 **Term Point**, elevation 4 m and rocky, is the SE end of an island bounding the east side of Whale Cove; this island is separated from the mainland peninsula by **shallow Hell Gate**. **Irik Island** and **Kayak Island** are NE of Hell Gate.

82 **Caution**. — **Corridor Shoal** lays 7 to 9 miles SE of Term Point. **Walrus Island Reef** is a wide **drying area** 2 miles ENE of Walrus Island.

83 **Caution**. — There are **shoal** areas NW of Walrus Island and around Morso Islands. A **breaking shoal** lies 1.6 miles SE of Term Point. There is a 5.9 m **shoal** 3.2 miles south of Term Point, in the approaches to Whale Cove.

84 The hamlet of **Whale Cove**, population 305 *(2001)*, is on the NW shore of Whale Cove. The community has a post office and a nursing station. Police services are administered by the RCMP detachment in Rankin Inlet. There is a retail store and an *Inns North* hotel in the settlement. *Kivalliq Air* provides daily flights except Saturdays; *Calm Air* provides flights on weekdays.

85 The brightly coloured houses of Whale Cove can be seen for about 6 miles. A **monument** in the shape of the tail of a whale, constructed of concrete and rock, is prominent on a hill above the settlement.

86 There is an **aeromarine radiobeacon** 4 miles NNW of the settlement. It transmits on 256 kHz with identification YXN (— • — — — • • — — •).

87 The air obstruction **lights** of the radiobeacon **tower** are **conspicuous**.

88 **Anchorage** can be found south of the hamlet in Whale Cove but the water is deep with protection only from the north. **Anchorage** with excellent protection, clay bottom, can be found in the eastern part of Akuuniq Bay.

89 The supply barge is berthed bows-to 1 hour before high water at a gravel **landing area** in the NE bay of Whale Cove.

*Chart 5449*

90 The *Northern Transportation Company* tug *Keewatin*, towing a barge whose tow cable reaches a depth of 90 feet (27 m), sets course directly for Churchill from a position 10 miles east of Walrus Island.

*Chart 5631*

## Walrus Island to Eskimo Point

91 The coast between Walrus Island *(61°58'N, 92°28'W)* and Eskimo Point, 68 miles SW, is low with no distinct features. **Tidal flats** extend from the shore for up to 10 miles in places. There are only a few prominent islands useful for navigation.

92 A corridor 5 miles wide between Walrus Island and Eskimo Point has been surveyed to modern standards *(1998)*.

93 **Caution**. — Most of the inshore coastal waters, except those off Walrus Island and Eskimo Point, are **not surveyed** and should not be entered without local knowledge.

94 **Caution**. — The sounded waters offshore were surveyed in 1977 and indicate a fairly even bottom. Because of the **wide spacing** of the sounding lines it is possible that **undetected dangers** exist and caution is recommended.

95 The approaches to Eskimo Point were also sounded in 1977.

96 **Tavani** *(62°03'N, 93°05'W)*, on the mainland WNW of Walrus Island, is the site of a former *Hudson's Bay Company* post and Roman Catholic mission. A **hill** with a flat top, 0.5 mile south of Tavani, is **conspicuous**. **Flattop Island** lies 3 miles to the east.

97 **Anchorage** in 18.3 m is available off Tavani.

98 **Caution**. — The Tavani **approaches**, sparsely surveyed, are **dangerous**; there are numerous **rocks** and **shoals**.

99 **Caution**. — **Vessels** drawing more than 3.7 m should not proceed west of Walrus Island towards Tavani without **local knowledge**.

100 **Bibby Island**, elevation 30 m, forms the south side of **Nevill Bay**; **Ferguson River** enters the head of the bay.

101 **Caution**. — Nevill Bay is **obstructed** with islands and **reefs**.

102 **Imilijjuaq Island** and **Imiligaarjuk Island**, with elevations of 23 to 30 m, lie 10 miles SW of Walrus Island. **Ivuniraarjuq Island**, low, lies 3 miles east of Imilijjuaq Island.

103 **Dawson Inlet**, with **Copperneedle River** at the head of the south arm, is believed to be **shallow** with irregular

depths. **Angusko Point**, elevation 23 m, is at the SW entrance of the inlet.

104 **Caution**. — **Breakers** have been reported 6 miles east of the point.

105 **Sandy Point** *(61°44'N, 93°16'W)* forms the north entrance point to a well-sheltered bay with a reported depth of 6.4 m.

106 The coast between Dawson Inlet and Maguse Point, 30 miles SSW, is characterized for many miles inland by glacier-formed gravel ridges known as eskers. Some of the eskers reach the water's edge as long narrow points and continue offshore as narrow islands.

107 **Caution**. — **Depths** off this stretch are very **irregular**; these waters should not be entered without **local knowledge**.

*Chart 5641*

108 **Maguse Point** *(61°20'N, 93°49'W)*, the east extremity of **Austin Island**, is less than 15 m high but is prominent. Austin Island, elevation 36 m, is separated from the mainland by the two island-choked channels of **Maguse River**. The site of an abandoned trading post is at the mouth of the south channel.

109 **Caution**. — Maguse River is **not navigable**, except with difficulty by canoe.

## Eskimo Point and approaches

110 **Sentry Island** *(61°09'N, 93°52'W)* rises gently from both ends to a central elevation of 17 m; it can normally be detected visually and on radar at 8 miles and sometimes has been sighted at 15 miles.

111 *Sentry Island* **light** and **racon** *(2603)* are near the highest point of the island. There is a triangular **beacon**, not maintained, on the highest point of land 9 m NW of the light structure.

112 **Caution**. — **Sentry Island Shoal**, a **drying boulder ridge**, extends 4 miles ESE of Sentry Island. **Rocks** with depths of 5 m or less extend 3.6 miles ENE. A vessel proceeding along the coast should pass at least 8 miles east of Sentry Island.

113 **Caution**. — **Tidal streams** off Sentry Island reach rates of 2 knots on the ebb and up to 5 knots on the flood. Rates can be affected by winds and streams are deflected by Sentry Island Shoal. The strongest streams are in **shallow** waters close to the shoal.

114 There is **anchorage** with good protection from northerly winds and free of strong tidal streams in a position bearing 174°, 2.2 miles from the *Sentry Island* light; depths of 13 m are close north of a 7 m **patch** of **mud** and **boulders**. Shallow-draught vessels can find **anchorage** closer to Eskimo Point but should be prepared to move should easterly winds develop. **Anchorage** in 24 m, soft clay, can also be found 1 mile north of Sentry Island.

115 **Eskimo Point** *(61°06'N, 93°59'W)*, low and sandy, is the south entrance point to an unnamed bay.

116 A **beacon** formed by wooden **poles** is on Eskimo Point; a similar **beacon** is on an unnamed point 2.5 miles to the north, at the north entrance of the bay.

117 **Caution**. — **Tidal flats** and **drying patches**, most covered with **boulders**, extend up to 1.5 miles off the north entrance point of the unnamed bay and fill the northern half of the inner part of this bay; there is a narrow channel along the south side. There is a **shoal depth** of 2.6 m in the approaches to the bay. A **rock** with a depth of 3.1 m lies 2.4 miles east of Eskimo Point. A **drying flat** extends 0.4 mile off the south shore 1.2 miles WNW of Eskimo Point.

118 The community of **Arviat (Eskimo Point)**, population 1,899 *(2001)*, is on the south side of the unnamed bay, 2 miles WNW of Eskimo Point. The community has a post office, health centre, RCMP detachment, 2 retail stores, 2 hotels, a bed-and-breakfast and a coffee shop. *Calm Air* provides flights daily and *Kivalliq Air* provides flights daily except Saturdays. Helicopter charters are available.

119 A privately maintained **aeromarine radiobeacon** *(61°06'N, 94°04'W)* transmits on 329 kHz with identification YEK (— • — — • — • —).

120 The radiobeacon **tower**, elevation 23.1 m, with red aircraft obstruction **lights** and two shorter **towers** with fixed red **lights** are **conspicuous** at night. A white, rotating aeronautical **light** on top of the airport building is also **conspicuous** at night.

121 A **conspicuous school** near the middle of the hamlet has been seen at 15 miles. The school has orange walls visible from north and south and a white roof visible from the east.

122 Six large **oil tanks** south of the hamlet are **conspicuous**, as is a wooden **cross** 5 m high on the south point of a narrow peninsula, elevation 11 m, lying 1 mile north of the hamlet.

123 Sand and gravel **landing beaches** with scattered boulders are between 2 boat **ramps**. The supply barge is berthed bows-to about 2 hours before high water. The *Northern Transportation Company* tug *Keewatin* uses a boat to mark the channel to the landing beaches with buoys before bringing the barges in.

*Chart 5449*

124 The *Northern Transportation Company* tug *Keewatin*, towing barges whose tow cables reach depths of 90 feet (27 m), sets an easterly course from the hamlet to a position 38 miles east of Eskimo Point, then alters course directly for Churchill.

## Eskimo Point to Churchill

*Charts 5399, 5400*

125 **Caution**. — Most of the inshore coastal waters between Eskimo Point *(61°06'N, 93°59'W)* and Egg Island, 75 miles to the SSW, are **not surveyed** and require local knowledge. The sounded waters offshore *(shown on Chart 5399)* were surveyed in 1977 and indicate a fairly even bottom; however, because of the **wide spacing** of the sounding lines it is possible that **undetected dangers** exist and caution is recommended. Hydrographic information between Egg Island and Churchill is based on lead-line surveys between 1928 and 1931 and should be used with caution.

*Chart 5399*

### Eskimo Point to Egg Island

126 The coast between Eskimo Point and Egg Island is marshy and low; the land rises less than 30 m in elevation for 3 to 5 miles inland. The coast is bordered by **drying flats** extending up to 4 miles offshore and should not be approached closer than 6 miles.

127 **McConnell River** *(60°52'N, 94°22'W)*, **Tha-anne River**, **Thlewiaza River** and **Geillini River** *(not named on the chart)* enter Hudson Bay along this stretch.

128 **Egg Island** *(59°55'N, 94°50'W)*, a low island at the mouth of **Egg River**, is the site of the former trading post of **Nunalla**. The abandoned **buildings** of this post are **conspicuous** *(2007)*. The parallel of 60°N, about 4 miles north of Egg River, is the boundary between Nunavut and the province of Manitoba.

*Chart 5400*

### Egg Island to Churchill

129 The coast continues to be low and featureless between Egg Island and Churchill, 68 miles southward. The tree line approaches the coast a few miles north of Seal River and from there to Churchill it is within a few miles of the shore.

130 **Caution**. — **Tidal flats**, littered with **boulders**, extend up to 3 miles offshore in the northern part and up to 5 miles offshore in the southern part of this coastline.

131 **Hubbart Point** *(59°22'N, 94°39'W)*, elevation 30 feet (9 m), is a prominent feature at the NE end of a group of islands lying on a **drying spit**. **Caribou River** enters Hudson Bay 3 miles SW of the point.

132 **Anchorage** with shelter from westerly winds can be found 1.5 miles SE of Hubbart Point in about 8 fathoms (15 m).

133 There is a **drying bank** 6 miles south of Hubbart Point. The mouth of **Little Seal River** is 5 miles SW of the bank.

### Approaches to Churchill Harbour

134 **Point of the Woods** *(59°02'N, 94°44'W)* is the south entrance point of **Seal River**. A large island splits the river into 2 channels. The river mouth can be identified by **The Knoll**, a hillock on the island.

135 **Caution**. — A large **boulder** lies 5.7 miles ESE of Point of the Woods. **Shoal depths** of less than 3 fathoms (5.5 m) lie 9.5 miles east of the point.

136 **Knife Delta**, elevation 17 feet (5 m), lies in the mouth of **North River**. **North Knife River** and **South Knife River** join just upstream of the delta to form North River. **Wales Point** is the east end of an esker.

137 **Button Bay** is only partly surveyed but is believed to be **shallow**. Two prominent rocky knolls on the east side of the bay are separated by **Sea Horse Gully**.

138 **Cape Churchill** *(58°47'N, 93°15'W)*, 30 miles east of Churchill Harbour, has an elevation of 25 feet (7.6 m).

139 The cape is marked with a **beacon** consisting of a **square structure** with a **pyramidal top**; the structure has a **radar reflector**. The condition of this beacon is unknown *(2006)*.

140 The coast from Cape Churchill westward past **La Pérouse Bay**, **Watson Point** and **Gordon Point** to Halfway Point is low and swampy.

141 **Caution**. — The foreshore here is **flats** of **sand** and **mud** covered with **boulders**. These flats extend up to 3.5 miles offshore and **shoal depths** less than 6 fathoms (11 m) exist up to 6.5 miles off as far as Watson Point and up to 8 miles off between Watson Point and Halfway Point.

142 **Churchill Shoals** *(58°52'N, 93°44'W)*, an extensive area of shoals with several **drying patches**, has depths of 3 fathoms (5.5 m) and less up to 5 miles off Gordon Point.

143 **Caution**. — **Vessels** should stay outside the 10 fathom (18.3 m) line to avoid Churchill Shoals and the depths under 6 fathoms (11 m) extending seaward.

144 **Fox Islands** *(58°48'N, 93°35'W)* are bare. **Halfway Point** is small and rocky.

145 An O*cean Data Acquisition System* **light buoy** is 15 miles NNW of Halfway Point.

146 A rocket-launching **tower** 2.5 miles SSE of Halfway Point is **conspicuous**. A number of prominent radio **towers** are along the coast between Halfway Point and Churchill. A **conspicuous** white **grain elevator** on the east side of Churchill Harbour is visible for 20 miles. The only prominent natural features are near Watson Point; these are **Knights Hill**, a small whale-backed mound, and **Stony Knoll**, similar in appearance but lower.

147 **Bird Cove** is close west of Halfway Point.

148 **Caution**. — **Rocks** and **drying patches** exist more than 2 miles offshore between Bird Cove and Churchill airport.

*Chart 5640*

## Churchill Harbour

149 **Churchill Harbour** *(58°47'N, 94°12'W)*, in the mouth of the **Churchill River**, is bordered on the east side by a rocky peninsula tapering to a blunt point at **Cape Merry**. On the west side of the harbour, on another rocky peninsula, **Fort Prince of Wales**, begun in 1732 and finished 40 years later, is black, flat-topped and prominent. It is now known as **Prince of Wales Fort National Historic Site of Canada**. **Eskimo Island**, with **Eskimo Point** at its north end, lies north of the west peninsula.

150 **Caution**. — **Merry Rock**, **drying** 3 m, lies on a shoal extending 0.2 mile NNW of Cape Merry. **Foul ground** extends 0.15 mile off the NW entrance point of the harbour. Both shores of the harbour are bordered by **drying flats**; those on the west side are more extensive.

152 *Merry Rock* **light buoy** *C1 (2606)* is in the harbour entrance 0.1 mile NNW of Merry Rock. The entrance and fairway through the harbour are marked by **lighted buoys**.

153 *Churchill range* **leading lights** *(2612, 2613)*, SW of Ship Point, in line bearing 236½°, lead through the harbour entrance to the intersection of *Fort Prince of Wales range* in a least depth of 7.1 m. The lights are visible only when in alignment. There is a **racon** at the front tower.

154 *Fort Prince of Wales range* **leading lights** *(2608, 2609)*, in line bearing 344°, lead from the intersection of *Churchill range* to that of *Ship Point range*. The lights are visible only when in alignment.

155 *Ship Point range* **leading lights** *(2610, 2611)*, NNW of Ship Point, in line bearing 317½°, lead from the intersection of *Fort Prince of Wales range* to the wharf. The lights are visible only when in alignment.

156 *Churchill Harbour* **light** *(2622)* is shown from the top of the grain elevator.

157 There are 3 privately maintained **aeromarine radiobeacons** at Churchill. The most powerful *(58°46'N, 93°57'W)* transmits on 305 kHz with identification YQ (— • — — — — • —). The second *(58°46'N, 94°11'W)* transmits on 356 kHz with identification Q (— — • —). The third *(58°40'N, 94°00'W)* transmits on 257 kHz with identification Y (— • — —). A privately maintained **aeronautical radiobeacon** *(58°45'N, 94°08'W)* transmits on 114.1 MHz with identification YYQ (— • — — — • — — — — • —).

158 An aeronautical rotating **light** is shown from a building at Churchill airport; aircraft obstruction **lights** are shown from the many radio towers in Churchill and vicinity.

159 The **tidal ranges** of mean and large tides at Churchill Harbour are 3.4 and 4.8 m.

160 The speed and direction of **currents** *(shown on Chart 5640)* were derived from studies carried out in 1992. These speeds and directions are averages of the currents observed in the upper 2 to 5 m of the water column; they indicate the current that can be expected to affect a vessel during spring tides.

161 **Caution**. — Shallow-draft vessels will experience near-surface **currents** stronger than those shown *(on Chart 5640)*. Ebbing surface flows at the mouth of the river, near Merry Rock, can reach speeds of 5 knots and can cause a slight set towards the NW shore. Ebbing surface flows near the grain wharf reach speeds of 4 knots and tend to set in a NE direction onto the wharf.

162 There is a noticeable back **current** along the east and west shores of Cape Merry during the ebb tide. The flow is stronger along the western shore and can reach speeds of about one knot near the surface.

163 During the flood, surface **currents** reach about 3 knots at the river mouth near Merry Rock and about 2 knots near the grain wharf; this flow tends to run parallel to the wharf.

164 **Currents** outside the deeper dredged areas are significantly weaker than those in the channel; shear lines develop and are visible near the western side of the dredged channel. These shear lines are most prominent during spring tides.

165 **Caution**. — During the ebb, the river flows into Hudson Bay in a strong jet flowing in a NE direction past *Merry Rock light buoy C1*. There may be **rips** and **eddies** near and north of this buoy during spring tides. During strong NE and easterly winds, steep **waves** develop at the river mouth on the ebb tide.

166 A vessel under 162 m long can enter on the flood tide and turn bows north on her port anchor, letting it go off the berth. A larger vessel enters on the ebb and lays bows south, turning on the next flood. Vessels berthed bows south should be well secured by a minimum of four head lines and two breast lines as a precaution against the strong ebb flow. A vessel berthed bows north should use six stern lines as well as her back springs.

167 **Pilotage** is compulsory for merchant ships entering or shifting berth in Churchill Harbour. Pilotage is controlled by the *Great Lakes Pilotage Authority Ltd*. Masters can arrange for a **pilot** through *MTCS Iqaluit* or may call the Port Warden's office at 204 675-2263 or the pilot boat *H. M. Wilson* direct on VHF. The pilot boat will meet vessels 4 miles NE of the harbour entrance. It is essential that a ship's ETA is known at least three hours in advance so that the pilot boat can be on station. During adverse weather, vessels are

CHURCHILL

requested to provide a good lee for the pilot boat boarding and disembarking operations.

168 The recommended **anchorage** for larger vessels is 1 to 3 miles NW to NE of the pilot boarding station in 20 to 26 m over sand and mud. This anchorage is exposed; vessels in light condition may drag, particularly in strong NE winds. Vessels should not anchor off the harbour entrance because the ebb tide is strong and there is a danger of dragging ashore should a NE gale develop.

169 Masters of smaller vessels may consult harbour authorities about possible short-term **anchorage** inside the harbour.

170 The average thickness attained by level **fast ice** at Churchill Harbour is 177 cm with a record maximum thickness of 206 cm *(1976)*. Break-up normally begins about the end of May, with the river clearing of ice about the middle of June. Freeze-up usually begins during the second half of October with complete ice cover developing during the second week of November. Two to four weeks variation in break-up and freeze-up can occur. Freeze-up and break-up on Hudson Bay, off Churchill Harbour, occur on the average two to four weeks later.

171 For non ice-strengthened (type E) vessels, navigation through Hudson Strait and Hudson Bay to Churchill is generally feasible by the last week in July; the latest departure date, governed by the ice in Churchill Harbour, is about October 20. The navigation season is several weeks longer for type C and type D vessels *(see "Arctic Shipping Pollution Prevention Regulations")*.

172 The *Canadian Coast Guard* provides ice information and routing and icebreaker assistance in Hudson Strait and Hudson Bay. To obtain these services a master should, before entering or leaving these waters, communicate with *NORDREG CANADA* directly or through the nearest *MCTS* centre *(see "Radio Aids to Marine Navigation — Atlantic, St. Lawrence, Great Lakes, Lake Winnipeg and Eastern Arctic")*.

173 Masters can obtain ice information for Churchill from the Port Warden *(see "Ice Navigation in Canadian Waters", 1999 Edition)*.

### Port of Churchill

174 The Port of Churchill is owned and operated by *OmniTRAX Canada*.

175 The port facilities of **Churchill** are on the east side of Churchill Harbour. Churchill is a major terminal for shipping grain to markets in Europe. The grain is brought by rail from the prairies and transferred to a storage elevator with a capacity of 154,000 tonnes. About 500,000 tonnes of grain are shipped each year. Other cargoes include gasoline, diesel fuel, jet fuel and dry goods destined for Nunavut.

176 The main **wharf**, 838 m long with depths alongside of 9 to 11.5 m *(2002)*, has a tanker berth and two grain loading berths; one is a deep berth where loaded ships can lay at low water spring tide. There is also a general cargo and coastal traffic berth.

177 The usual procedure is to load one vessel at a time using up to four grain belts; each belt has a capacity of 227 tonnes per hour. Loading is suspended when a draught of 9.1 m is reached and then resumed on the flood to enable the vessel to sail at high water. The water density varies from almost fresh at low water to almost salt at high water; a hydrometer must be used to determine fresh water allowance for the loaded draught.

178 A crawler **crane** on the wharf, with a 24 m boom length, has approximate capacities of 35 tonnes at 75 degrees and 72 tonnes at 45 degrees. The maximum rated capacity is 100 tonnes.

179 **Stevedoring** is done by the port's general utility workers.

180 The community of **Churchill**, population 963 *(2001)*, is a local government district for administrative purposes. The town has a post office, bank, health centre with medical and dental care and a detachment of RCMP. Because Churchill is a centre for ecotourism, hotels, restaurants and gift shops abound. There is a *Northern Store* in the community. Accommodation may be difficult to find at certain times of the year, particularly in late fall. *Calm Air* provides daily flights and *Kivallik Air* provides flights daily except Saturdays.

181 The site of the former military base of *Fort Churchill* is 3 miles east of the town. Further east, the **Churchill Rocket Research Range**, now designated by Parks Canada as a National Historic Site, was formerly operated by the National Research Council of Canada to conduct atmospheric research.

## Churchill to James Bay

*Chart 5003*

182 **Caution**. — The coastal waters along the SW shore of Hudson Bay from Churchill to James Bay, except for the entrance of Nelson River, are **not surveyed** and should not be entered without local knowledge.

183 **Caution**. — The SW shore of Hudson Bay is low with **shoal water** extending, in most places, for a considerable distance offshore. There are numerous beaches of sand, gravel, pebbles and boulders where small craft can land but they can find shelter afloat only at Port Nelson and Fort Severn. The whole coast is open to northerly winds and there are no sheltered anchorages for larger vessels.

184 The land is flat. The tree line is 10 to 15 miles behind the coast from Churchill almost to Owl River, then is close to the coast as far as Cape Tatnam. From there to Cape Henrietta Maria the tree line lies 5 to 15 miles inland.

## Cape Churchill to Cape Tatnam

185 The coast is low and swampy with no distinguishing features between Cape Churchill *(58°47'N, 93°15'W)* and Cape Tatnam, 116 miles SE. **Rupert Creek**, **White Whale River**, **Salmon Creek**, **Broad River** and **Owl River** are named creeks and rivers entering this stretch, most through wooded valleys.

186 **Caution**. — The coast is bordered by a **drying flat** and **shoal water** extends an average of 6 miles offshore and as much as 10 miles off at Rupert Creek.

187 **Thompson Point** is a slight projection 30 miles SSE of Cape Churchill.

*Charts 5003, 5406*

188 **Caution**. — **Nelson Shoal** *(57°36'N, 92°15'W)* is an extensive **shoal** and **drying patch** extending 10 miles offshore, about 30 miles north of the mouth of Nelson River. Composed of gravel and occasional **boulders**, it dries 16 feet (4.9 m), remains partly uncovered at neaps but covers 2 feet (0.6 m) at springs.

189 **Port Nelson** *(57°05'N, 92°24'W)* is in the estuary of **Nelson River**.

190 **Historical Note**. — This is where Thomas Button wintered in 1612-13. Button named the site after Francis Nelson, master of the *Resolution*, who died during that winter. Almost 300 years later, Port Nelson was intended to be the terminus of the Hudson Bay railway; a considerable amount of work was done but it was abandoned, in 1917, in favour of Churchill.

191 The ruins of Port Nelson settlement and wharf are on the west shore near **Root Creek**.

192 The **tidal ranges** of mean and large tides at Port Nelson are 12 and 16 feet (3.8 and 4.8 m).

193 **Caution**. — The **tidal stream** floods at up to 3.5 knots and ebbs at up to 6.5 knots; the stream sets a vessel strongly SE in the entrance.

194 A narrow channel, with depths over 18 feet (5.5 m), leads as far as the anchorage at the site of the former settlement. The river upstream, with broad **mud flats** at low water, is navigable as far as **Flamborough Head**.

195 **Caution**. — **Depths** and the position of channels in Nelson River may have changed due to **silting**.

196 **Caution**. — Two **wrecks** in Port Nelson and approaches were reported *(1954)* to be good landmarks but may no longer be prominent.

197 **Hayes River**, site of the abandoned *Hudson's Bay Company* post of **York Factory** *(57°01'N, 92°16'W)*, is entered through a very narrow channel with a depth of only 1.5 feet (0.5 m) between extensive **mud banks**. Once over the entrance **bar** it is reported that, by keeping close to the NW shore, a depth of 4 feet (1.2 m) can be carried to York Factory.

198 **Historical note**. — York Factory, first established as Fort York in 1682, was the major *Hudson's Bay Company* post on the bay. Furs from the interior were brought down the Nelson and Hayes Rivers for shipment to Europe. The Red River settlers from Scotland were landed here in the early 1800's and made their way south along the Hayes River to what is now Winnipeg.

199 **Marsh Point** is at the end of a low swampy peninsula between Nelson River and Hayes River. The outer 10 miles of the peninsula is almost covered at high water. A narrow strip of slightly higher land along the SE side of this peninsula is about 2 feet (0.6 m) above high water at Marsh Point and 25 feet (8 m) above at York Factory.

200 There is an **anchorage** suitable for small vessels off Port Nelson. **Anchorage** can be found bearing 027°, 12 miles from Marsh Point in 7 fathoms (12.8 m), in an area known as **York Roads**.

201 **Caution**. — Both anchorages are **exposed** to frequent NE gales.

202 A communications **tower** 820 feet (250 m) high is on Marsh Point.

203 **Cape Tatnam** *(57°16'N, 91°00'W)*, low and swampy, is 40 miles ENE of Marsh Point. A large **boulder** close west of the cape is **conspicuous**. **Tatnam Shoal**, 4 miles NNE of the cape, is a pile of **drying boulders**.

204 **Caution**. — **Vessels** should stay outside the 5 fathom (9.1 m) line in this vicinity.

*Chart 5003*

## Cape Tatnam to Fort Severn

205 The coast between Cape Tatnam and Fort Severn, 137 miles ESE, continues to be low and swampy.

206 **Caution**. — Sparse soundings indicate **shoal water** extends 10 to 15 miles offshore, and perhaps farther.

207 **Anabusko River**, **Kaskattama River**, the site of a former *Hudson's Bay Company* summer trading post, and **Kettle River** reach salt water 18, 33 and 58 miles ESE of Cape Tatnam. **Black Duck River** enters Hudson Bay 12 miles farther ESE. Inconspicuous **monuments** near the mouth of Black Duck River mark the boundary between the provinces of Manitoba and Ontario.

208 **West Pen Island** *(56°51'N, 88°50'W)* and **East Pen Island** are low islands composed of disintegrated limestone ridges. A sandy **knoll**, on the mainland opposite East Pen Island, is **conspicuous**. The knoll has an elevation of 50 feet (15 m).

209 **Caution**. — The Pen Islands lie in a **shoal area** with depths of less than 3 fathoms (5.5 m) extending 10 miles offshore.

210 **Niskibi River** and **Pipowitan River** enter Hudson Bay 24 and 52 miles SE of East Pen Island.

211 **Partridge Island**, in the mouth of **Severn River**, has elevations of 8 to 15 feet (2.4 to 5 m); salt marshes extend off its NW point.

212 The estimated **tidal range** of large tides at Severn River is 11 feet (3.4 m). West winds tend to increase the range.

213 The channel on the west side of Partridge Island is marked by **private buoys** and **beacons** and is navigable by craft drawing up to 8 feet (2.4 m).

214 **Caution**. — **Mud bars** in the approaches and entrance and **rapids** within the entrance must be navigated at high water. Local knowledge is essential; a local **pilot** is available.

215 The settlement of **Fort Severn** *(56°00'N, 87°38'W)*, population 401 *(2001)*, lies at the head of navigation 6 miles within the entrance of Severn River. The community has a post office, a health centre staffed with 2 nurses and a police station with 1 constable. There is a *Northern Store*, a convenience store and a hotel. *Wasaya Airways* provides flights daily except Sundays and *North American Charters* provides flights on weekdays.

216 A **jetty** made of poles is constructed at the settlement each year. A new permanent wharf, in deeper water, is planned *(2005)*.

## Fort Severn to Winisk River

217 The low marshy coast between Severn River and Winisk River, 96 miles ESE, is broken by only four features: **Goose Creek**, **Shell Brook**, **Wood Creek** and **Gooseberry Brook**.

*Chart 5476*

218 **Winisk River**, wide but **shallow**, has a broad **bar** of **stones**, **boulders** and **gravel** with depths of 1.5 to 2 feet (0.4 to 0.6 m) across the entrance. The bar can be crossed at high water by small craft or canoes only.

219 **Caution**. — Winisk River bar **breaks** with the slightest sea or swell. A **shoal area** filled with **reefs**, SE of **Wabuk Point**, extends 3 miles off the bar.

220 The **tidal ranges** of mean and large tides in the Winisk River area are 7.5 and 11 feet (2.3 and 3.4 m).

221 **Drying sand and mud flats** border the coast east of the river mouth, extending 2 miles off **Oman Point**. There is a **conspicuous rock** just off Oman Point. A dredged approach channel and turning basin at **Flagstaff Point** are no longer maintained and are reported to have silted up. A **wharf** along the approach channel is in **ruins**.

222 An **anchorage** in 4 fathoms (7.3 m), 5 miles NNE of Flagstaff Point, is unsheltered with poor holding over rock or stone.

223 The site of the former settlement of **Winisk** *(55°16'N, 85°14'W)* lies in the mouth of Winisk River. Winisk was destroyed by a spring flood in 1986; the settlement was relocated to the west side of the Winisk River about 20 miles from the entrance and renamed Peawanuck. Many of the structures of the abandoned *RCAF Winisk* station on the east shore at the mouth of the river are still standing *(2004)*.

224 **Peawanuck** *(55°01'N, 85°28'W)*, population 193 *(2001)*, has a post office, a health clinic staffed with 2 nurses and a police station staffed with 2 constables. There is one retail store in the community; there are no hotel accommodations. *Air Creebec* provides flights on Tuesdays and Thursdays.

225 The sealift barge discharges cargo at the mouth of the river near the site of Winisk. Supplies are transported to Peawanuck later in the year over a winter road.

226 A draught of 3 feet (0.9 m) can be carried above the **bar** in the mouth of Winisk River upriver to Peawanuck. Freighter canoes can navigate the river; local knowledge is recommended.

*Chart 5003*

## Winisk River to Cape Henrietta Maria

227 **Wachi Creek** flows into Hudson Bay midway between Winisk River and **Cape Lookout** *(55°18'N, 83°56'W)*, 42 miles east. The cape, low and backed to SE by an area of raised beaches, has a boulder and pebble islet 0.25 mile offshore.

228 **Caution**. — A sunken **reef** is reported to extend NW from the cape.

229 **Sutton River** and **Kinushseo River** enter a **shallow** reef-filled bay on the west side of **Little Cape**.

230 An island, with an elevation of 25 feet (8 m), lies close offshore 25 miles east of Little Cape; an islet and **drying patches** lie up to 8 miles offshore from here.

231 **Caution**. — Between the **drying patches** and Cape Henrietta Maria *(55°09'N, 82°20'W) (described in Chapter 5)*, two small islands on **drying flats** and a **rock** with a depth of 2 fathoms (3.7 m) lie up to 6 miles offshore.

# Foxe Channel
# Roes Welcome Sound




## General

*Chart 7000*

1 **Foxe Channel**, between Foxe Peninsula on Baffin Island and Southampton Island, joins Hudson Strait and Hudson Bay to Foxe Basin. Roes Welcome Sound separates Southampton Island from the mainland to the west.

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

2 The **magnetic compass** is erratic throughout the area described in this chapter.

## Foxe Channel

*Chart 7065*

3 Foxe Channel is entered between Seahorse Point *(63°47'N, 80°08'W)*, the SE end of Southampton Island, and Lloyd Point, 68 miles NE on Foxe Peninsula.

4 **Caution**. — **Depths** through Foxe Channel are mostly from track soundings except for Duke of York Bay, near the north tip of Southampton Island, where a controlled **survey** was done in 1962. Ice conditions permitting, vessels should follow sounded tracks.

5 The west side of Foxe Channel has a wide, deep trough parallel with the east side of Southampton Island. The water gradually shoals north and NE of this trough. The east side of Foxe Channel is much more shoal than the west

side; **shallow water** is reported to extend several miles off Foxe Peninsula and **depths** of 9 fathoms (16.5 m) have been reported 8 miles off this shore.

*Charts 7481, 7482*

6 A **shipping corridor**, leading from abreast of Cape Queen on Foxe Peninsula to abreast of Parry Bay on Melville Peninsula, was surveyed in 1985. **Soundings** in the corridor are more accurate than track soundings.

*Chart 7065*

## Offshore dangers

7 **Seven Fathom Bank**, 68 miles north of Seahorse Point, was reported in 1955. The bank, position doubtful, has a depth of 7 fathoms (12.8 m).

*Charts 7481, 7065, 7066*

8 **Fife Rock** *(65°17'N, 82°30'W)*, 25 miles ENE of Cape Comfort on the NE side of Southampton Island, is a rocky islet with three small above-water rocks extending 0.4 mile SW. Fife Rock is a good radar target.

*Charts 7482, 7065, 7066*

9 **Elizabeth Bank** is 25 to 35 miles ESE of Adderley Bluff *(66°36'N, 82°31'W)*. **Elizabeth Reef**, a **shoal spot** on Elizabeth Bank, has a depth of 1.5 m.

*Charts 7482, 7066*

10 A **shoal area** with a depth of 11 m is 13 miles SSE of Cape Wilson *(67°00'N, 81°27'W)*. This shoal, position approximate, was reported in 1955.

*Chart 7065*

## West side of Foxe Channel — Southampton Island

11 The NE coast of **Southampton Island** rises abruptly from the sea to high broken ranges of gneiss. Very few islands lie offshore. There appears to be deep water close inshore except in some of the bays in the SE section of the coast. The highest point along the coast is 5 miles inland in the **Porsild Mountains**.

12 Seahorse Point *(63°47'N, 80°08'W) (described in Chapter 6)* is low but a hill 1 mile inland has been identified at a distance of 20 miles to seaward. Another hill, 9 miles west of Seahorse Point, is 780 feet (238 m) high and has a flat top.

13 **Caution**. — **Gorden Bay** is **too shallow** for navigation.

14 There are a few small islets close to the shore and a narrow band of **shoal water** between **Saunders Point** and **Terror Point**, 18 miles NW.

15 **M'Clure Point** *(64°04'N, 81°16'W)* consists of steep gneiss cliffs 400 feet (122 m) high. Neither M'Clure nor **Gore Point**, 3 miles west, is visible at a distance of 30 miles but the land, elevation 750 feet (229 m), 4 miles south of Gore Point appears as an island.

16 **Nalojoaq Bay** is SE of M'Clure Point. The SW shore of the bay is steep, rising to 500 feet (152 m); its NE shore is sloping. **Mount Minto**, at the head of the bay, is cone-shaped, **conspicuous** and visible for 35 miles. A mound-shaped hill, prominent from northward, lies 7 miles SE of Mount Minto.

17 **Caution**. — Nalojoaq Bay is reported to be **shallow**. There are low, shelving beaches at its head; probably bordered with **shoal water**.

18 **East Bay** is **shallow** with low shores; the small island 6 miles from its head is low. **Caribou Island** *(64°12'N, 81°27'W)* has **McMurdo Point** at its eastern end. The island has a ridge in the centre running almost the entire length; otherwise it is low, swampy and difficult to distinguish from seaward.

19 **Caution**. — **Ascension Islands** are low with **shoal water** between them and possible **submerged reefs** to the north.

*Charts 7481, 7065*

20 **Cape Fisher** and a 152-m hood-like **hill** 1 mile west are **conspicuous** between bearings of 135° and 225°. The cape is composed of rocky cliffs rising almost vertically from the water to a height of over 213 m.

21 **Caution**. — Observations in 1955 showed a **tidal stream** of 4 knots parallel to the coast off Cape Fisher.

22 **Stanley Harbour**, surrounded by rugged hills and rocky cliffs, appears to have deep water except near its head; there are two small islets near the western shore of the harbour.

23 **Cape Donovan** *(64°46'N, 82°22'W)* is easily identified by its white cliffs. They rise to 213 m within 1 mile SE of the point and extend SE for some 5 miles before being replaced by darker rock.

24 Between Cape Donovan and Cape Comfort, 34 miles NW, the coast is rocky cliffs or very steep slopes rising to more than 305 m. This stretch of coast is broken by a number of river gorges.

25 **Qakutaak Bay** is 5 miles west of Cape Donovan.

26 **Caution**. — The head of the small inlet on the west side of Qakutaak Bay and the low point protecting the north side of the inlet have **shoal water** extending a short distance off.

27 The mouth of **Mathiassen Brook**, 12 miles WNW of Cape Donovan, offers shelter for small craft. There is a small rocky islet close NW near the shore.

28 **Kokumiak Harbour** is steep-sided. The head of the harbour is silting up; the silt is from a river that cuts through a number of old beaches to reach the sea.

29 **Cape Comfort** *(65°08'N, 83°24'W)* is a prominent, high, double-headed bluff with another steep rock face rising behind; the cape is backed by hills reaching 457 m.

## East side of Foxe Channel

30 **Lloyd Point** *(64°26'N, 78°02'W)*, 30 m high, is the SW end of Foxe Peninsula. The point is the end of the largest of a series of rocky ridges with an east-west axis. A short distance inland this ridge rises to 91 m.

31 **Caution**. — This coast is usually **ice-bound** until mid July. Pieces of **ice** detached from the Foxe Basin ice pack after break-up and driven onto the shores of Foxe Peninsula pose a regular **danger to navigation**.

32 The **tidal range** at Schooner Harbour is almost 7.3 m; it is believed to increase to northward.

33 **Caution**. — Observations in 1955 showed **tidal streams** of 5 knots running north and south off Foxe Peninsula; strong **eddies** and **tide rips** have been reported.

34 The west coast of Foxe Peninsula between Lloyd Point and Cape Dorchester, 63 miles NNE, is composed of low Precambrian rock rising to 152 to 244 m 10 to 20 miles inland. Elevations are least towards the north end of the peninsula.

35 **Caution**. — Many islets, **rocks** and **shoal patches** lie near this coast and very **irregular depths** have been reported offshore.

36 The coastal hills have an elevation of 61 m between Lloyd Point and Cape Queen, while 15 miles east the Kingnait Range *(described in Chapter 3)* rises to over 396 m.

37 **Trinity Islands**, in the approaches to **Lonebutte Bay**, are bare, dark-coloured rock; the NE and highest of the group rises 15 m.

38 **Caution**. — There are **drying rocks** in the vicinity of Trinity Islands.

39 **Caution**. — A **tidal stream** of 3 to 4 knots has been recorded and strong **eddies** and **tide rips** have been reported inshore of these islands.

40 **Enukso Point** and **Green Point** are 9 and 14 miles north of Lloyd Point.

41 **Cape Queen** *(64°42'N, 78°18'W)*, a steep, **conspicuous bluff** 46 m high, is the termination of an inland east-west ridge.

42 **Caution**. — The small coves between **Harkin Bay** and Cape Enauolik are filled with **drying flats** and it is reported that the water is very **shoal** for several miles offshore along this stretch.

43 **Cape Enauolik** is a granite cape 61 m high and slightly higher than its surroundings; the cape rises 2 miles inland to 122 m.

44 **Caution**. — In 1955, *HMCS Labrador*, draught 8.1 m, had to lie 8 miles off this cape because of **shoal water**; she had 7.6 m under her keel at one time and encountered many **pinnacles**.

45 North of Cape Enauolik, the granite hills recede inland; a low, swampy plain backs the shore with occasional granite hummocks 12 to 18 m high. At **Nuwata**, this wetland plain extends inland for 6 miles. The area is a breeding place for several species of water fowl and small wading birds.

46 **Wildbird Islands** *(65°01'N, 78°03'W)*, low and rocky, are north of the mouth of the **Dunne River**.

47 **Caution**. — There are **shoal patches** near the Wildbird Islands and a number of **shoals** lie from 2 to 5 miles off the coast between these islands and Nuwata.

48 The beach in the area of **Finnie Bay** consists of sand, gravel and silt interspersed with rock outcrops. North of Finnie Bay, the coast is low and rocky with elevations of 23 to 46 m.

49 **Weston Escarpment**, elevation 152 m, is an extension of the Kimmik Range. The range crosses Foxe Peninsula in a NW direction from Hudson Strait.

50 **Cape Weston** *(65°22'N, 77°29'W)*, with swampy meadows, ponds, streams and rocky hummocks, is low and inconspicuous at its outer end.

51 **Caution**. — Numerous islets lie off the cape and **shoal water** has been reported up to 4 miles offshore.

52 **Nabukjuak Bay** has extensive **tidal flats** towards its head. A number of streams, fed from **McNabb Lake**, drain into the bay through a boggy delta.

53 **Cape Dorchester** is composed of low, broken, barren hills 30 m high.

54 **Caution**. — A long chain of **rocks** and **shoals** 3 miles NNE of the cape projects into Foxe Channel. There are numerous **tide rips** in this vicinity, extending out to a distance of 25 miles.

# Frozen Strait

*Charts 7404, 7405*

55 **Frozen Strait** joins Foxe Channel to the north end of Roes Welcome Sound and Repulse Bay.

56 **Caution**. — The available **soundings** show the strait to be full of **peaks** and **pinnacles**. This is consistent with a report from *HMCS Labrador* in 1955.

57 **Shoal patches** of 13 and 8 fathoms (23.8 and 14.6 m) are 3 miles east and 5 miles NE of Passage Island, at the NW end of the strait.

58 The **tidal range** at Cape Welsford *(65°29'N, 84°32'W)* is reported to be from 14 to 18 feet (4.3 to 5.5 m); Vansittart Island, 9.5 feet (2.9 m).

59 **Caution**. — The **tidal stream** is reported to be 3 knots, running parallel to the shores. *HMCS Labrador* experienced a westerly set with a rate of 3.6 knots north of Cape Frigid *(66°05'N, 85°04'W)* in September, 1955.

*Chart 7404*

## SW side of Frozen Strait and approaches

60 Between Cape Comfort *(65°08'N, 83°24'W) (previously described)* and Cape Bylot, 21 miles NW, the coast is rocky with cliffs rising to an elevation of 1,000 feet (305 m). The water appears to be deep until very close to the shore.

61 **Smyth Harbour**, protected by a rocky point on the north side, is steep-walled and appears to be deep. The inlet 5 miles west of Smyth Harbour has a low coastline on its south side but on the promontory forming its north side the hills fall to the water in sheer cliffs 600 feet (183 m) high. The mouth of **Canyon River**, at a small inlet 4 miles farther west, affords shelter for small craft.

62 **Cape Bylot** *(65°20'N, 84°08'W)* is a high, rounded mass of grooved rock strata connected to the shore by a low ridge.

63 Between Cape Bylot and Cape Welsford, the coast is mostly steep and rocky with heights of 500 feet (152 m), but the occasional raised beach breaks the continuity of the hills.

64 **Caution**. — There is **shoal water** near the heads of the two inlets 6 and 8 miles NW of Cape Bylot.

65 **Cape Welsford** is rocky but less steep than the coast to the SW; it has an elevation of 500 feet (152 m).

*Chart 7405*

## Duke of York Bay

66 **Duke of York Bay** *(65°26'N, 84°49'W)* was discovered, examined and named by Parry, in *Fury*, in August 1821.

67 **Soundings** in Falcon Strait and Duke of York Bay are mostly from a controlled survey in 1962; only part of the bay was surveyed.

68 **Caution**. — A **drying patch** of 2 feet (0.6 m) and a **drying patch** of 6 feet (1.8 m), limestone **rocks**, are 2.5 and 8 miles north of the head of the bay.

69 **Falcon Strait** is obstructed by **Nias Island**, rocky with cliffs; by a group of five rocky islets of varying heights; and by **Black Rock**, which dries 8 feet (2.4 m). Black Rock may be passed on either side at a distance of 0.3 mile. Nias Island rises to 480 feet (146 m) and has a deep north-south valley in the centre.

70 The **tidal stream** through Falcon Strait has a rate of 1.5 knots; the outgoing stream continues for 1¾ hours after low water at Cape Welsford.

71 The east coast of Duke of York Bay is high and steep for 10 miles SSW of Cape Welsford and then becomes a strip of low and light-coloured land, 1 or 2 miles wide, backed by hills rising 800 to 900 feet (244 to 274 m).

72 **Cleveland River** *(65°12'N, 84°48'W)* empties at the head of the bay. The land here is low and marshy; there is a broad **tidal flat**.

73 The land on the west side of the bay rises gradually from the beach to an elevation of 60 to 70 feet (18 to 21 m). **Thomsen River** discharges into the bay through low and marshy shores. **Point Henderson** is low.

## Comer Strait

74 **Comer Strait** *(65°47'N, 85°10'W)*, **not sounded**, runs NNW from the north end of Duke of York Bay.

75 **Caution**. — **Shoals** and islets are scattered in the strait, especially in its south approaches.

76 **Caution**. — The **tidal stream** sweeps through the strait with violence and irregularity, attaining a rate of 5 or 6 knots; it sets south on the ebb. In winter there are always current holes in the ice.

77 The shore on the west side of Comer Strait between Point Henderson and Cape Munn *(65°54'N, 85°31'W)* is low and bordered by **shallow water**. The large bay west of the north entrance to the strait is almost filled with **tidal flats**; its shores are mostly low marshland with limestone flats and ridges.

78 The west coast of **White Island**, from the south end to the north end of Comer Strait, has raised beaches with rocky broken land sloping up to 500 feet (152 m). North of Comer Strait the coast rises quickly from a narrow foreshore to rocky hills with elevations of 700 to 800 feet (213 to 244 m).

*Charts 7404, 7405*

## West side of Frozen Strait

79 **Cape Deas** *(65°33'N, 84°38'W)*, the SE end of White Island, rises to a height of over 500 feet (152 m). The east side of White Island is rocky and steep-to in places with elevations of up to 1,200 feet (366 m) in its southern one-third, and averaging 500 feet (152 m) over its northern two-thirds. **Seekoo Island** is 300 feet (91 m) high.

80 The outer of the two large islands, 7 miles NNW of **Toms Harbour**, has an elevation of 200 feet (61 m); the inner, 300 feet (91 m).

81 **Caution**. — **Shoal water** is apparent near some of the islands that shelter **Whale Sound**; the largest of the islands has an elevation of over 600 feet (183 m).

82 **Passage Island** *(66°01'N, 84°46'W)* has an elevation of over 200 feet (61 m). Shoals *(previously mentioned)* with depths of 13 and 8 fathoms (23.8 and 14.6 m) lie 3 miles east and 5 miles NE of Passage Island.

83 **Cape Frigid** is on the north end of an island, elevation over 300 feet (91 m), north of White Island.

### East side of Frozen Strait

84 **Sanderson Island** and **Mooneshine Island** *(65°32'N, 83°12'W)* lie on the east side of the south entrance to Frozen Strait.

85 **Vansittart Island** is almost divided into two parts; **Petersen Bay** *(65°43'N, 83°51'W)* and **Sokongen Bay** are separated only by a low, flat neck of land. In September 1821, *Fury*, with a draught of about 13.8 feet (4.2 m), passed between Vansittart Island and the rocky islet that lies 3 miles NNW of Sanderson Island.

86 The SE half of Vansittart Island is high and steep with elevations of 700 feet (213 m); **Cape Baffin** falls to the sea in a series of terraces. **Opposite Island** and **Danish Island**, in Sokongen Bay, have elevations of 500 feet (152 m). The inlets on the south side of the SE part of Vansittart Island are apparently shallow towards their heads.

87 **Historical note**. — The headquarters of the Fifth Thule Expedition in 1921-24 was on Danish Island.

88 **Sun Island**, 300 feet (91 m) high, has steep sides and a flat top.

89 **Ivaluarjuk Island** has an elevation of 20 feet (6.1 m). There are indications of a **shoal** 3 miles east of this island.

90 **Cape Shackleton** *(66°08'N, 84°27'W)*, the NW end of Vansittart Island, is a steep headland 300 feet (91 m) high. **Bushnan Island** has an elevation of 400 feet (122 m). **Garnet Island** and **October Island**, with elevations of 100 and 200 feet (30 and 61 m), lie in the SE approaches to **Palmated Bay**. **Bluhme Island**, elevation 100 feet (30 m), lies 2 miles ESE of **Cape Clarke**.

91 **Caution**. — Follow the sounded tracks, if possible, as there is less likelihood of encountering **uncharted dangers** on or near these tracks than elsewhere in the strait.

### Hurd Channel

92 **Hurd Channel**, surveyed by Parry's expedition in 1821, separates the coast of Melville Peninsula to the north from Vansittart and Bushnan Islands to the south. Parry passed through Hurd Channel from west to east.

93 **Georgina Island**, NE of **Cheyne Point** *(66°09'N, 84°21'W)*, is 200 feet (61 m) high. **Cape Montagu** is a steep point 100 feet (30 m) high. The north side of Hurd Channel is mostly steep and rocky; the greatest elevation is at **Brooks Bluff**.

94 **Bear Islands**, 200 feet (61 m) high, are connected by **drying rocky ledges**. The islet midway between Bear Islands and **Duckett Cove** is surrounded by a **rocky shoal**.

95 Parry's ships found **anchorage** 0.5 mile from the head of Duckett Cove in 12 to 15 fathoms (21.9 to 27.4 m) with a bottom of stiff mud. He described the anchorage as affording perfect shelter with little tidal stream. He reported that the only ice to enter the cove is that brought in by a SE wind, but this comes in with little force and is not likely to cause damage to a ship.

96 **Caution**. — Parry found a **shoal** depth of 2¾ fathoms (4.9 m) off the SW entrance point to Duckett Cove and depths of 13 to 25 fathoms (23.8 to 46 m) 0.3 mile NE of Bushnan Island. A **rocky shoal** with depths of 12 to 17 feet (3.7 to 5.2 m) lies 1 mile SE of the SE end of Georgina Island. This is the extent of positive information on depths in Hurd Channel.

97 Parry reported that, with a rising tide, the **tidal stream** runs west and NW through Hurd Channel and SW through the channel between Cape Shackleton and Bushnan Island; on the ebb the directions are reversed.

98 **Caution**. — Near Bushnan Island, the **tidal stream** attains a rate of 4 knots, while in the narrows near the east end of Hurd Channel it reaches 6 knots.

99 **Historical note**. — Parry's route from westward was north of Bushnan Island to Duckett Cove, where his ships anchored. From the cove, the vessels passed west of the islet midway between the cove and Bear Islands, then NE of Bear Islands and east, in mid-channel, between Cape Montagu and Cape Shackleton.

## SE coast of Melville Peninsula

*Chart 7404*

### Gore Bay and Moyle Bay

100 **Sturges Bourne (Sturges) Islands** *(66°03'N, 83°36'W)*, NE of Vansittart Island, form the east side of the approaches to Gore and Moyle Bays. Sturges Bourne Islands are of low to moderate elevation with rugged and steep areas; the most southerly rises to 180 feet (55 m).

101 **Caution**. — Little is known about the **depths** in the channel between Sturgess Bourne Islands and Vansittart Island. According to Parry's chart, they appear to be very irregular with over 100 fathoms (183 m) in some

places and as little as 8 fathoms (14.6 m), 4 miles SW of Cape McLaren.

102 **Cape McLaren** is 100 feet (30 m) high. **Farhill Point**, between Gore Bay and Moyle Bay, has an elevation of 200 feet (61 m).

103 The SW coast of **Gore Bay** is steep. At the head of the bay there is a strip of low land between the shore and the hills. The east coast is low and uniform.

*Charts 7404, 7000*

## Lyon and Hoppner Inlets

104 **Lyon Inlet** has a total length of 65 miles; it leads NNW for 53 miles then SW for 12 miles to its head. *(Only the wide southern portion is covered by a large-scale chart.)*

105 **Cape Martineau** *(66°10'N, 83°40'W)*, near the SW entrance point to Lyon Inlet, has an elevation of 400 feet (122 m). **Cape Edwards**, the SE entrance point, is rocky and low.

106 **Cape Reid** *(66°41'N, 84°06'W)* is on the west side of Lyon Inlet, 31 miles inside the entrance.

107 **Hoppner Inlet** branches from the east side of Lyon Inlet opposite Cape Reid. Hoppner Inlet has a length of 15 miles and an average width of 1 mile. It is surrounded by high land that rises near the head of the inlet to between 800 and 900 feet (244 and 274 m). **Red Point**, named for the bright colour of the rocks, lies 5.5 miles within the entrance of Hoppner Inlet on the east side.

108 **Caution**. — Depths in the upper part of Hoppner Inlet are irregular and there are numerous **shoals**. The deepest water is towards the steep east shore.

109 Lyon Inlet, now narrow, trends west for 5 miles from Cape Reid, then NNE for 4 miles, where the channel is encumbered by an islet. There is a deep passage, 0.5 mile wide, west of the islet; the water is shallow on the east side. North of this passage the main inlet widens out in places but is filled with islets and **shoals**. **Culgruff Inlet** and **Sherer Inlet** indent the shores of Lyon Inlet on its west side; **Norman Inlet** and other smaller unnamed bays are on the east side. **Ross Bay** forms the last 5 miles of Lyon Inlet.

110 **Caution**. — **Tidal streams** attain 6 knots in the narrow channel in Lyon Inlet.

111 The shores around Lyon Inlet are hilly, rising steeply from the water in places. In other places there are strips of low, grassy land at the foot of the hills. **Allison Bluff**, on the west side of the inlet 18 miles within the entrance, is a remarkable bluff over 600 feet (183 m) high.

112 **Caution**. — **Bay of Shoals** *(66°31'N, 83°43'W)* is full of **dangerous rocks** and **shoals**. Most are submerged at high water.

113 Parry's vessels obtained **anchorage** in **Safety Cove** *(66°31'N, 83°38'W)* in 13 fathoms (23.8 m), mud, where they were sheltered from an ENE gale; however, with an onshore wind there would be little shelter from weather or ice.

114 Parry also found **anchorage** in **Five-Hawser Bay**, a passage between the mainland and a group of islands close off the eastern shore 20 miles NNW of Cape Edwards. The vessels anchored close to the shore in depths of 17 to 19 fathoms (31 to 35 m) with their sterns secured by hawsers to the rocks.

115 **Anchorage** was also obtained abreast the mouth of Hoppner Inlet, the most northerly position in Lyon Inlet reached by *Fury* and *Hecla*.

116 In the middle of Lyon Inlet, there is 100 to 200 fathoms (183 to 366 m) nearly as far up as Five-Hawser Bay.

*Chart 7404*

## Winter Island to Cape Wilson

117 **Winter Island** *(66°15'N, 83°07'W)* is low and brown, when free of snow, with a smooth outline. The island is very low at its NW end towards **Point Belford** and its greatest elevation is 225 feet (69 m). **Cape Fisher** is 76 feet (23 m) high.

118 **Crawford Island**, 60 feet (18 m) high at the north end, is separated from Winter Island by a channel with a depth, reported by Parry, of 16 fathoms (29.3 m).

119 Parry reported depths off the SE side of Winter Island to be deep and regular near the shore, but he saw a **reef** indicated by the breakers east of the east end of the island. Air photographs indicate that the bays in the coast of Winter Island are shallow towards their heads and there are extensive shallows off **Bird Islands** *(66°22'N, 83°12'W)*. **Hoppner Strait** is also shallow.

120 *Fury* and *Hecla* found **anchorage** for the winter in the bay west of Cape Fisher; they moored in 6 fathoms (11 m), secured by hawsers to grounded ice and by cables to anchors on the beach.

121 **High water**, **spring tide** *(spring rise)* in the bay west of Cape Fisher is 14 feet (4.3 m); **neap rise** is 11 feet (3.4 m). High water occurs 20 minutes before high water at Resolute.

122 **Turton Island**, 8 miles NE of Hoppner Strait, is low, light-coloured and surrounded by **shallow water**.

123 The coast between Hoppner Strait and Adderley Bluff is low with **drying flats**; these flats are extensive in **Blake Bay**. **Adderley Bluff** *(66°36'N, 82°31'W)* is a steep gneiss cliff with three steps; the lower one drops straight down to the beach. The height of the bluff is over 500 feet (152 m); this elevation continues northward for 6 miles. The bluff is prominent on this otherwise low coast.

*Charts 7482, 7066*

124 Parry considered that a small, unnamed cove 6 miles NNE of Adderley Bluff would afford a safe

**anchorage**. A small rocky islet, 0.5 mile off the coast, guards the entrance.

125 **Caution**. — There are a number of **drying shoals** in the vicinity of the islet.

126 **Palmer Bay** is filled with extensive **drying flats**. **Aua River** discharges into the bay.

127 **Point Elizabeth** *(66°42'N, 82°07'W)*, 30 m high, is difficult to pick out without radar assistance when approaching from the south. When abreast or north of the point it appears as a low, distinct projection against a background of dark hills. The southern tip of the point has a clear patch with a reddish tinge. A small islet surrounded by a **drying flat** lies close off its eastern side. The land around Point Elizabeth is a low plain of sedimentary rock with outcrops of low gneiss ridges.

128 **Caution**. — The **tidal stream** off Point Elizabeth is reported to run at 3 knots parallel to the coast.

129 The coast of Melville Peninsula, between Point Elizabeth and **Cape Wilson** *(67°00'N, 81°28'W)*, is low and rocky and covered with limestone gravel. The largest islet off **Freuchen Bay** is 15 m high.

130 Cape Wilson is relatively low. A 122-m ridge north of the cape and the terrain inland form a plateau of nearly uniform elevation. Close west of the cape there are two parallel bluffs running NW-SE with their perpendicular faces towards the SW.

131 There is a **beacon** on Cape Wilson consisting of a skeleton **tower** 12.2 m high fitted with a fluorescent-orange rectangular **daymark** and a **radar reflector**.

132 **Owlitteeweek Island** is 30 m high in the north end but lower towards the south.

133 **Caution**. — There is **shoal water** close off the SE side of Owlitteeweek Island. From the air photograph evidence of heavy masses of grounded ice, **shallow water** may extend south and SW as well.

134 **Caution**. — A 9-m **shoal**, position approximate, was reported in 1955 to lie 6.5 miles SSE of Cape Wilson; a 22-m **shoal patch** lies 2 miles farther south.

135 The **tidal stream** in the Cape Wilson area is rectilinear and parallels the coast although there is a net southerly drift. Observations in August 1955 showed rates of 2.8 knots in a SW direction and 1 knot in a NE direction.

## Roes Welcome Sound

*Charts 5533, 7065*

136 **Roes Welcome Sound** separates Southampton Island from the mainland to the west and runs from Hudson Bay 160 miles NNE to Repulse Bay. **Ne Ultra Strait** is the south part of the sound. *(The south part of Southampton Island is described in Chapter 6.)*

137 **Caution**. — The **depths** through Roes Welcome Sound are mostly from track soundings.

138 **Caution**. — The strong **tidal streams** in Roes Welcome Sound tend to keep the ice in motion throughout most of the year; even in winter, there is usually some open water near the middle of the sound. It is reported that the tidal undulations from north and south meet opposite Wager Bay. Thus, with a rising tide, a north-flowing tidal stream will be found in the southern part of the sound and a south-flowing stream in the northern part. With a falling tide, the directions will be reversed.

*Chart 5533*

### East side of Roes Welcome Sound

139 Cape Kendall *(63°36'N, 87°13'W) (described in Chapter 6)*, although low, is somewhat higher than the adjacent coast; it is the SE entrance point to Roes Welcome Sound. **Drying flats** extend from 1 to 3 miles off the cape; landing is difficult and can be made only at high water.

140 The west coast of **Southampton Island** is low, with no distinguishing landmarks between Cape Kendall and Cape Munn, 145 miles NNE. The land behind the shoreline rises in a succession of ridges, each a few feet higher than the one immediately in front. Very little plant life grows on the ridges, but there is typical tundra vegetation in the wide depressions between the ridges on wet ground surrounding many lakes and ponds.

141 **Caution**. — **Shoal water** extends 2 or 3 miles from the land, and in some places as much as 8 miles; **reefs** of limestone lie much farther out. There is no shelter on this coast except to a very limited extent, for small craft, in one or two bays and river entrances. **Shallow water** extends for many miles off **Ell Bay**.

142 Bluffs 6 feet (1.8 m) high form the coastline for some miles north of **Anchor Cove** *(64°15'N, 86°17'W)*. These bluffs increase moderately in height northward and develop into cliffs and terraces interspersed with ridges. **Tidal flats** appear, from air photographs, to extend from 0.5 to 2 miles offshore; **shallow water** probably extends much farther out.

143 **Murray River** enters the sea 41 miles north of Anchor Cove.

144 **Battery Bay** offers fair shelter for small craft, from north and NW winds, off its north point in 10 feet (3 m). The bay is otherwise exposed. At the south point of Battery Bay there is a small, prominent limestone bluff; the main ridge is higher than farther north.

145 Between Battery Bay and **Cape Munn**, the north end of Southampton Island, the coast consists of raised beaches with occasional outcrops of limestone. Inland, the land rises

to over 100 feet (30 m) with a very gentle even slope. The beaches are shingle with scattered boulders.

146 At Cape Munn, the coast is low and numerous beach lines are evident.

147 **Caution**. — The tidal flats do not appear, from air photographs, to extend far from the shoreline but there are many small **spits** and there are **shoals** offshore; these are marked by **tide rips**.

## SW side of Roes Welcome Sound

148 Cape Fullerton *(63°58'N, 88°47'W) (described in Chapter 6)* is the SW entrance point to Roes Welcome Sound.

149 **Caution**. — A **shoal** is reported to extend 10 miles SE from Cape Fullerton; several **dangerous rocks** lie within a few miles of the SE end of the shoal.

150 The west coast of Roes Welcome Sound is low and mostly bordered by islets, **rocks** and **shoal water**. It is composed almost entirely of solid rock, often in the form of knoblike hills which, near the shoreline, seldom rise to more than 20 to 40 feet (6 to 12 m). Similar but somewhat higher hills farther inland are visible from seaward.

151 The coast consists of barren, rugged, red and grey granite rocks between Cape Fullerton and Whale Point; there are extensive **tidal flats**.

152 Rae, in 1846, reported finding a good harbour in an inlet 14 miles NE of Cape Fullerton in 64°05'N. The harbour, 0.1 mile wide and nearly 4 miles long, has depths of 4 to 6 fathoms (7.3 to 11 m) over a bottom of sand and mud. **Borden River** *(not named on the charts)*, with a succession of rapids and deep pools, empties into this inlet. The shores in the vicinity have a very rugged appearance, with many ridges of ancient rock running far out into the sea in an east-west direction.

153 Rae reported the **tidal range** here as being 13.5 feet (4.1 m).

154 **Whale Point** *(64°12'N, 88°02'W)*, although not high, rises somewhat above the near-by coast. It was used as a lookout station in the days when whaling flourished. A **bank** with a depth of 9 fathoms (16.5 m) is reported to lie 6 miles ESE of Whale Point.

155 **Mistake Creek** *(64°14'N, 88°02'W)* enters the sea close north of Whale Point. The area around the creek is composed of low rock ridges, 15 to 100 feet (5 to 30 m) high, covered with shattered boulders. The highest point in the immediate vicinity is a hill, 130 feet (40 m) high, almost vertical on the side facing the sea. The ridges reach elevations of 90 to 100 feet (27 to 30 m) 3 to 4 miles from the sea. A group of hills 500 feet (152 m) high can be seen 10 miles farther inland. The water offshore is shallow.

156 **Yellow Bluff** *(64°22'N, 87°50'W)* is a small promontory 9 miles NNE of Mistake Creek. The name comes from the colour of the rock here. This sector of the coast is higher, rising from 100 to 200 feet (30 to 61 m).

157 **Caution**. — From Yellow Bluff to Kamarvik Harbour, 21 miles NNE, the coast is low and there are **reefs** with depths of less than 6 feet (1.8 m) as far as 3 miles offshore.

158 **Iterdlak Bay** *(not named on the chart)* is the wide bay 7 miles NNE of Yellow Bluff; the **Gordon River** discharges into the head of the bay.

*Charts 5533, 7065*

159 **Kamarvik Harbour** *(64°41'N, 87°29'W)* affords shelter for small craft. It is possible to carry a draught of 7 feet (2.1 m) at any state of the tide by keeping to the eastern side of the channel into the harbour. The channel, not surveyed, is thought to have a depth of not less than 2 fathoms (3.7 m). The inner harbour is spacious for small craft, with depths of over 50 feet (15.2 m). **Kamarvik Creek** empties into the head of the harbour.

160 Between Kamarvik Harbour and Cape Dobbs, the coast consists mostly of bare rocky hills. These are less than 30 to 40 feet (9 to 12 m) high as far as **Nuvuk Point**, and are seldom more than 50 feet (15 m) high from Nuvuk Point to **Cape Dobbs**.

161 **Caution**. — The shore is bordered with islets and **shoal water**, and there are **tidal flats** scattered with **boulders** in the bays.

*Chart 5440*

## Wager Bay

162 **Wager Bay** extends 90 miles from Roes Welcome Sound to the reversing falls at Ford Lake. The mouth of Wager Bay between Cape Dobbs and **Handkerchief Point** *(65°17'N, 88°00'W)* is known as **Wager Bay Narrows**.

163 **Caution**. — The information on **depths** in Wager Bay is from track soundings.

164 It is reported that there is deep water close to the shore along almost the whole of the SW side of the bay.

165 **Caution**. — **Tidal streams** run with great strength in Wager Bay Narrows. The rates reach 6 to 7 knots, according to some reports; the water continues to flow out of the bay for some time after low water on the open coast. There are many **whirlpools** and **eddies**; the Inuit claim these are predominant towards the south side of the channel where the tidal streams are at their strongest. A weaker stream, said to be 4 knots or less, is found towards the north side. Several reports indicate that, owing to the strength of these streams, the narrows are seldom frozen over; however, the great quantities of **ice** in motion are a serious **danger** to ships. In the middle of December, open water was found for 40 miles within the entrance. The Inuit stated that

this was the normal condition due to the strength of the tidal streams.

166 **Handkerchief Inlet** affords good protection and is a useful temporary **anchorage** for small craft waiting for the tide to turn. The shores of the inlet are boulder beach and there is deep water to within 46 m of its head.

167 **Savage Islands** *(65°27'N, 88°25'W)*, with **Nuvudlik Island** at the SE end, are all 30 m high and are almost entirely bare rock. **Paliak Islands** have a maximum height of 61 m.

168 **Caution**. — Savage Islands should be given a wide berth because **soundings** to the south, SW and west indicate a very irregular bottom with several **dangerous shoals**.

169 **Tikilak Point** *(65°39'N, 88°50'W)* is the SE entrance point to **Douglas Harbour**.

170 **Mackay Bluff** rises abruptly from the water to heights of 214 to 244 m.

171 Douglas Harbour provides **anchorage**, with good holding ground of rock and gravel, with some protection just inside the harbour entrance on the south side. A very rocky beach surrounds the harbour. Small craft can reach the mouth of the **Piksimanik River**, at the head of the harbour, approaching up the centre or favouring the south shore.

172 **Tidal range** at Douglas Harbour is 4.9 m.

173 **Caution**. — A 3.7-m **shoal**, position approximate, lies 4 miles SSE of Tikilak Point. A **shoal rock**, position approximate, lies 3 miles west of the same point. It is reported that there are **uncharted drying areas** in Douglas Harbour and its entrance.

174 **Aiqqujat (Abruyuk) Islands** *(65°46'N, 89°15'W)* are mostly bare rock 30 m high. The two arms at the head of **Bennett Bay** are **shallow**; the peninsula between them has conical hills 213 m in elevation.

175 The channel through **Reversing Falls** into **Ford Lake** is 46 m wide. The channel broadens at high tide; passage should be made at slack water.

176 The small inlet 3 miles from the west end of Ford Lake was formerly the site of a *Hudson's Bay Company* post. Small craft can obtain **anchorage** with good holding near the post.

177 **Tidal range** in Ford Lake is reported to be 0.5 to 0.9 m. The **tide** flows northward into Ford Lake for 4 hours followed by slightly less than 1 hour of slack water and then 6 hours of rather faster outflow.

178 In 2003, Wager Bay and the surrounding area became **Ukkusiksalik National Park of Canada**.

## NW side of Roes Welcome Sound

179 **Cape Montague** *(65°19'N, 87°21'W)* is on the north side of the mouth of Wager Bay. **Berthie Harbour** was the site of a *Hudson's Bay Company* post. A short distance west of the harbour there is a hill shaped like a flat-topped cone.

*Chart 7405*

180 The coast between Cape Montague and Beach Point *(66°12'N, 85°52'W)* is low with a few modest hills interspersed with lakes and large alluvial plains.

181 **Caution**. — Islets, **rocks** and **shoals** extend from 1 to 4 miles offshore, especially in the SW part. The whole of this stretch is **dangerous** to approach.

182 **Bury Cove** is backed by a steep ridge, 175 feet (53 m) high, parallel to the coast.

183 Bury Cove offers **anchorage** for small craft although it is exposed at high tide.

184 **Caution**. — Special care is required when approaching this anchorage because of the many **reefs**.

185 The coast does not exceed 150 feet (46 m) high from Bury Cove to the mouth of **Snowbank River** *(65°54'N, 86°23'W)*. There is a steep slope 100 feet (30 m) high on the NE side of the river mouth. Small craft can, with great care, enter the mouth of this river.

186 **Panalik Point** is reported to be low but prominent.

## Repulse Bay

187 **Repulse Bay**, discovered by Middleton in 1742, can be approached either by Roes Welcome Sound or by Frozen Strait. The bay is surrounded by hills; the highest land is on its SW side. **Beach Point**, at the west entrance, is low and the hills in its vicinity are less than 150 feet (46 m) in height.

188 Ice conditions vary greatly from year to year but generally, ice conditions are very good during supply operations. The period of navigation in Repulse Bay is from early August to late September, but with SE winds ice may be blown back to block the bay almost anytime during the summer.

189 **Caution**. — The **depths** through most of Repulse Bay are from track soundings. **Soundings** in Talun Bay and approaches are from a reconnaissance survey in 1955.

190 **Cape Hope** *(66°14'N, 86°04'W)*, on the SW side of Repulse Bay, is a bluff 300 feet (91 m) high. There is reported to be deep water close to shore at Cape Hope. The peninsula SW of **Gibson Cove**, at the west end of Repulse Bay, has an elevation of 300 feet (91 m). The mouth of the **North Pole River** is the site of **Fort Hope**, used as winter quarters by Dr. John Rae in 1846-47 and 1853-54.

191 Cape Clarke *(66°15'N, 85°10'W)* is the east entrance point of Repulse Bay. **Cleveland Harbour**, on the west side of the cape, appears to be quite **shallow**. **Hall Islands** are low. The east side of **Haviland Bay** has cliffs and steep slopes rising to 600 feet (183 m); the NW side of the bay is somewhat lower. From the head of Haviland Bay, an overland crossing leads to Ross Bay at the head of Lyon Inlet.

*Chart 7430*

192 **Harbour Islands**, elevation 100 feet (30 m), do not show up visually until after the mainland has been sighted.

193 **Anchorage** with ample room for a small vessel to swing in 6 fathoms (11 m) can be found in a very well sheltered harbour, with over 9 fathoms (16.5 m) in the middle, south of the NE island of the Harbour Islands. This harbour may be approached from the east by following a channel that runs south of the NE island; the minimum depth is 22 feet (6.7 m).

## Talun Bay

194 **Talun Bay** is entered between **Walrus Island** *(66°30'N, 86°15'W)* and an unnamed point 2 miles to the west. **Aivilik Point** lies 1 mile farther west.

195 Talun Bay is noted for the persistence of strong **winds** during the summer. Night **fog** is said to be frequent during the first part of July but apart from this there appears to be little fog in summer.

196 Private red **tripod beacons**, 18 feet (5.5 m) high, are on the west entrance point of Talun Bay, on Walrus Island and on an islet close north of Walrus Island. These beacons are **no longer charted**, **no longer maintained** and the **condition** of these beacons is **unknown** *(2013)*.

197 **Caution**. — The **anchorage** between Walrus Island and the west entrance point of Talun Bay is extremely **exposed**.

198 Supply vessels can find **anchorage** in Talun Bay from 0.6 to 0.8 mile west of **Netchik Point** in 10 fathoms (18.3 m). The bottom is gravel and rock and the holding is fair. A deep-water channel runs from Repulse Bay to the anchorage.

199 **Caution**. — This anchorage is very **exposed**; the bay becomes rough in winds from any direction but particularly in a southerly wind of more than 18 knots.

200 There is good **anchorage** for vessels less than 150 feet (46 m) in length, over gravel and mud, between Netchik Point and the NE shore in the inner harbour. This anchorage is fairly well sheltered by land on three sides but swinging room is restricted; a kedge anchor should be used to hold the stern.

201 **Caution**. — There are a number of **shoal areas** in Talun Bay, between Repulse Bay and the inner harbour, with depths of 10 to 12 feet (3 to 3.7 m). The bottom in Talun Bay is uneven.

202 **Caution**. — Vessels with a **draught** of more than 10 feet (3 m) should not enter the inner harbour without local knowledge.

203 The **tidal range** is from 14 to 22 feet (4.3 to 6.7 m). The **tidal streams** in the outer anchorage and in the inner harbour are negligible.

204 The hamlet of **Repulse Bay**, population 612 *(2001)*, is on the SW end of a peninsula on the east side of Talun Bay. The settlement has a post office, health centre and RCMP detachment. There is a *Northern Store*, a *Co-op* store and an *Inns North* hotel. Both *Calm Air* and *Kivalliq Air* provide flights daily except Saturdays.

205 A privately maintained **aeromarine radiobeacon** *(66°32'N, 86°15'W)* north of the hamlet transmits on 335 kHz with identification YUT (— • — — • • — —)

206 The main **landing beach** is 0.2 mile WNW of the former Roman Catholic Mission. A second beach, known as Hudson's Bay beach, is close north. Hudson's Bay beach was used in the 1976 supply operation. Both beaches have a very gradual gradient from the low water mark and are workable at all stages of the tide. However, **caution** is required during the ebb and at low tide to avoid **rocks** and **boulders**.

207 Dry cargo vessels normally anchor in Talun Bay and their cargo is transferred by barge to a landing beach. Tankers discharge directly through a floating hose from the berth west of Netchik Point.

# Foxe Basin
# Fury and Hecla Strait

## Foxe Basin — General

*Chart 7000*

1 **Foxe Basin** is bounded to the west by **Melville Peninsula** and to the north, east and SE by Baffin Island.

1.1 ***Arctic Canada Vessel Traffic Services Zone (NORDREG CANADA)*** covers all waters described in this chapter. The primary objective of this system is to assist the Master in the safe and expeditious conduct of the vessel by promulgating information on ice conditions, giving advice on routes and providing icebreaker support where available and considered necessary.

1.2 Traffic clearance requests and reports required by this system shall be addressed to *NORDREG CANADA*. Requests and reports may be passed through any *Canadian Coast Guard Marine Communications and Traffic Services (MCTS)* centre free of charge. All times shall be given in *Co-ordinated Universal Time (UTC)*.

1.3 For further information concerning this system consult *Radio Aids to Marine Navigation*, available at: *http://www.ccg-gcc.gc.ca/eng/CCG/MCTS_Radio_Aids*.

2 The coastal topography of Foxe Basin presents two distinct types of relief related to the bedrock of the region. Pre-Cambrian granite forms the coast of Melville Peninsula, southward of Cape Penrhyn; also the north coast of Foxe Peninsula. Palaeozoic sedimentary rocks *(sandstone, dolomite and limestone)* form the coastline of the west side of the basin, from Cape Penrhyn to Fury and Hecla Strait, and of the east side from Bowman Bay to Taverner Bay. The northern shores of Foxe Basin are predominantly granite, except for Baird Peninsula and the large peninsula separating Steensby Inlet from Murry Maxwell Bay; these are sedimentary. The areas of pre-Cambrian origin are characterized by a rugged, barren landscape of moderate elevation, while the coast formed of palaeozoic rocks exhibits a gentle topography with low, poorly drained areas extending many miles inland. In the NE of Foxe Basin there are a number of large islands, some very flat and low, others rising a few hundred feet above sea level.

3 Controlled surveys of limited extent were made between 1955 and 1970 in or near Roche Bay, Hall Beach, Frustration Bay and Longstaff Bluff. In subsequent years, a corridor was surveyed in the northern part of Foxe Basin in the approaches to, and through, Fury and Hecla Strait.

4 **Caution**. — Charted **depths** through much of Foxe Basin are based on reconnaissance surveys and track soundings; mariners are advised to follow sounded tracks if possible.

5 Depths of 37 to 110 m are found in Foxe Basin off the west shore. In the central part of the basin, there are depths of 37 to 46 m.

6 **Caution**. — Based on sparse soundings, the basin is quite **shoal** in the east part. The north section has an irregular bottom with air photo evidence of a number of **dangerous shoals**. Particular caution must be exercised when navigating in this area.

7 Maximum **tidal range** has been estimated as 7.6 m at Cape Dorchester and 9.1 m in Bowman Bay, in the SE part of Foxe Basin along the coast of Foxe Peninsula. The tidal range decreases to the north and west to 1.2 to 1.5 m in the NW corner of the basin.

8 **Caution**. — The **magnetic compass** is erratic throughout the area described in this chapter (see Magnetic Declination chart, Sheet No. 10 of the Geophysical Atlas Series, published by the Geological Survey of Canada).

## West side of Foxe Basin

*Chart 7482*

### Cape Wilson to Hall Beach

9 Between Cape Wilson *(67°00'N, 81°27'W) (described in Chapter 8)* and Cape Penrhyn, 30 miles north, the coast rises to elevations of 30 to 61 m and radar fixes are easy to obtain.

10 **Caution**. — A south-flowing **current** of 2 to 3 knots has been experienced off Cape Penrhyn.

11 **Barrow River** flows through a steep-walled rocky gorge. The land north of the river is very rocky with small rough hills up to 61 m high; to the south there is a narrow piece of lower land 30 m high. The spectacular **Barrow Falls**, falling 31.6 m, is 1.2 miles above the river mouth.

12 An **anchorage** for small craft is inside the Barrow River entrance in 4.9 m. The deepest channel in the approach to the anchorage has a depth of 3 m.

13 A prominent hill, 107 m high with a vertical cliff on part of its face, is 1 mile south of **Cape Penrhyn** *(67°27'N, 81°11'W)* and within 0.5 mile of the shore.

14 The bay immediately north of Cape Penrhyn affords good **anchorage** for small craft.

15 There is a **beacon** consisting of a skeleton **tower** 12.2 m high, fitted with three fluorescent-orange rectangular **daymarks** and a **radar reflector**, on Cape Penrhyn.

16 **Cape Robert Brown** is a prominent headland over 61 m high; 2 miles to the NW there is a cliff of red rock 18 m high.

17 **Cape Jermain**, 9 m high, is at the end of a narrow spit. It is easy to identify on radar.

18 **Caution**. — **Shoal water** extends SE from Cape Jermain for 1 mile.

19 **Anchorage** for small vessels can be found in **McCaig Bay** *(67°46'N, 81°44'W)*.

*Chart 7485*

20 **Amitioke Peninsula**, low and sandy, is the south entrance point of an unnamed bay. **Ignertok Point** *(68°20'N, 82°00'W)* is the north entrance point; it and the land west are low. The inshore areas of the bay are **shallow** and **drying areas** lie in the entrance to its NW arm; inland the terrain rises gradually to hills with elevations of over 305 m.

21 **Roche Bay**, in the NW part of **Parry Bay**, is entered between Ignertok Point and **Qavvialuk Point**, 4 miles to the NNE. Roche Bay has lower shores than the unnamed bay south of Ignertok Point. Depths in the entrance and central part of Roche Bay are between 16.5 and 20.1 m. **Ajaqutalik River** flows into the SW arm of the bay. Roche Bay is the proposed site of an iron ore loading terminal.

22 The **anchorage** in Roche Bay provides only moderate shelter. However, in 1981, M.V. *Polar Circle* obtained excellent holding over a mud and sand bottom and rode out a NW gale.

23 **Ikerasak River** drains **Hall Lake**. **Walrus Island** and **Kite Island** are in the north portion of the lake.

24 **South Ooglit Island** has an elevation of 21 m. A **beacon** with a **radar reflector**, 9 m high, is on a high part of the island. This aid to navigation is **no longer charted**, **no longer maintained** and the **condition** of this aid is **unknown** *(2013)*.

25 **Quarman Point** *(68°31'N, 81°34'W)* has an elevation of 15 m. The bay west of the point has low shores with lines of raised beaches.

26 From Quarman Point to Arlagnuk Point, 41 miles north, the shore is backed by a broad belt of low land; the high land is a considerable distance from the coast.

### Hall Beach

27 **Hall Beach** *(68°46'N, 81°13'W)* is the site of a decommissioned *Distant Early Warning (DEW) Line* radar station, a *North Warning System* radar station, a *North Warning System* logistics support base, a meteorological station and an Inuit community.

28 **Iligliak Point**, 7 miles south of Hall Beach, is low and inconspicuous. **Hall Point** is low; the cove on its west side is **shallow**. Between Hall Point and Nugsanarsuk Point,

the coast is low; there are **shallows** up to 0.5 mile wide off the beaches.

29 Red **tripod beacons**, 5 m high, are 2.5 miles south of Hall Point and on **Kingmitokvik Point**. A similar **beacon**, with a **radar reflector**, is 2 miles SE of **Nugsanarsuk Point**. These three aids to navigation are **no longer charted**, **no longer maintained** and the **condition** of these aids is **unknown** *(2013)*.

31 An aeronautical rotating **light** is near the airstrip. Radio **towers** and radar **domes** and **towers** carry air obstruction **lights**.

32 Radar **domes** south of the airport are **conspicuous**. The radar domes have been sighted at a distance of 30 miles. Two **conspicuous** parabolic **antennas**, 37 m high, are 0.9 mile south of the airport. These features are remnants of the *DEW Line* radar station. The radio **tower**, buildings and oil **tanks** of the *North Warning System* complex also show up well from seaward.

33 A privately maintained **aeromarine radiobeacon** *(68°46'N, 81°15'W)* at Hall Beach transmits on 378 kHz with identification UX (• • — — — • • —) and a privately maintained **aeronautical radiobeacon** *(68°47'N, 81°14'W)* transmits on 117.3 MHz with identification YUX (— • — — • • — — — • • —).

34 Break-up at Hall Beach occurs early in July but Foxe Basin is never completely free of ice. Normal ice drift is south towards Foxe Channel and the pack usually passes 5 miles to the east of Hall Beach. In 1955 and 1956, the ice moved back into the anchorage and landing areas after the final break-up; this was unusual. The recommended period for resupply is the last part of August and the first two weeks of September.

35 **Caution**. — The **tidal stream** 5 miles east of Hall Point reaches maximum rates and directions of 2.9 knots, 350° on the flood, and 3.2 knots, 160° — 170° on the ebb. At the beach the tidal stream runs constantly southward and at a lesser rate than offshore; during strong winds its rate appears to increase. Vessels anchored 0.2 mile off the beach experience little tidal stream.

36 **Caution**. — The predicted times of slack water cannot be relied upon. Vessels maneuvering into position at the landing beach must watch the tide carefully.

37 The **anchorage** area is 1 to 3 miles east of Hall Beach in 21.9 to 31 m. The holding is fair in clay covered by a thin layer of sand, gravel, shells and some boulders.

38 **Caution**. — The anchorage is **open roadstead**, sheltered only to the west. Winds from any other direction can cause very rough conditions and may force vessels to proceed to sea for safety. In September 1976, the resupply vessels were forced to move from Hall Beach and found shelter in the lee of Rowley Island, 45 miles ENE.

39 **Caution**. — There is an uncharted **wreck** off Hall Beach; mariners are advised to remain outside the 20-m contour when approaching the anchorage.

40 A **pier** at Hall Beach, now in **ruins** *(2006)*, is formed of round steel caissons filled with rubble.

41 The **landing beach**, close south of the pier, is composed of small and medium sized gravel; a stretch of 61 m is workable at all stages of the tide.

42 **Caution**. — The shoreline at Hall Beach is low and flat. The water off the beach is **shallow** and the landing beach should be approached with caution. The best approach is close to the south side of the jetty ruins.

43 **Caution**. — Strong easterly winds usually cause **flooding** in the beaching area by 0.6 to 0.9 m of water extending inshore for 0.2 mile. Cargo should be moved off the beach immediately.

44 The Inuit settlement **landing beach**, also composed of small and medium sized gravel, is in the slight bay 1.2 miles south of Kingmitokvik Point. The Inuit beach their boats and canoes here. The water off this beach is too **shallow** for barges; there are sand **bars** 30 m from the shore.

45 General cargo for both the *North Warning System* station and the settlement is landed at the beach. Dry cargo vessels, during good weather, lie 0.25 mile off the beach. There is strong current and rough water farther out which can make it impossible to work cargo.

46 When discharging bulk oil tankers moor 0.25 mile off the landing beach. Oil is discharged to the shore pipeline through two floating hoses.

47 **Caution**. — Vessels anchored off the landing beach should be prepared to move instantly as the **holding** is **unreliable**.

48 The hamlet of **Hall Beach**, population 609 *(2001)*, was established when Inuit came to settle near the *DEW Line* site, built in 1957. The community has a post office, an RCMP detachment and a nursing station. There is a *Northern Stores* outlet, a *Co-op* store and an *Inns North* hotel. *First Air* provides daily flights except Sundays.

*Chart 7486*

## Hall Beach to Hooper Inlet

49 **Pinger Point** *(69°05'N, 81°14'W)*, elevation 14 m, is the north entrance point to **Foster Bay**. The south part of the south arm and the narrow west arm of Foster Bay are **shallow**. Most of the NW shore of the bay is lined by **drying flats**; the coast is formed of lines of raised beaches.

50 **North Ooglit Islands** appear from a distance as three islands; the SE island is divided into two parts by a long, narrow **bar** which may be covered at high water.

51 A **beacon**, fitted with a **radar reflector**, stands 9 m high on the highest part of the SE island. The condition of this beacon is unknown *(2006)*.

52 **Caution**. — A **rock** with a depth of 1.8 m or less, reported in 1979, lies 1 mile NW of the NW island.

53 Between Pinger Point and Arlagnuk Point the coast is low with lines of raised limestone beaches. The water appears, from satellite imagery, to be deep except south off Pinger Point where a **shoal area** discolours the water for 1.5 miles to seaward.

54 **Arlagnuk Point** *(69°12'N, 81°19'W)*, elevation 23 m, is the SE entrance point to Fury and Hecla Strait.

55 **Caution**. — Depths from 5.5 to 9.1 m are reported to extend more than 2.5 miles off Arlagnuk Point.

*Charts 7486, 7487*

## Hooper Inlet

56 **Caution**. — The stretch of coast extending 25 miles NW of Arlagnuk Point is low and bordered by very **shoal water** to a distance of 2.5 miles in places. This coast forms the south shore of **Hooper Inlet**.

57 **Mogg Bay** is very shallow. **Coxe Islands** rise to over 30 m. **Cape Matthew Smith** is at the east end of this group. **Khemig Island** is steep and rugged. The south shore of **Quilliam Bay** is low, seldom exceeding 30 m in elevation, but the north shore is hilly, rising to over 122 m. Many small islands obstruct the entrance to Quilliam Bay. **Crozier River** flows into the head of the bay. The land here is a range of high hills stretching NW that attain elevations of over 305 m.

58 **Caution**. — **Depths** as little as 7.6 m are charted near the sounded track into Hooper Inlet. A **rock** submerged 4.3 m lies 4.1 miles NNE of Arlagnuk Point. **Uncharted rocks** are reported in the passage between Coxe Islands and Igloolik Island.

*Chart 7486*

## Igloolik

59 **Igloolik Island** *(69°23'N, 81°48'W)* is generally low, particularly in its eastern part where lines of raised beaches reach an elevation of 34 m. The island is composed of flat plateaus of sedimentary rock interspersed with bare raised beaches of loose stones.

60 **Caution**. — **Shoal water** borders the whole island except along part of the south coast.

61 **Turton Bay** almost separates the island into two parts.

62 **Caution**. — The bay is divided into inner and outer parts by a **shoal bar** that runs SE from the land close east of the settlement to the SE entrance point of the bay. The bar has a patch that just dries, 1.1 miles SE of the church, and several other very **shoal patches**. **Shoals** with 0.5 and 4.7 m over them are in the inner part of Turton Bay, 1.8 miles ESE and 1.3 miles ENE of the church. **Depths** of 9.7 m lie 0.3 mile off the west side of the outer part of the bay. **Depths** of 9 and 9.1 m, existence doubtful, are 0.5 mile offshore on the NE side of the approach to the bay.

63 Small vessels, able to cross the bar, can obtain very well-sheltered **anchorage** in 18 m in the inner part of Turton Bay.

64 **Anchorage** for larger vessels, in depths of 10 to 20 m, can be obtained 0.5 to 1 mile SSE of the settlement, on the west side of the outer part of Turton Bay. This anchorage is well-sheltered from the north and NW winds which prevail in summer but affords no protection from south or SE winds. The holding ground, of sand, is not good.

65 **Ice** in Turton Bay breaks up in mid July and the bay usually clears by the first week of August. The pack ice drifting south from Fury and Hecla Strait sometimes comes into the bay with southerly winds in August and September. Normally, this ice is driven out with a change of wind. The optimum period for supply is the first week of September. Freeze-up generally occurs in mid October.

66 The **tidal stream** in the outer part of the bay is weak.

67 Oil tankers normally moor in a position 0.6 mile SSE of the church, lying on a heading of ESE, with two anchors and with stern lines to the shore. Bulk oil is delivered direct to the shore through a floating hose.

68 The hamlet of **Igloolik**, population 1,286 *(2001)*, on the NW shore of a small cove in the outer part of Turton Bay, is known as the cultural centre of Nunavut. It is home to the *Igloolik Research Centre*, primarily focused on documenting Inuit knowledge, social and cultural values, practices, beliefs, language and world-view. The community has a post office, a Health Centre with a staff of 4 nurses and an RCMP detachment. There is a *Northern Stores* outlet, a *Co-op* store, a coffee shop and several hotels. *First Air* provides scheduled flights to Iqaluit daily except Sundays; *Air Nunavut* has a charter service at the airport.

69 A disc-shaped, elevated **building** in the settlement, containing Nunavut Department of the Environment laboratories, is **conspicuous**. **Oil tanks** and buildings are prominent.

70 A gravel **landing ramp** has been constructed at the NW corner of the cove at Igloolik. A **breakwater**, projecting from the north shore at the east edge of the settlement, protects the ramp area from easterly winds. Small craft are moored in the vicinity.

71 Two radio **towers**, the highest with an elevation of 60 m, show air obstruction **lights**.

72 A privately maintained **aeromarine radiobeacon** *(69°22'N, 81°49'W)* at Igloolik airport transmits on 241 kHz with identification YGT (— • — — — — • —).

## South and east sides of Foxe Basin

*Chart 7066*

### Foxe Peninsula — North Coast

73 Between Cape Dorchester *(65°27'N, 77°27'W) (described in Chapter 8)* and Bowman Bay, 95 miles to the east, the land is generally low. Inland there are extensive grassy plains with numerous ponds and lakes. Ridges trending SE-NW terminate in low points along the coast.

74 **Caution**. — **Drying flats** extend from 0.5 mile to at least 1 mile from the shore and there are numerous rocky islets and **reefs** farther offshore. The prevalence of **shoals** and the movement of **pack ice** along this shore make it **inaccessible** to large vessels and **dangerous** for small craft.

75 The maximum **tidal range** is estimated to be 25 feet (7.6 m) at Cape Dorchester and 30 feet (9.1 m) at Bowman Bay.

76 **Caution**. — **Tidal streams** flow roughly parallel to the coast and are reported to attain a rate of 6 knots.

77 Expeditions in 1928-1929 found a considerable amount of pack ice along the north coast of Foxe Peninsula in August. The ice, most of it old and dirty, was jammed against the points and shoals by the flood stream; it receded with the ebb and changed position with any change of wind.

78 **Dorchester Bay**, entered east of **Cape Willoughby** *(65°27'N, 77°10'W)*, has **drying shoals** extending seaward for several miles; hundreds of large and small **boulders** are exposed near the shore at low water. The land at the head of the bay is low, marshy grassland.

79 **Peregrine Point** is slightly higher than the surrounding country and terminates in a bluff 30 to 40 feet (9 to 12 m) high.

80 **Caution**. — Although deep water is reported in places nearby, there are **dangerous shoals** off Peregrine Point.

81 The shores of **Gibson Bay** are low and rocky. **Kommanik River** empties into the bay.

82 **Caution**. — **Drying shoals** extend several miles offshore in this area.

83 **Viola Bay** and **Garnet Bay** have **shallow water** extending from their shores.

84 **Cape Ketoria** *(65°26'N, 75°14'W)* is the end of a range of flattened hills and ridges. Hills with elevations of 100 to 200 feet (30 to 61 m) or higher, several miles SE of the cape, are prominent on this otherwise low and featureless coast.

85 **Drying flats** extend a considerable distance off the shores of **Cory Bay**, and as much as 3.5 miles off **Cape Alberta**.

86 **Floe Bay**, at the mouth of the **Aukpar River**, is almost completely filled by **drying flats**. A rocky ledge extends east of **Farley Point** for 3.5 miles. Two named hills in this area are **Keeka Hill** and **Kokittwa Hill**.

87 **Bowman Bay** *(65°30'N, 73°40'W)*, at the mouth of the **Bluegoose River**, is shallow with rocky ledges and **drying flats** extending as much as 5 miles from the south and east shores. **Bluegoose Prairie**, a vast marsh around the head and eastern side of the bay, was once thought to be one of the few known nesting places of the Blue Goose. The Blue Goose was later discovered to be a colour variation, or morph, of the Snow Goose. **Putnam Highland**, elevation 550 feet (168 m) is the one distinctive landmark in this area.

### East side of Foxe Basin — Bowman Bay to Point Peters

88 For 135 miles the east coast of Foxe Basin, from Bowman Bay past **Cape Dominion** *(66°10'N, 74°28'W)* to Taverner Bay, is very flat and low with **drying flats** extending in places as much as 10 miles offshore. This stretch of coast is the western edge of the **Great Plain of the Koukdjuak**.

89 This coast was described by T.H. Manning as follows: "From a mile or two offshore, where at high tide there is only 3 or 4 feet (0.9 or 1.2 m) of water, the coast line appears only as a line of boulders, the height of which is greatly exaggerated by mirage. Along most of this coast the spring tides penetrate a mile farther inland than the neaps and a very short, close grass grows on a border of land, several hundred yards wide, that is covered only by the highest tides. This border in summer is a favourite feeding ground for both geese and caribou. Toward the sea the grass gives place to a fine gritty mud. This mud has a firm, cracked surface where it is seldom flooded, but is soft and sticky below the level of the spring tides. In many places farther out still, mud has either never formed, or has been washed away by the tides, leaving limestone gravel and perhaps some limestone in situ; at least when sounding with the boathook, we struck places that seemed like solid rock. The sea bottom, like the land, is quite flat, and the water is very muddy".

90 The **Koukdjuak River** *(66°43'N, 73°00'W)* drains **Nettilling Lake**, 40 miles inland, the largest lake in Baffin Island. The depth in the mouth of the river is only 2.5 feet (0.8 m); 7 miles upstream the depth in the middle is 8 feet (2.4 m), shoaling rapidly towards the sides.

91 **Caution**. — The **current** is swift, probably 6 knots, in the lower reach of the river but there are no rapids.

92 **Taverner Bay** has numerous **shoals** in its outer part and its inner part is **very shallow**.

93 **Figgures Point** *(67°17'N, 72°18'W)* is on a small island at the north end of Taverner Bay. There is a **spit**, partly dry at low water, extending west from the point for at least 5 miles.

94 Between Taverner Bay and Point Peters, 80 miles NNW, the coast becomes higher and the depths are generally greater than to the south. The water near the shore is for the most part clear, so that the bottom can be seen in depths of 20 feet (6.1 m) or more. In some places the water is deep close to shore; in others, **drying flats** may extend as much as 0.3 mile offshore.

95 **Caution**. — **Reefs** are numerous in all the bays.

96 From Figgures Point to Hantzsch Bay, the land consists of low, rocky hills with a maximum elevation of 60 feet (18 m). **Hantzsch Bay** *(67°34'N, 72°31'W)* is bordered by low hills that rise to 200 feet (61 m) high near the head of the bay; the hills recede 5 miles inland from the north entrance point. There are rapids in the mouth of **Hantzsch River**; these are drowned at high water. The unnamed bight north of Hantzsch Bay appears to be **shallow** and rocky.

97 Maximum **high water**, **spring tide** *(spring rise)* is 25 feet (7.6 m) at Hantzsch Bay.

98 **Caution**. — Strong **tidal streams** are reported to northward of Hantzsch Bay.

99 **Caution**. — **Weeks Bay** is **obstructed** by rocky islets and **shoals**.

100 The coast between Weeks Bay and **Parry Point** *(67°59'N, 72°57'W)* is low with hills rising 4 to 5 miles inland to 200 feet (61 m).

101 **Caution**. — The river 2 miles south of Parry Point is **shoal**; the inlet 2 miles farther south is **shoal** with rocky islets and **reefs** in its entrance.

102 **Nichols Bluff** is on the SE shore of **Wordie Bay**. The bluff is over 300 feet (91 m) in elevation and is distinguishable by a band of white quartz visible for several miles. The high land recedes from the coast north of the bluff; around the NE side of Wordie Bay it is several miles inland.

103 At the south end of Wordie Bay the average **high tide** is 12 feet (3.7 m). A marked pause in the rise and fall was noted although there was no actual double tide.

104 **Caution**. — At Parry Point the **tidal stream** flows northward into Wordie Bay, on the flood, with a rate of 1.5 to 2 knots.

105 **Point Peters** *(68°15'N, 73°38'W)*, the NW entrance point of Wordie Bay, is at the end of a low rocky island connected to the mainland by **shoals**. A knoll over 100 feet (30 m) high rises close NE of the point.

### Prince Charles and Air Force Islands

106 **Prince Charles Island**, the largest island in Foxe Basin, is typical flat limestone terrain. Wet arctic meadows interspersed with melt-water lakes surround higher, dryer gravel fields that support only sparse low shrubs further inland. The centre of the island is bare bedrock. Limestone gravel beaches surround the island. The maximum elevation is reported to be 250 feet (76 m). **Outcrop Point** *(68°20'N, 76°18'W)*, at the north end of the island, is a low projection of limestone.

107 The western half of the island faces open sea and has many raised beaches. The more-sheltered eastern half is low and swampy and subject to seasonal flooding, with innumerable ponds. A few low hummocks interrupt the flat terrain and there are many boulders on the land and along the shore.

108 **Caution**. — The water off the north coast of the island is extremely shallow with numerous **rock shoals**. **Shoal water** extends 2 to 3 miles off the south coast and at least 6 miles off the east coast where depths of only 2 or 3 fathoms (3.7 or 5.5 m) are found at this distance offshore. Captain Poole of the Department of Railways and Canals tug *Ocean Eagle*, who first sighted Prince Charles Island in 1932, found a depth of 10 fathoms (18.3 m) 4 miles off **Poole Point**, the west extremity of the island.

109 Near **Gravell Point**, at the south end of Prince Charles Island, there is a **landing beach** that is one of the few places usable at all stages of the tide. There are no sheltered anchorages, even for small craft, on this island.

110 Brief observations near Gravell Point showed a **tidal range** of only 3 feet (0.9 m).

111 **Caution**. — The **tidal stream** at Gravell Point reaches 3 knots. Captain Poole reported that off Poole Point the ebb stream runs south for 5 hours at 2 knots; the flood stream runs north for 7 hours at 2.5 knots.

112 **Air Force Island** is separated from Prince Charles Island by **Cockram Strait**. The island is low and flat except for a ridge of granite and gneiss 100 feet (30 m) high in the western part. The ridge tends north to terminate in **Fee Peninsula** *(68°08'N, 74°19'W)*, also 100 feet (30 m) high. The island has a surface of beach gravels and flattened glacial deposits. Except for Fee Peninsula the coasts of the island are extremely low, wet and slope gently into the sea.

113 Good **anchorage** for small craft with shelter from winds from south to NW can be found in the outer part of **Nauja Harbour**, close to the shore of Fee Peninsula.

## North shores of Foxe Basin

*Charts 7486, 7067*

### Jens Munk Island to Cape Thalbitzer

114 **Jens Munk Island**, with **(Cape) Konig Cape** *(69°29'N, 80°01'W)* at its south end, lies in the NW part of

Foxe Basin. Low shores rise to higher land in the interior of the island.

115 **Caution**. — Partly **drying shoal banks** extend a considerable distance offshore from the NE and SE sides of Jens Munk Island.

*Chart 7486*

116 **Cape Elwyn** *(69°34'N, 80°18'W)*, at the entrance to Skeoch Bay, is 30 m high and rises gradually northward to over 122 m.

117 **Skeoch Bay**, reported to be an excellent harbour and ice-free during most of the navigation season, has a depth of 9.1 m in the middle of the entrance.

*Chart 7067*

118 The coast between Cape Elwyn and Cape Lamprenen, 13 miles NW, is rocky and rough and has several rocky, small islets close offshore. The land around **Cape Lamprenen** is steep, 100 feet (30 m) high and prominent.

119 **Caution**. — **Shoal water** extends 0.5 mile offshore in this area.

120 **South Passage** provides access to Murray Maxwell Bay. **Deer Island** *(69°47'N, 80°42'W)* is surrounded by **shoal water**.

121 **Caution**. — South Passage is **dangerous** for ships; **currents** of up to 7 knots cause heavy **tide rips**, and the passage may be blocked by **ice**.

122 The NE shore of **Siorarsuk Peninsula** is low and smooth with hills rising inland to over 500 feet (152 m).

123 The north shore of **Murray Maxwell Bay** is low. To the west, there are numerous rocky islets in front of this shore. Several islands lie off the eastern part; many **rocks** and **shoals** lie close to the shore and among the islands.

124 **Caution**. — The east entrance to Murray Maxwell Bay, known as **East Channel**, is almost completely **obstructed** by **shoal water** extending from both sides and in the east entrance.

125 From the NW end of East Channel to Cape Thalbitzer, 20 miles east, the coast is smooth and even and the hinterland low and rolling. The shore is a continuous beach.

126 **Caution**. — A wide stretch of **shoal water** lies offshore of the beach.

127 **Cape Thalbitzer** *(69°53'N, 78°45'W)*, the west entrance point to Steensby Inlet, is 40 feet (12 m) high and rugged with steep cliffs on both sides.

128 An offshore **survey** in 1981 and earlier track soundings indicate **depths** ranging from 12 to 69 fathoms (22 to 126 m) between Jens Munk Island and Koch Island. **Uncharted depths** of 16 fathoms (30 m) lie NE of Tangle Island.

129 **Caution**. — **Shoal depths** as little as 15 feet (4.6 m) are charted 10 to13 miles south of Cape Thalbitzer. An **uncharted shoal** with 31.5 feet (9.4 m) over it lies 4 miles north of the north end of Maneetok Island *(69°44'N, 78°24'W)*. Depths of less than 11 fathoms (20 m) lie in the area between the shoal and the island; deeper water is found north of the shoal.

## Cape Thalbitzer to Reid Point

130 **Steensby Inlet** is entered between Cape Thalbitzer and **Cape Jensen** *(69°43'N, 77°33'W)*, the south end of **Nuvuit Peninsula** *(not named on the chart)*. Cape Jensen is rocky. The islands in the mouth of the inlet are low and surrounded by **shallow water**.

131 Offshore track **soundings** in 1981, as shown, indicate depths of up to 82 fathoms (150 m) in the south, decreasing to 21 fathoms (38 m) midway within the inlet.

132 **Ravn River** and **Harder River** flow into the shallow bay at the NW end of the inlet.

133 **Caution**. — The west shore of Steensby Inlet is low and **shoal water** extends 1 mile offshore.

134 **Tariujaq Arm** is the narrow channel at the north end of Steensby Inlet; **Aulasivik Peninsula**, 100 feet (30 m) high and pocked with numerous small lakes, forms the west side of the arm *(neither feature is named on the chart)*.

135 The east side of Steensby Inlet from Cape Jensen north to **Rowley River** *(70°15'N, 77°42'W)* is precipitous, rising to over 500 feet (152 m), and elevations of over 1,000 feet (305 m) are found a short distance inland. The shore is less steep NW of Rowley River and generally does not rise higher than 200 feet (61 m); however, elevations over 1,700 feet (518 m) are found 6 miles east of this stretch.

136 **Caution**. — Pack **ice** drifts freely in and out of Steensby Inlet with wind and tide and, some years, this condition may persist until mid or late September.

137 **Grant-Suttie Bay** is entered between Cape Jensen and **Ignerit Point** *(69°39'N, 77°10'W)*. The shores rise moderately to elevations of 500 to 800 feet (152 to 244 m). **Isortoq Fiord** runs NE from the NW part of the bay. **Imarujuk Island**, 100 feet (30 m) high, and **Imiliq Island** lie in the mouth of the bay.

138 **Caution**. — Grant-Suttie Bay contains many small rocky islands and **rocks** and **shoals**.

139 Good **anchorage** for small craft may be obtained in the NE part of Grant-Suttie Bay, 6 miles from Ignerit Point.

*Chart 7411*

140 **Harbour Bay**, 7 miles ESE of Ignerit Point, is reported to provide good **anchorage** for small craft.

141 A least depth of 6 fathoms (11 m) in mid-channel can be maintained to the head of **Eqe Bay**. The land at the head of the bay is over 800 feet (244 m) high.

142 The coast between Eqe Bay and **Tikerarsuk Point** is low and smooth; rounded hills with elevations of 500 to 600 feet (152 to 183 m) are inland.

143 **Caution**. — A narrow belt of **shoal water** borders the shore, reaching 0.5 mile in width at Tikerarsuk Point.

144 **Inniq Point** *(69°28'N, 76°27'W)* is a low point at the mouth of a stream. The entrance to **Trident River** lies 2.5 miles NW of Inniq Point; the river drains **Trident Lake**, 3 miles inland *(both shown but not named on Chart 7067)*.

145 **Caution**. — **Ikpik Bay** has not been sounded but it is reported that the channel between Bray Island *(69°20'N, 77°00'W)* and **Reid Point**, on Baird Peninsula, is very **shoal**.

146 **Ikpik River**, which drains **Lake Gillian** *(both named on Chart 7067)*, enters Ikpik Bay 10 miles ESE of Tikerarsuk Point. The shore is sandy beach in this area.

147 **Caution**. — Numerous **shoals** and **drying areas** extend 3 miles offshore from the Ikpik River to the head of Ikpik Bay and westward to Reid Point.

148 **Ullit Island** *(69°11'N, 75°34'W)*, at the head of Ikpik Bay, is composed of lines of raised beach. **Drying flats**, extensive along this coast, join Ullit Island to the mainland.

## Islands in north part of Foxe Basin

*Charts 7485, 7411, 7067*

149 **Caution**. — From air photos there is shallow to moderate depths off the low islands in the north part of Foxe Basin; great caution must be exercised when navigating these waters.

### Spicer and Manning Islands

150 **South Spicer Island** *(68°16'N, 79°00'W)* is low, flat and marshy with a maximum height of 7.6 m along the coast and 30 m near its north end. The island is composed of lines of raised limestone gravel beaches. **Era Island**, 4 miles eastward, is low; the water in the vicinity appears shallow.

151 **Caution**. — Several unnamed islands lie up to 7 miles offshore and extensive areas of very **shoal water** surround South Spicer Island. There is no shelter.

152 **Caution**. — A **shoal depth** of 13.1 m is 20.5 miles west of the north end of South Spicer Island.

*Charts 7485, 7489, 7411*

153 **North Spicer Island**, mostly marsh, is lower than South Spicer Island and is a poor radar target. **Ocean Eagle Point** and **Bowdoin Point** are its NW and NE extremities.

154 **Caution**. — The island is almost entirely surrounded by extensive **drying areas** and wide **shoal areas**.

155 There is a **beacon**, consisting of a square skeleton **tower** 15.2 m high, fitted with three fluorescent-orange rectangular **daymarks** and a **radar reflector**, on Ocean Eagle Point.

156 **Skelton Bay** affords **anchorage** with moderate shelter, except from the east, for small craft. Anchor 0.8 mile from the shore because of the shallow water.

157 **Manning Islands** *(68°47'N, 80°04'W)* is a group of four small islands 27 miles WNW of Ocean Eagle Point.

158 There is a **beacon**, consisting of a fluorescent-orange rectangular **daymark** on a galvanized steel **tower** 15.2 m high, fitted with a **radar reflector**, on the highest island.

159 **Caution**. — Manning Islands are surrounded by **shallow water**; there is a 6.7-m **shoal** 6 miles SSE of these islands.

160 **Navy Channel** runs between North Spicer and Rowley Islands.

161 **Caution**. — Only the fairway has been sounded. **Shoal water** extends into Navy Channel for a considerable distance from North Spicer Island and probably also from Rowley Island. A vessel using the channel should fix its position by ranges and bearings on Manning and Rowley Islands as the soundings are relative to those islands.

*Chart 7486*

### Rowley Island

162 **Rowley Island** is flat with a generally low shoreline and a greatest elevation of 67 m.

*Charts 7486, 7411*

### East shore of Rowley Island

163 Between **Morrisey Point** *(68°50'N, 79°15'W)* and **Dunn Point**, 10 miles to the NE, the shore is composed mainly of raised beaches. **Shallow water** borders this stretch of coast.

164 There is a square skeleton **tower** 16.1 m high, fitted with three fluorescent-orange rectangular **daymarks** and a **radar reflector**, on Morrisey Point.

165 **Clay Point** and **Tideflat Bay** are the only named features between **Dunn Point** and **Kootyuk Point**. The bay is nearly **dry** at low water; the **flats** consist of solid, horizontally bedded limestone.

### West shore of Rowley Island

166 Between **Bartlett Point** and **Ewerat Point**, the coast is bordered with **shallows** more than 0.5 mile wide.

167 Bartlett Point is marked by a **beacon** with a **radar reflector**. The condition of this aid is unknown *(2006)*.

*Chart 7465*

168 There is a **beacon**, consisting of a square skeleton **tower** 50 feet (15.2 m) high fitted with three fluorescent-orange rectangular **daymarks** and a **radar reflector**, on Ewerat Point.

169 **Needle Point** *(69°06'N, 79°08'W)* is bluff and 60 feet (19 m) high. The points of land protruding into Frustration Bay are low and inconspicuous.

170 Red, 18-foot (5-m) **tripod beacons** were constructed, in 1955, 0.9 mile east of Ewerat Point, on Needle Point and 0.5 mile ESE of **Frustration Point**. The condition of these beacons is unknown *(2006)*.

171 A radar **dome** mounted on a skeleton **tower** at a *North Warning System* site, 1.8 miles SE of the head of Needle Cove, is **conspicuous**; the dome has an aircraft warning light on top. Two smaller domes at ground level and a building are prominent *(the radio tower shown on the 1957 edition of Chart 7465 and on the 1973 edition of Chart 7411 no longer exists)*. An abandoned airstrip is near the site.

172 **Caution**. — The Rowley Island *North Warning System* site is **not manned**. There is an emergency shelter with a telephone and a motion-activated camera but no supplies or services.

173 The soundings off Needle Point and in Needle Cove are from a controlled survey in 1955.

174 **Caution**. — The east part of Frustration Bay has not been surveyed; **shallow water** prevails inshore from Frustration Point past **Elder Point** to **Fife Point** and northwards. The bay entered 5 miles NNE of Fife Point is shallow. The whole of the SE side of Needle Cove is bordered with **shoal water**.

175 If ice conditions permit, vessels may find **anchorage** in 12 to 18 fathoms (21.9 to 33 m) 1 mile NNW of Needle Point. The holding ground is reported to be very good; the bottom is small rocks, gravel and clay. **Anchorage** for small craft is available 0.2 mile off the west shore of Needle Cove. Some protection is afforded from winds between NE and SW by a range of low hills running from near Needle Point to Frustration Point.

176 **Caution**. — Frustration Bay usually presents a lee shore because of the prevailing NW winds. **Ice** from the north part of Foxe Basin might enter the bay at any time during the navigation season.

177 The **tidal range** in Needle Cove is 7 to 10 feet (2 to 3 m). With a persistent strong south or SE wind, the tidal range is considerably reduced.

178 **Caution**. — **Tidal streams** in the main anchorage area have maximum rates and directions of 2 knots, 060° on the flood, and 1.8 knots, 230° on the ebb. The streams are weaker near the shore.

179 A **landing beach**, at the head of Needle Cove, is composed of fine soft gravel. There are **oil tanks** and equipment behind the beach. The approach is made along the centre line of Needle Cove.

180 **Caution**. — Keep well clear of the **shoal water** off Needle Point.

*Charts 7486, 7411*

## Labrador Channel and Koch Island

181 **Labrador Channel** runs between Rowley and Koch Islands. Soundings in the channel are from a controlled survey in 1956.

182 **Wallace Head** *(69°24'N, 78°31'W)*, the north end of Rowley Island, is bluff and rises quite steeply from the sea. **Cape Bushnan** and **Cape Lindenwald**, on Koch Island, are reported to stand out enough to provide good fixing marks. The shores of **Tremblay Bay** are shallow.

183 There are 9-m high beacons on **Pursuit Point**, Wallace Head, **Cape Sadlek**, Cape Bushnan, Cape Lindenwald and in a position 5.4 miles NE of Cape Lindenwald. All of these beacons are fitted with **radar reflectors**. The condition of these beacons is unknown *(2006)*.

184 **Caution**. — **Bushnan Rock** *(69°25'N, 78°51'W)* lies 2.8 miles south of Cape Bushnan; there is **shoal water** between the rock and the cape. A **shallow spit** projects north of Pursuit Point. **Shoal patches** with 14.9 and 11.9 m over them lie near mid-channel.

185 The **tidal range** in Labrador Channel is 3 to 3.7 m.

186 **Caution**. — Brief current observations in the west approaches to Labrador Channel indicate a **tidal stream** of 2 knots, apparently flowing east through the channel on the flood tide.

*Charts 7486, 7411, 7067*

187 **Koch Island** is generally low with a maximum elevation of 210 feet (64 m) near the middle of the west shore. **Tidal flats** extend a considerable distance offshore along most of the coast. **Cape Bazin** *(69°38'N, 77°56'W)* is the east end of the island. **Maneetok Island**, off the NW shore of Koch Island, is 30 feet (9 m) high. From air photos, there appear to be other low islets in the vicinity *(offshore dangers, NW of Koch Island, have been previously described)*.

*Chart 7411*

## Bray Island

188 **Bray Island** is low and flat with numerous ponds in the interior. **Thuban Point**, **Polecat Point** and **Turner Point** are the SE, SW and NW extremities of the island.

189 **Caution**. — Bray Island is surrounded by **shoal water** and broad **drying flats**; it should be approached only with extreme caution.

190 There is a *North Warning System* site several miles inland from the SW coast of Bray Island.

191 **Caution**. — The Bray Island site is **not manned**. There is an emergency shelter with a telephone and a motion-activated camera but no supplies or services.

192 A **landing beach** is 2 miles south of **Aggakjuk Point** *(69°17'N, 77°23'W)*. The soft beach, usable only at high water, is composed of gravel and crushed limestone.

193 Four wooden **tripod beacons**, 18 feet (5 m) high, fitted with **radar reflectors**, are near the landing beach. The condition of these beacons is unknown *(2006)*.

194 **Anchorage** may be obtained in the open roadstead west of the landing place in 6 to 10 fathoms (11 to 18.3 m) over clay bottom with good holding.

195 **Caution**. — Because of the prevailing NW wind, **drift ice** may be encountered in this area. Records over nine years indicate that mid September to early October is the period most likely to be ice-free.

196 **Caution**. — The **tidal stream** at the anchorage flows north and south with average maximum rates of 2.4 and 1.3 knots, respectively. Near the landing beach the stream is reported to run continuously southward.

*Charts 7489, 7411*

## SW approaches to Longstaff Bluff

197 **Cape Burpee** *(68°40'N, 76°35'W)* is the SW end of **Baird Peninsula**. The cape has a maximum elevation of 30 m and there are numerous ponds. The bight midway along this stretch is nearly dry at low water. The shoreline north and east of Cape Burpee is composed of lines of raised beach.

198 **Caution**. — Between Reid Point and Cape Burpee, **shoal water** extends offshore for 2.5 miles.

199 A **beacon**, consisting of a skeleton **tower** 18.3 m high fitted with three orange **daymarks** and a **radar reflector**, is 4 miles north of Cape Burpee.

200 A **radar reflector**, fitted on a mast 12.2 m high, is 4 miles south of Reid Point. The condition of this aid is unknown *(2006)*.

201 **Caution**. — Extensive areas of **shoal water** are reported in the vicinity of the **drying shoal** 2 miles SSE of Cape Burpee.

202 From Cape Burpee to **Sidjegiak Point** *(68°55'N, 75°31'W)*, the SE coast of Baird Peninsula is low. This coast forms the NW shore of **Nauja Bay**.

203 **Caution**. — The NW shore of Nauja Bay is bordered with **shoal water**.

204 **Rushmore Bay** has **drying flats** at its head. A line of hills 122 m high, with steep slopes facing west, approaches the head of Rushmore Bay and extends SE to Longstaff Bluff. A coastal plain, which narrows towards the SE, is between the hills and the sea.

205 **Caution**. — **Shoal water** extends from the west shore and a narrow belt of **shoal water** borders the east shore of Rushmore Bay.

206 **Foley Island**, on the SE side of Nauja Bay, has a maximum elevation of 85 m near prominent **Anderson Bluff** *(68°39'N, 75°01'W)*. The NE part of the island is composed of raised beaches; most of the remainder is low with many scattered ponds. Between **Kotuko Point** and **Makalu Point** the land is a little higher.

207 **Caution**. —The east and west coasts have a narrow border of **shoal flats** that widen towards the south end of the island. The west coast of Foley Island is lower than the east and shallows extend a considerable distance seaward.

208 **Anderson Island** has rough rocky coasts. From air photos, the north side of the channel between Anderson Island and Foley Island appears to be deep.

209 **Caution**. — Anderson Island is bordered by narrow **shoal** areas.

210 **Amagok Island** *(68°48'N, 75°12'W)*, 2.5 miles NW, is low and rocky.

211 **Caution**. — There is **shoal water** 0.5 mile SSE of Amagok Island.

*Charts 7067, 7411*

## SE and east approaches to Longstaff Bluff

212 Point Peters *(68°15'N, 73°38'W) (previously described)* is the SE entrance point to Clarke Sound.

213 **Clarke Sound** is reported to be very **shallow** where it narrows north of the entrance to Straits Bay.

214 **South Tweedsmuir Island** *(68°23'N, 74°15'W)* is almost entirely devoid of vegetation. The highest elevation on the island, 390 feet (119 m), is a rounded rocky dome in its NE part. In its south part a rounded hill rises to 100 feet (30 m). The shoreline is of solid rock or gravel and shingle beaches except at the north end where there is a low boulder beach. Raised beaches are found up to 60 feet (18 m) above the present shoreline. From air photos, the east coast of the island appears to have deep water close inshore.

215 **Caution**. — Most of the west coast is low and bordered with rocky **shoals** and **shallow water** for some distance offshore. The unnamed island south of South Tweedsmuir Island is entirely barren; the channel between the islands is full of islets and **shoals**.

216 **North Tweedsmuir Island** is almost uniformly bare and rocky. The granite rocks extend into the sea in low peninsulas, especially on the east side, separated by small bays with pebble and gravel beaches. A ridge with a few lakes along its foot forms a prominent feature along the north and east coasts

of the island. On the SW coast the water deepens quickly; on the NW coast it shoals gradually and forms a wider **tidal flat**.

217 The islands between North and South Tweedsmuir Islands are rocky with a maximum elevation of 100 feet (30 m).

218 **Caution**. — These unnamed islands have numerous **rocks** and **drying shoals** among them.

219 The islands in the entrance to **Straits Bay** are low, rocky and surrounded by **shoals**; those in the inner part of the bay are of moderate elevation, the highest 180 feet (55 m). The east shore of the bay is broken by a series of rocky ridges; the north shore is low and the west rises steeply to over 400 feet (122 m).

220 The shore between Straits Bay and Piling Bay, 29 miles NW, is low, irregular and rocky and bordered with a number of rocky islets and **drying areas** which extend, in places, more than 1 mile offshore.

221 The south entrance point to **Piling Bay** *(68°52'N, 74°50'W)* is low and rocky.

222 **Caution**. — The head and south shore of the bay are **obstructed** by **shoal spits** and rocky islets.

223 The entrance to **Piling Lake**, to the north of Piling Bay, can be navigated by shallow-draught boats at high water but there are **rapids** at low water.

*Chart 7488*

### Longstaff Bluff

224 **Longstaff Bluff** *(68°54'N, 75°12'W)* consists of sharp, jagged hills of rock interspersed with lakes; it is prominent from south and SW. The buildings, radar domes, oil tanks and a tower of an abandoned DEW Line site are near the summit of the bluff; there are more oil tanks near the landing beach. An abandoned airstrip is 2.5 miles NW of the landing place. A *North Warning System* site has been built near here.

225 **Caution**. — The Longstaff Bluff site is **not manned**. There is an emergency shelter with a telephone and a motion-activated camera but no supplies or services.

226 The **conspicuous** radar **domes** have been sighted at a distance of 35 to 40 miles.

227 Soundings in the vicinity of Longstaff Bluff are based on controlled surveys in 1955, those in the approaches are based on reconnaissance surveys.

228 **Message Island** is close SE of Longstaff Bluff; there is a depth of 4 m in the middle of the channel between the two. A 4.9-m depth is 0.2 mile east of the island. **Akalukjuk Island** *(68°54'N, 75°03'W)* is on the west end of several **drying patches**.

229 The **landing beach** is 1.3 miles west of the DEW station. The recommended **anchorage** for dry cargo vessels is 0.5 mile SW of the landing beach, in 27.4 m clay, good holding ground. It is protected only from offshore winds.

230 Good **anchorage** is available on the SE side of Longstaff Bluff in 40 to 55 m, clay and mud. The area is enclosed by the bluff, Message and Akalukjuk Islands and **Index (Finger) Point**, 1 mile north of Akalukjuk Island. The best approach to this anchorage is from the south between Message and Akalukjuk Islands.

231 **Caution**. — Care must be taken to avoid the **shoal patch** lying east of Message Island.

232 The anchorage area off the landing beach is usually free of fast ice towards the end of July; medium to big floes may be expected to remain in the approach to Longstaff Bluff until late September. The floes usually stay 2 miles offshore but may sometimes be brought into the anchorage and beaching areas by southerly winds. The tidal stream, islands and drying reefs keep the anchorage SE of Longstaff Bluff free of ice during the navigation season. Freeze-up usually commences mid October.

233 The **tidal range** at Longstaff Bluff is reported to be 4.6 m.

234 **Tidal flats**, scattered with boulders, extend over 0.1 mile from the high water line at the landing place. A channel 91 m wide has been cleared to create the landing beach. This beach can only be worked between full and half tide.

235 **Caution**. — The **tidal stream** is rectilinear and runs parallel to the beach at 1 to 2 knots. Operators of landing craft or barges approaching the beach must exercise extreme caution to avoid being set onto the boulders that line the sides of the channel.

236 Tankers normally moor at a 45° angle, stern to the beach, with bow and stern anchors. Fuel is delivered through a floating hose 915 m long.

237 An abandoned airstrip is 4 miles NW of Longstaff Bluff. A gravel road connects the beach with the *North Warning System* site and the airstrip.

## Fury and Hecla Strait — General

*Charts 7486, 7487, 7067*

238 **Fury and Hecla Strait**, named after the ships of Parry's expedition of 1821-23, runs 105 miles WNW from Foxe Basin to the Gulf of Boothia. The east entrance lies between Arlagnuk Point on Melville Peninsula and Cape Konig, 33 miles NE on Jens Munk Island *(both previously described)*. The west entrance lies between Cape Englefield on Melville Peninsula and Cape Hallowell, 11 miles NE, on Baffin Island.

239 The south coast of the strait is formed of sloping rounded hills of rusty-looking dark rock cut by many small

valleys. The hills gradually attain a height inland of 345 m. The north side is similar but has snow-capped mountains behind the coast in the middle of the strait. The highest mountain, some 9 miles inland, has an elevation of over 579 m.

240 The mid-channel route through Fury and Hecla Strait was surveyed to modern standards between 1960 and 1981.

241 The channel is 7 miles wide, between 20-m contours, southwest of Tern Island.

242 The width of the channel, within Labrador Narrows, is 1 mile except in the central part where it is reduced to 0.5 mile. Depths in the channel range from 120 to 205 m.

243 West of Labrador Narrows, the sounded channel widens to 2 miles but between Liddon and Ormonde Islands, NE of a shoal, the fairway is restricted to a width of 1 mile.

244 Beyond Ormonde Island, and as far as the Mocklin Islands, the sounded channel, 5½ miles wide, lies along the centre line of the strait. Apart from a shoal area, north of the west end of Liddon Island, the strait is clear of charted dangers and has mid-channel depths of between 80 and 220 m.

245 **Caution**. — In the area west of Purfur Cove *(69°50'N, 84°15'W)*, soundings are derived from reconnaissance surveys and track soundings. At the west end of the strait, from Mocklin Islands to the west entrance, sparse soundings show depths between 146 and 366 m.

246 The least charted depths in or near the sounded channel are 5.8 m SW of Tern Island, 20 m SE of Cape Ossory, 3.9 m NW of Northeast Cape and 11.1 m ENE of Freuchen Point. Depths of 16.2 and 18.6 m lie 7.6 miles NW of Freuchen Point.

247 It is not usually feasible for ships, other than icebreakers, to attempt to reach Bellot Strait by way of Fury and Hecla Strait. There may be ice in Fury and Hecla Strait and there is pack ice that lies to the westward and also to the south of Crown Prince Frederick Island in the Gulf of Boothia.

248 Tremblay, in 1913, said "The heavy arctic ice floes that drift in from the Gulf of Boothia and Prince Regent Inlet are driven eastwards by the strong prevailing current and become solidly jammed between Ormonde and Elder Islands and the mainland...". Observations in recent years confirm that this may happen, but on occasions, in August and September, Fury and Hecla Strait has been nearly ice-free except for a concentration in or close westward of the western entrance. It is reported that due to the strength of the current ice never forms in Labrador Narrows; any ice there will have been carried in by the current.

249 The first passage of Fury and Hecla Strait was made by a U.S. icebreaker from west to east in September 1948. At that time 4/10 to 6/10 ice coverage was found in the western entrance; there was less than 1/10 coverage in the remainder of the strait.

250 In September 1956, the icebreaker H.M.C.S. *Labrador* made the first east to west passage through the strait and found only scattered ice floes.

251 There may be rare occasions when ice conditions are suitable for ordinary vessels but they cannot be relied upon. One such occasion was in 1975 when several vessels made the west to east transit of Bellot and Fury and Hecla Straits, in September, with no problems from ice.

252 H.M.C.S. *Labrador* reported moderate currents in the wider parts of the strait with a possible maximum of 2 knots to the eastward.

## Fury and Hecla Strait — SE entrance — Islands

253 **Neerlonakto Island**, 1 mile north of Igloolik Island *(previously described)*, is formed of limestone and is very low and flat. It is covered with muskeg and ponds and reaches a maximum elevation of 19 m near its NW end. **Drying flats** extend off its NE and east sides from gently shelving beaches.

254 There is a **beacon**, fitted with a **radar reflector**, on the highest part of Neerlonakto Island; it is the first part of the island to be detected by radar when approaching from any direction. The condition of this beacon is unknown *(2006)*.

255 Local **magnetic anomalies** of 90° or more have been observed over a small area 7 miles ENE of the north point of Neerlonakto Island.

256 **Tern Island** *(69°33'N, 80°50'W)*, elevation 8 m, is on the NE side of the fairway through Fury and Hecla Strait.

257 Tern Island is marked by a **beacon** with a **radar reflector**. The condition of this beacon is unknown *(2006)*.

258 **Caution**. — Tern Island has **shoal water** close around and many **drying rocks** off the north side; **gravel spits** extend from the east and west ends. A large **shoal patch**, centered 3.5 miles SW of Tern Island on the SW side of the fairway, has three pinnacles; the least depth is 5.8 m.

259 **Tangle Island**, the southernmost of the Calthorpe Islands, was so named by Parry because of the quantity of seaweed floating nearby. It is low, composed of raised beach lines 30 m high, and is surrounded by **shoal water** except off its SE coast. The west coast of the narrow island, 1 mile north of Tangle Island, consists of steep cliffs 18 m high.

260 A **beacon** on Tangle Island is 9 m high and is fitted with a **radar reflector**. The condition of this beacon is unknown *(2006)*.

261 **Caution**. — Heavy **tide rips** have been reported in the area east of Tern Island and Tangle Island.

262 **Caution**. — **Depths** of 10.4 and 10.1 m are charted 15 miles south and 12 miles SW of the south point of Tangle Island, near the main sounded route between Foxe Basin and Fury and Hecla Strait.

263 *Fury*, in July 1822, found **anchorage** 1 mile west of the middle three islands of the Calthorpe group, in 21.9 m, with good holding over a flat bottom.

264 In August 1975, the survey ship *Baffin*, length 90 m, found **anchorage** in 37 m with Cape Elwyn bearing 082°, 1.9 miles distant.

*Chart 7487*

## SE approaches to Labrador Narrows

265 **Bouverie Islands** *(69°38'N, 82°12'W)* lie off the east end of the south side of Labrador Narrows. **Mount Sabine**, near the west end of the largest island, has a **cairn** on its summit and is the most **conspicuous** landmark in the area.

266 **Caution**. — **Uncharted rocks** and islets are reported north and south of Bouverie Islands. **Shoal water**, of limited extent, lies off the SE and SW coasts. **Depths** of 4.3 m and 14.5 m are charted on either side of the approach channel to Labrador Narrows, 0.5 mile and 3 miles north of the northernmost of the islands.

267 **Richards Bay** is on the south side of Bouverie Islands; the land at the head of the bay has an elevation of 122 m.

*Chart 7067*

## NE approaches to Labrador Narrows

268 The SW coast of Siorarsuk Peninsula *(previously described)*, from **Augarnar Point** *(69°43'N, 80°57'W)* NW to a point opposite Cape Griffith, rises to over 600 feet (183 m). There is a narrow sandy beach along the shore.

269 **Caution**. — **Shoal areas** and a few **rocks** lie within 1.5 miles of the shore of the peninsula.

270 **Cape Griffith** is low, light-coloured gneiss fringed with a sandy beach.

271 **Caution**. — Some narrow **shoals** and a few islets, some of them **uncharted** *(1978)*, lie off the cape.

## Gifford Fiord

272 The land around the mouth of **Gifford Fiord** is low and formed of rock with rounded edges; the depressions between the ridges have been filled with marine deposits. Within the fiord, the sides become gradually steeper and higher, reaching elevations of over 1,000 feet (305 m); the surrounding land is plateau-like. **Ikuma Bay** is a small inlet. **Gifford River** flows into the head of the fiord; **Asta Lake** is a widening of the river.

273 From Cape Griffith to **Sévigny Point**, 12 miles SW, the coast is 200 feet (61 m) high and bordered by islets.

274 In late August 1975, the survey ship *Baffin* found **anchorage** in 22 fathoms (40 m) with Sévigny Point bearing 348°, 4.8 miles distant.

*Chart 7487*

275 **Elder Island** *(69°50'N, 82°33'W)* is separated from Baffin Island to the north by **Adolf Jensen Sound**. Elder Island is rocky and has a conical peak, 91 m high with a cleft at the top, near its north side.

276 **Caution**. — Very strong **tidal streams** run through Adolf Jensen Sound and through the narrow channel separating Elder Island from **Ormonde Island** to the south. The stream flows east with the flood and west with the weaker ebb tide. Patches of open water are found in winter in these channels.

## Labrador Narrows to Gulf of Boothia

277 **Northeast Cape** *(69°41'N, 82°32'W)*, the SE entrance point to the narrows, is low. The land to westward, terminating in **Cape Lilly**, is higher and formed of red sandstone.

278 **Cape Ossory**, the SE end of Ormonde Island, is steep sided and composed of very broken grey or dark rock. The NW portion of the cape rises to 213 m. **Friday Point**, the SW end of Ormonde Island, has an elevation of 106 m. Ormonde Island is **conspicuous** from westward.

279 **Caution**. — Labrador Narrows has a least depth near mid-channel of 20 m, 1.2 miles SE of Cape Ossory. Depths of 4 and 13.1 m lie on the north side of the narrows, 2 miles WNW of Cape Ossory. A 9.8-m patch lies on the north side of the approach, 0.7 mile east of the cape.

280 **Caution**. — The **current** through Labrador Narrows usually flows continuously to the east at rates of 2 to 5 knots but at times there is a westward **eddy** along the south shore. Numerous **eddies** and **tide rips** have been observed near the east entrance, and very strong **tide rips** occur off Cape Lilly. Information on tidal streams in Fury and Hecla Strait, and especially in Labrador Narrows, is scant. In Labrador Narrows, mid-channel tidal streams flowing westerly on the ebb, at indicated rates of up to 8 knots, have been reported *(2008)*.

281 Very strong **magnetic anomalies** were reported by *Fury* and *Hecla* 9 miles east of Northeast Cape and 8 miles east of Cape Ossory.

282 **Liddon Island** has a maximum elevation of 61 m. **Freuchen Point** *(69°45'N, 82°58'W)* appears as a long low spit with the land gradually rising to the west.

283 **Caution**. — **Shoal water** extends off the point for a short distance, and off the south side of the point for 0.5 mile in places. **Submerged rocks** and **rocks** reported to dry lie between Liddon Island and the mainland to the south.

284 **Caution**. — A **shoal depth** of 11.1 m is in mid-channel, 0.9 mile ENE of Freuchen Point.

285 **Caution**. — An **isolated shoal**, with a depth of 16.2 m, is on the south side of the sounded channel, 2.6 miles north of the west end of Liddon Island.

286 **Caution**. — The **currents** in mid-strait north of Liddon Island have rates from 0 to 2 knots. The currents are variable in direction, frequently flowing across the axis of the strait.

287 **Cape Tordenskjold** *(69°59'N, 83°20'W)*, 12 miles NNW of Liddon Island at the west end of **Sikosak Bay**, rises from a low foreland to an elevation of 410 m 4 miles inland. The shore from Cape Tordenskjold west to **Whyte Inlet** is bordered by **shallows** that reach a width of 0.8 mile in the west part of this stretch. Hills from 183 to 244 m high rise a short distance inland. Farther north, snow-capped mountains rise to over 600 m.

288 **Autridge Bay** has high shores except in the NE parts.

289 **Cape Hallowell** *(69°59'N, 85°13'W)*, a bluff 142 m high, is the NW entrance point of Fury and Hecla Strait. From the SW the cape appears as a high headland with a marked depression to the NW. The cape is recognizable at 12 to 15 miles from the SE. It appears dark with a marked split in its lengthwise direction; the right half is very much lower.

290 **Dybbol Harbour** is narrow with steep sides.

## South shore — Cape Lilly to Cape Englefield

291 The south shore, from Cape Lilly west for 16 miles to Griffiths Bay, is moderately high. **Griffiths Bay** has steep cliffs near its head with elevations of 250 m. From Griffiths Bay the coast gradually becomes lower until, 4 miles west of **Purfur Cove**, it again becomes steep and rugged, rising 2 miles inland to 350 m.

292 **Amherst Island**, elevation 80 m, appears as part of the mainland from westward and northward; the narrow strait that separates the island from the mainland is difficult to identify.

293 **East Cape** *(69°51'N, 84°52'W)* is a low point that rises gradually to an elevation of 110 m. There are three saw-tooth **peaks** with elevations of 213 m 4 miles south of the cape; the northernmost of these is **conspicuous** and a useful landmark when entering the strait from westward.

294 **Alfred Island**, 9 miles west of East Cape, has an elevation of 137 m.

295 **Cape Englefield** *(69°49'N, 85°34'W)*, the SW entrance point of Fury and Hecla Strait, has an elevation of 145 m. From the NW the cape shows as a **conspicuous** black, rounded **promontory** with a very distinctive sharp notch. Several islets and **rocks** lie close off the north and NW shores of the cape.

296 An unnamed island with an elevation of 41 m and two adjacent islets lie 3 miles NNW of Cape Englefield. **Mocklin Islands**, four rocky islets, lie 9 miles NE of the cape.

297 There is a **beacon**, with a **radar reflector**, on the middle Mocklin Island. The condition of this beacon is unknown *(2006)*.

298 *Gulf of Boothia and the western approaches to Fury and Hecla Strait are described in ARC 402 (ARCTIC CANADA VOL. II).*

# Sail Plan

Adapted from Transport Canada Publication TP 511E.

Fill out a sail plan for every boating trip you take and file it with a responsible person. Upon arrival at your destination, be sure to close (or deactivate) the sail plan. Forgetting to do so can result in an unwarranted search for you.

## Sail Plan

### Owner Information

Name: _____

Address: _____

Telephone Number:_____ Emergency Contact Number: _____

### Boat Information

Boat Name:_____ Licence or
Registration Number:_____

Sail:_____ Power:_____ Length:_____ Type: _____

Colour Hull:_____ Deck: _____ Cabin: _____

Engine Type:_____ Distinguishing Features: _____

### Communications

Radio Channels Monitored: HF: ☐ VHF: ☐ MF: ☐

MMSI (Maritime Mobile Service Identity) Number: _____

Satellite or Cellular Telephone Number: _____

### Safety Equipment on Board

Lifejackets and PFD's *(include number)*: _____

Liferafts (include type and colour): _____ Dinghy or Small Boat
*(include colour)*: _____

Flares (include number and type): _____

Other Safety Equipment:_____

### Trip Details — Update These Details Every Trip

Date of Departure: _____ Time of Departure:_____

Leaving From:_____ Heading To: _____

Proposed Route:_____ Estimated Date and

Stopover Points (include date and time):___ Time of Arrival:_____

_____ Number of People on Board: _____

**Search and Rescue Telephone Number:** _____

The responsible person should contact the nearest Joint Rescue Coordination Centre (JRCC) or Maritime Rescue Sub-Centre (MRSC) if the vessel becomes overdue.

Act smart and call early in case of emergency. The sooner you call, the sooner help will arrive.

**JRCC Victoria (British Columbia and Yukon)** 1-800-567-5111
+1-250-413-8933 (Satellite, Local or out of area)
# 727 (Cellular)
+1-250-413-8932 (fax)
jrccvictoria@sarnet.dnd.ca (Email)

**JRCC Trenton (Great Lakes and Arctic)** 1-800-267-7270
+1-613-965-3870 (Satellite, Local or Out of Area)
+1-613-965-7279 (fax)
jrcctrenton@sarnet.dnd.ca (Email)

**MRSC Québec (Quebec Region)** 1-800-463-4393
+1-418-648-3599 (Satellite, Local or out of area)
+1-418-648-3614 (fax)
mrscqbc@dfo-mpo.gc.ca (Email)

**JRCC Halifax (Maritimes Region)** 1-800-565-1582
+1-902-427-8200 (Satellite, Local or out of area)
+1-902-427-2114 (fax)
jrcchalifax@sarnet.dnd.ca (Email)

**MRSC St. John's (Newfoundland and Labrador Region)** 1-800-563-2444
+1-709-772-5151 (Satellite, Local or out of area)
+1-709-772-2224 (fax)
mrscsj@sarnet.dnd.ca (Email)

## MCTS Sail Plan Service

Marine Communications and Traffic Services Centres provide a sail plan processing and alerting service. Mariners are encouraged to file Sail Plans with a responsible person. In circumstances where this is not possible, Sail Plans may be filed with any MCTS Centre by telephone or marine radio only. Should a vessel on a Sail Plan fail to arrive at its destination as expected, procedures will be initiated which may escalate to a full search and rescue effort. Participation in this program is voluntary. *See Canadian Radio Aids to Marine Navigation.*

**A**berdeen Bay, C3/P131
Abloviak Fiord, C1/P31
Abruyuk Islands, C8/P174
Acadia, Cape, C4/P14
Acadia Cove, C3/P17
Acadia Passage, C3/P20
Access Passage, C7/P56
Adderley Bluff, C8/P123
Adolf Jensen Sound, C9/P275
Adversary Bank, C6/P132
Aeeraktoo Island, C1/P250
Aggakjuk Point, C9/P192
Agvik Island, C1/P210
Ahigik Island, C7/P29
Aiqqujat Islands, C8/P174
Air Force Island, C9/P112
Aisavartalik, Pointe, C1/P92
Aivilik Point, C8/P194
Ajaqutalik River, C9/P21
Akalukjuk Island, C9/P228
Akilahaarjuk Mountain, C6/P257
Akilahaarjuk Point, C6/P258
Akilasakallak, Anse, C1/P56
Akimiski Island, C5/P157
Akimiski Strait, C5/P162
Akpatok Island, C1/P239
Akreavenek Island, C6/P82
Akuling Inlet, C3/P128
Akulivik, C4/P52
Akulivik, Baie, C4/P44
Akulivik, Pointe, C4/P46
Akunak Bay, C6/P161
Akunak Islet, C1/P210
Akunok Islet, C1/P210
Akuuniq Bay, C7/P74
Akwatuk Bay, C5/P44
Alakakvik, Colline, C1/P208
Alareak Island, C3/P143
Albany Island, C5/P173
Albany River, C5/P172
Alberta, Cape, C9/P85
Albert-Low, Mont (Mount), C2/P100
Albert Shoal, C5/P159
Alfred Island, C9/P294
Algerine, Passe de l', C1/P152
Algerine, Pointe de l', C1/P152
Algerine Channel, C4/P124
Allan, Mount, C4/P94
Allatalik, Pointe, C1/P49
Alle Harbour, C4/P110
Alle Island, C1/P182
Alle Reefs, C1/P182
Allison Bluff, C8/P111
Alluviaq Fiord, C1/P31
Altavik Summit, C1/P208
Alukpaluk Bay, C1/P68
Amadjuak Bay, C3/P134
Amagok Island, C9/P210
Amherst Island, C9/P292
Amitioke Peninsula, C9/P20
Amittok Inlet, C1/P14
Amittoq Inlet, C1/P14
Anabusko River, C7/P207
Anchor Cove, C8/P142
Anchor Island, C1/P92
Anderson Bluff, C9/P206
Anderson Brook, C6/P8
Anderson Island *(Albany River)*, C5/P173
Anderson Island *(Longstaff Bluff)*, C9/P208
Anderson Island *(Nastapoka Islands)*, C4/P268
Anderson Point, C5/P173
Andrew Gordon Bay, C3/P143
Angusko Point, C7/P103
Aniguq River, C6/P261
Anik Islands, C5/P15
Ankle Passage, C2/P47
Annapolis Strait, C3/P55
Anse Akilasakallak, C1/P56
Anse aux Refuges, C1/P169
Anse De Villiers, C1/P175
Anse Kanik, C1/P226
Anse Merganser, C1/P187
Anse Nascopie, C1/P110
Apalooktook Point, C3/P149
Apex, Colline, C1/P185
Apiskutikutasich, Pointe, C5/P69
Apqusiurniq Island, C6/P129
Aquiatulavik Point, C3/P141
Aquttutalik, Pointe, C4/P324
Archibald Bay, C3/P136
Arctic Island, C2/P153
Arlagnuk Point, C9/P54
Arlug Island, C6/P260
Armstrong Island, C4/P260
Arnaud, Rivière, C1/P219
Arvalik, Îles, C1/P66
Arvavik Bay, C2/P34
Arviat, C7/P118
Arvik Island, C1/P210
Ascension Islands, C8/P19
Ashe Inlet, C3/P119
Asta Lake, C9/P272
Asuqaaq, Pointe, C1/P122
Asuraaq, Pointe, C1/P122
Asuuqaaq Island, C1/P122
Attawapiskat, C5/P167
Attawapiskat River, C5/P163
Attikuan, Pointe, C5/P7
Attiquane, Pointe, C5/P7
Aua River, C8/P126
Augarnar Point, C9/P268
Auk Island, C6/P210
Aukpar River, C9/P86
Aukpik Island, C7/P53
Aulasivik Peninsula, C9/P134
Aulassivik Island, C3/P94
Aulatsevik, C3/P94
Aulatsivik Point, C6/P91
Aulatsivittuaq Bay, C6/P257
Aupaluk, C1/P199
Aupartuapik, Cap, C2/P175
Austin Island, C7/P108
Autridge Bay, C9/P288
Ava Inlet, C3/P131
Ayuak Island, C2/P42

**B**abs Bay, C4/P41
Back Peninsula, C6/P6
Baffin, Cape, C8/P86
Bag Island, C7/P38
Baie Akulivik, C4/P44
Baie aux Baleines, C1/P168
Baie Boulder, C1/P145
Baie Brochant, C1/P202
Baie de Bonnard, C1/P201
Baie De Rozière, C1/P248
Baie Héricart, C2/P54
Baie Nanuttuvik, C2/P169
Baie Profonde, C1/P164
Baie Sèche *(Kap Inuksutujuq)*, C1/P122
Baie Sèche *(Lac aux Feuilles)*, C1/P160
Baie Tasiujaaluk, C2/P49
Bailey Islands, C6/P69
Baird Bay, C7/P6
Baird Peninsula, C9/P197
Baker Foreland, C7/P4
Baker Lake, C6/P226
Baker Lake *(hamlet)* , C6/P272
Bakers Dozen Islands, C4/P162
Balcom Inlet, C3/P76
Baldpate Island, C3/P96
Baldpate Rock, C2/P36
Baleen Island, C6/P201
Baleine, Grande rivière de la, C4/P296
Baleine, Petite rivière de la, C4/P282
Baleine, Rivière à la, C1/P70
Baleine Blanche, Pointe de la, C4/P249
Baleines, Baie aux, C1/P168
Ball Island, C5/P173
Bannerman Island, C6/P236
Bar, Île, C1/P109
Bar, The *(Moose River)*, C5/P198
Bar, The *(Sugluk Inlet)*, C2/P177
Barboteau Rock, C5/P124
Barbour Bay, C6/P155
Barbour Point, C6/P240
Bare Banks, C5/P159
Bare Island, C5/P4
Barge Shoal, C5/P32
Barrier Inlet, C3/P77
Barrier Islands, C7/P29
Barrier Shoals, C1/P179
Barrow Falls, C9/P11
Barrow River, C9/P11
Barry Rock, C3/P188
Bartlett, Cape, C4/P188
Bartlett Island, C4/P143
Bartlett Point, C9/P166
Basking, Île (Island), C1/P225
Bassin Payne, C1/P225
Bates, Péninsule, C4/P110
Battery Bay, C8/P144
Bay of Gods Mercy, C6/P60
Bay of Shoals, C8/P112
Bazin, Cape, C9/P187
Beach Island, C4/P157
Beach Point, C8/P187
Beacon Island *(Cape Dorset)*, C3/P152
Beacon Island *(Lake Harbour)*, C3/P92
Beacon Island *(Rivière George)*, C1/P33
Beak Point, C3/P10
Bear Cove, C6/P26
Bear Cove Point, C6/P26
Bear Island *(Coral Harbour)*, C6/P36
Bear Island *(north James Bay)*, C5/P149
Bear Islands *(Hurd Channel)*, C8/P94
Bear Islands *(SE Hudson Bay)*, C4/P313
Beartrack Bay, C4/P110
Beaulieu Bay, C3/P111
Beaumont Harbour, C3/P115
Bedford Harbour, C3/P128
Bélanger Island, C4/P272
Belcher Islands, C4/P162
Belford, Point, C8/P117

C = Chapter/P = Paragraph

Bell Cove, C1/P240
Bell Harbour, C4/P149
Bellin, C1/P234
Bell Inlet, C1/P31
Bell Peninsula, C6/P1
Bencas Island, C6/P15
Bennett Bay, C8/P174
Bérard, Rivière, C1/P166
Bernheimer Bay, C6/P66
Bernier, Pointe, C4/P11
Berthe Cove, C2/P21
Berthé Islet, C2/P83
Berthie Harbour, C8/P179
Bertrand Point, C6/P235
Beyts Cove, C6/P218
Bibby Island, C7/P100
Big, Île (Island) *(Rivière de Puvirnituq)*, C4/P75
Big Bay, C6/P175
Big Duck Island, C5/P205
Big Finger, Pointe, C4/P74
Big Hips Island, C6/P254
Big Island *(Chesterfield Inlet)*, C6/P131
Big Island *(Hudson Strait)*, C3/P109
Big Island *(James Bay)*, C5/P43
Big Island *(Ungava Bay)*, C1/P72
Big Owl Creek, C5/P156
Big Piskwanish Point, C5/P186
Big Pod Rock, C7/P27
Big Point, C6/P189
Big Swallow Hill, C6/P220
Big Willow River, C5/P170
Bilge Rocks, C3/P19
Bill of Portland Island, C4/P286
Bird Cove, C7/P147
Bird Islands, C8/P119
Bittern, Îlot, C1/P162
Black Bear Point, C5/P128
Black Bluff, C3/P44
Black Bluff Island, C3/P90
Black Boulder Point, C6/P121
Black Duck River, C7/P207
Black Island *(Grimmington Bay)*, C5/P48
Black Island *(La Grande Rivière)*, C5/P31
Black Rock *(Deception Bay)*, C2/P157
Black Rock *(Duke of York Bay)*, C8/P69
Black Rock *(Hopes Advance Bay)*, C1/P184
Black Rocks Point, C6/P115
Black Stone Bay, C5/P75
Black Whale Harbour, C4/P312
Black Whale Island, C5/P46
Blake Bay, C8/P123
Blandford Bay, C3/P131
Blind Reef, C1/P126
Blind Rock, C5/P18
Blocked Passage, C4/P180
Bluegoose Prairie, C9/P87
Bluegoose River, C9/P87
Bluff, Pointe, C1/P151
Bluff, The, C4/P177
Bluff Island, C4/P122
Bluhme Island, C8/P90
Boas River, C6/P61
Boat Cove, C2/P75
Boat Island, C5/P28
Boat Opening, C4/P289
Boat Passage, C5/P124
Boatswain Bay, C5/P103
Boatswain Island, C3/P15
Bois Brûlé, Pointe du, C5/P125
Bold Point *(Chesterfield Inlet)*, C6/P174
Bold Point *(King George Archipelago)*, C2/P120
Bombardier, Plage du, C2/P166
Bond Inlet, C3/P72
Boniface, Rivière, C4/P239
Bonnard, Baie de, C1/P201
Bonney Island, C3/P135
Booth Island, C4/P93
Borden River, C8/P152
Borealis Reef, C6/P197
Borel, Rivière, C1/P200
Bosanquet Harbour, C3/P112
Bossard Island, C5/P124
Bosuns Reef, C1/P128
Boucher, Pointe, C4/P105
Boucherville, Port de, C3/P189
Boulder, Baie, C1/P145
Boulder Island, C6/P143
Boule, Cap la, C2/P75
Boule, La, C2/P75
Bourjoli, Pointe, C4/P105
Bourlamaque, Pointe, C5/P69
Bouverie Islands, C9/P265
Bowdoin Point, C9/P153
Bowell Islands, C6/P201
Bowman Bay, C9/P87
Bowser Island, C6/P186
Bowser Point, C6/P244
Bradbury Island, C4/P197
Brae Island, C5/P46
Brant Island, C6/P197
Brant Island Channel, C6/P197
Bray Inlet, C1/P31
Bray Island, C9/P188
Breaker Shoal, C4/P125
Breakwater, Pointe, C1/P187
Brewer Bay, C3/P33
Broadback, Rivière (River), C5/P127
Broad River, C7/P185
Brochant, Baie, C1/P202
Brochant, Rivière, C1/P202
Broken Islands, C7/P21
Bronson Island, C4/P93
Brooks Bluff, C8/P93
Broomfield Island, C4/P218
Broughton Island *(Nastapoka Islands)*, C4/P242
Bruce Harbour, C3/P85
Buff Island, C7/P56
Bun Island, C4/P186
Bunting Island, C7/P41
Burgoyne Bay, C2/P55
Burial Point, C6/P220
Burnt Island, C5/P46
Burpee, Cape, C9/P197
Bursting Brook, C6/P26
Burwash Point, C4/P191
Burwell, Port, C1/P20
Bury Cove, C8/P182
Bush Island, C1/P12
Bushnan, Cape, C9/P182
Bushnan Island, C8/P90
Bushnan Rock, C9/P184
Bushy Island, C5/P205
Buteo, Pointe, C2/P45
Butler Island, C5/P205
Button Bay, C7/P137
Buttress Island, C1/P181
Buttress Islands, C7/P29
Bylot, Cape, C8/P62

Cabbage Willows Bay, C5/P130
Cachechu, Pointe, C5/P137
Cairn, Île, C4/P75
Cairn Cove, C4/P26
Cairn Islet, C2/P120
Cairns, Isle of, C7/P19
Cake Island, C4/P186
Calanus Bay, C6/P17
Camp Bay, C6/P232
Camp Cove Island, C6/P131
Camp Islands, C4/P221
Camp Islet, C6/P232
Camsell Island, C4/P231
Canon, Pointe au, C4/P246
Canon Inlet, C3/P126
Cantley, Pointe (Point), C2/P96
Canyon River, C8/P61
Cap Aupartuapik, C2/P175
Cap (Cape) Hopes Advance, C1/P251
Cap (Cape) William-Smith, C1/P18
Cap Colmer, C3/P116
Cap Dalmas, C2/P187
Cap Daulat, C2/P170
Cap De Châteauguay, C2/P187
Cap de Nouvelle-France, C2/P141
Cap du Long-Sault, C2/P170
Cap du Prince-de-Galles, C2/P65
Cape Acadia, C4/P14
Cape Alberta, C9/P85
Cape Baffin, C8/P86
Cape Bartlett, C4/P188
Cape Bazin, C9/P187
Cape Burpee, C9/P197
Cape Bushnan, C9/P182
Cape Bylot, C8/P62
Cape Churchill, C7/P138
Cape Clarke, C8/P90
Cape Comfort, C8/P29
Cape Deas, C8/P79
Cape Digges, C2/P193
Cape Dobbs, C8/P160
Cape Dominion, C9/P88
Cape Donovan, C8/P23
Cape Dorchester, C8/P53
Cape Dorset, C3/P149
Cape Dorset *(community)*, C3/P157
Cape Dorset Harbour, C3/P153
Cape Dufferin, C4/P113
Cape Duncan, C5/P158
Cape Edwards, C8/P105
Cape Elwyn, C9/P116
Cape Enauolik, C8/P43
Cape Englefield, C9/P295
Cape Fisher *(Southampton Island)*, C8/P20
Cape Fisher *(Winter Island)*, C8/P117
Cape Frigid, C8/P83
Cape Fullerton, C6/P64
Cape Griffith, C9/P270
Cape Hallowell, C9/P289
Cape Henrietta Maria, C5/P143
Cape Hope, C8/P190
Cape Hope Islands, C5/P83
Cape James, C3/P136
Cape Jensen, C9/P130
Cape Jermain, C9/P17

C = Chapter/P = Paragraph

Cape Jones, C7/P69
Cape Jones Island, C4/P330
Cape Kendall *(south coast Southampton Island)*, C6/P62
Cape Ketoria, C9/P84
Cape Konig, C9/P114
Cape Lamprenen, C9/P118
Cape Lilly, C9/P277
Cape Lindenwald, C9/P182
Cape Lookout, C7/P227
Cape Low, C6/P23
Cape Martineau, C8/P105
Cape Matthew Smith, C9/P57
Cape McLaren, C8/P102
Cape Merry, C7/P149
Cape Montagu, C8/P93
Cape Montague, C8/P179
Cape Moses Oates, C2/P143
Cape Munn, C8/P145
Cape Netchek, C6/P18
Cape Novoa, C3/P88
Cape Ossory, C9/P278
Cape Pembroke, C4/P23
Cape Penrhyn, C9/P13
Cape Prefontaine, C6/P14
Cape Prince of Wales, C2/P65
Cape Queen, C8/P41
Cape Reid, C8/P106
Cape Robert Brown, C9/P16
Cape Sadlek, C9/P183
Cape Shackleton, C8/P90
Cape Silumiut, C6/P77
Cape Smith, C4/P39
Cape Southampton, C4/P32
Cape Tanfield, C3/P86
Cape Tatnam, C7/P203
Cape Thalbitzer, C9/P127
Cape Tordenskjold, C9/P287
Cape Warwick, C3/P32
Cape Welsford, C8/P65
Cape Weston, C8/P50
Cape Weymouth, C3/P85
Cape Wight, C3/P94
Cape Willingdon, C3/P143
Cape Willoughby, C9/P78
Cape Wilson, C8/P129
Cap Fox, C1/P148
Cap Halfway, C1/P148
Cap Hébert, C2/P185
Cap Inuksutujuq, C1/P77
Cap Jagged, C2/P18
Cap Kattaktoc, C1/P32
Cap Kattatuuq, C1/P39
Cap Kernertut, C1/P67
Cap la Boule, C2/P75
Cap La Potherie, C2/P96
Cap Neptune, C2/P62
Cap Nuvukallak, C1/P50
Cap Pain, C2/P19
Cap Qairtualuk, C1/P50
Cap Sarvak, C1/P211
Cap Siakkaaluk, C2/P212
Cap Siukkaaluk, C2/P212
Captain Island, C4/P110
Cap Tavernier, C2/P185
Cap Valets, C2/P172
Cap Whales, C1/P106
Cap Wolstenholme, C2/P191
Careenage Arm, C2/P160
Carew Bay, C3/P86
Carey Island, C5/P110
Caribou Island *(Foxe Channel)*, C8/P18
Caribou Island *(James Bay)*, C5/P24
Caribou River, C7/P131
Caroline Island, C5/P103
Carys Swan Nest, C4/P29
Castle, Presqu'île, C4/P280
Castle Island, C4/P286
Castor, Rivière au (du), C5/P46
Catherine Bay, C3/P146
Caution Point, C6/P240
Caution Shoals, C1/P80
Central Hill, C1/P241
Centre Island, C6/P135
Chain Islet, C6/P244
Chalmers Island, C2/P97
Chamberlain Island, C3/P135
Channel Rock, C2/P157
Chapel, Colline, C1/P108
Charles Bay, C2/P148
Charles Inlet, C2/P146
Charles Island *(Hudson Strait)*, C2/P143
Charles Island *(James Bay)*, C5/P205
Charlton Depot, C5/P112
Charlton Harbour, C5/P112
Charlton Island, C5/P107
Chaunsler, Mount, C3/P89
Checkered Islands, C4/P105
Chenal Nakirtuq, C1/P222
Chesterfield Anchorage, C6/P96
Chesterfield Inlet, C6/P79
Chesterfield Inlet *(hamlet)*, C6/P97
Chesterfield Narrows, C6/P220
Cheyne Point, C8/P93
Chickney Channel, C5/P172
Chien Rouge, Rivière au, C1/P186
Chimo, Fort, C1/P112
Chisasibi, C5/P37
Chiyask Bay, C5/P138
Chiyask Point, C5/P138
Chorkbak Inlet, C3/P137
Chrissie Thomey Passage, C5/P122
Christie Island, C4/P250
Christopher Inlet, C1/P31
Christopher Island, C6/P230
Christopher Rocks, C6/P142
Chudliasi Bay, C3/P128
Chukotat, Rivière, C4/P56
Churchill *(community)*, C7/P180
Churchill *(Port of)*, C7/P175
Churchill, Cape, C7/P138
Churchill Harbour, C7/P149
Churchill River, C7/P149
Churchill Rocket Research Range, C7/P181
Churchill Shoals, C7/P142
Churchill Sound, C4/P176
Clarke, Cape, C8/P90
Clarke Island, C4/P265
Clarke Sound, C9/P213
Clark Island, C5/P173
Claw Point, C4/P180
Claw Rock, C2/P32
Clay Island, C6/P94
Clay Point, C9/P165
Clear Water River, C6/P253
Cleft Island, C2/P127
Clergue, Rivière, C5/P73
Cleveland Harbour, C8/P191
Cleveland River, C8/P72
Clutterbuck Head, C1/P241
Coates Inlet, C1/P31
Coats Bay, C4/P177
Coats Island, C4/P22
Cockade Island, C3/P17
Cockispenny Point, C5/P186
Cockram Strait, C9/P112
Coffin Islet, C1/P182
Colbert, Promontoire, C2/P186
Colline Alakakvik, C1/P208
Colline Apex, C1/P185
Colline Chapel, C1/P108
Colline Inuksulik, C1/P68
Colline Qikirtaujaq, C1/P52
Colline Sherrick, C5/P114
Collines Jagged, C2/P18
Colmer, Cap, C3/P116
Comb Islands, C5/P46
Comer Strait, C8/P74
Comfort, Cape, C8/P29
Commodore Island, C4/P110
Cône, Île en, C1/P162
Cone Hill, C6/P212
Cone Island, C1/P174
Congnarauya Point, C1/P75
Conn River, C5/P88
Consolation, Pointe de la, C5/P130
Conway Point, C6/P161
Cook Bay, C3/P28
Cook Passage, C3/P23
Copper, Pointe, C1/P160
Copperneedle River, C7/P103
Copter Island, C1/P161
Coral Harbour, C6/P49
Coral Harbour *(hamlet)*, C6/P50
Corbett Inlet, C7/P70
Cormorant Rock, C5/P103
Corridor Shoal, C7/P82
Cory Bay, C9/P85
Cotter Island, C4/P238
Cotter Point, C5/P53
Coutlée, Pointe, C4/P62
Coxe Islands, C9/P57
Cox Inlet, C1/P31
Cox Island, C4/P110
Crag Rock, C7/P37
Crane Island, C7/P19
Crawford Island, C8/P118
Crooks Inlet, C3/P116
Cross Bay, C6/P195
Cross Bay Channel, C6/P198
Crozier River, C9/P57
Culgruff Inlet, C8/P109
Cur Island, C7/P38
Curran Island, C4/P260
Cusson, Pointe, C4/P59
Cutaway Channel, C5/P173

**D**'Aeth Point, C1/P241
Dalmas, Cap, C2/P187
Daly Bay, C6/P69
Danby Island, C5/P112
Dangerous Point, C6/P141
Danger Passage, C3/P22
Danish Island, C8/P86
Dark Island, C2/P112
Dark Point, C7/P33
Daryl Rock, C2/P79

C = Chapter/P = Paragraph

Daulat, Cap, C2/P170
Davieau Island, C4/P248
Davies Island, C2/P139
Davis Inlet, C1/P31
Dawson Inlet, C7/P103
Dead Duck Bay, C5/P44
Deadman Island, C7/P15
Dean Islet, C6/P240
Deas, Cape, C8/P79
Déception, C2/P166
Deception, Rivière, C2/P151
Deception Bay, C2/P151
Deceptive Bay, C6/P232
De Châteauguay, Cap, C2/P187
Deer Island *(Chesterfield Inlet)*, C6/P131
Deer Island *(Foxe Basin)*, C9/P120
Deer Island Channel, C6/P135
De Martigny, Promontoire, C2/P137
Demers, Pointe, C4/P57
Demon Point, C6/P117
Deposit Cove, C4/P223
Depot Island, C6/P76
De Rozière, Baie, C1/P248
Desgoffe Point, C4/P191
Despins, Pointe, C4/P106
Detroit Island, C1/P144
De Villiers, Anse, C1/P175
De Villiers, Pointe, C1/P175
Diamond Islands, C3/P136
Diana Bay, C2/P3
Diana Island, C2/P21
Diana River, C7/P29
Digges, Cape, C2/P193
Digges, Passe (Sound), C2/P201
Digges Harbour, C2/P199
Digges Islands, C2/P193
Digges Islet, C2/P195
Dixon Island, C5/P120
Dobbs, Cape, C8/P160
Doctor Island, C2/P68
Dog Island, C2/P18
Dôme, Le, C2/P173
Dome Island, C1/P134
Dome Islet, C2/P203
Dominion, Cape, C9/P88
Donovan, Cape, C8/P23
Dorchester, Cape, C8/P53
Dorchester Bay, C9/P78
Dorset, Cape, C3/P149
Dorset Island, C3/P149
Double Island *(King George Archipelago)*, C2/P117
Double Island *(Loon Islands)*, C5/P20
Douglas Harbour *(Hudson Strait)*, C2/P129
Douglas Harbour *(Wager Bay)*, C8/P169
Douglas Islet, C2/P131
Douglas Rock, C2/P131
Dove Island, C4/P199
Draulette Island, C5/P124
Drayton Island, C4/P143
Driftwood Island, C4/P159
Dry Bay, C1/P248
Dry Cove, C7/P22
Duchesnau, Pointe, C2/P28
Duckett Cove, C8/P94
Duck Island *(Middle Savage Islands)*, C3/P71
Duck Island *(SE coast Hudson Bay)*, C4/P284
Duckling Island, C5/P24
Dufferin, Cape, C4/P113
Dufourmentel Rocks, C5/P120
Dufrost, Pointe, C4/P65
Duke of York Bay, C8/P66
Duncan, Cape, C5/P158
Duncan Island, C6/P189
Duncan Passage, C5/P198
Dunne Foxe Island, C7/P71
Dunne Foxe Shoal, C7/P73
Dunne River, C8/P46
Dunn Point, C9/P163
Dwarf Island, C3/P10
Dybbol Harbour, C9/P290

**E**arthquake Island, C5/P44
East Bar, C5/P189
East Bay, C8/P18
East Bluff, C3/P60
East Cape, C9/P293
East Channel *(Deception Bay)*, C2/P156
East Channel *(Murray Maxwell Bay)*, C9/P124
East Cove, C2/P170
East Cub Island, C5/P12
Eastern Passage, C2/P24
Eastmain, C5/P98
Eastmain River, C5/P90
East Mussel Island, C2/P43
East Pen Island, C7/P208
East Point *(Chesterfield Inlet)*, C6/P156
East Point *(Hannah Bay)*, C5/P139
Écueils, Pointe aux, C4/P65
Edaloh Inlet, C3/P181
Eddy Island, C4/P96
Eddy Point, C6/P216
Edge, Île, C1/P97
Edgell Island, C3/P44
Edwards, Cape, C8/P105
Eegaiyo, C3/P99
Eegatuak Hill, C3/P149
Egg Island, C7/P128
Egg River, C7/P128
Egg Rock, C5/P14
Eider Island, C6/P164
Eider Islands, C1/P250
Ejooreeta, C3/P95
Ekatuvik Point, C6/P148
Ekkik Cove, C2/P29
Elbow, Grande île, C1/P109
Elbow, Petite île, C1/P109
Elbow, The *(Moose River)*, C5/P189
Elbow, The *(Rivière Koksoak)*, C1/P109
Elder Island, C9/P275
Elder Point, C9/P174
Elizabeth, Point, C8/P127
Elizabeth Bank, C8/P9
Elizabeth Reef, C8/P9
Ell Bay, C8/P141
Ellis Island, C6/P115
Elsie Island, C4/P108
Elson, Pointe, C1/P40
Elwyn, Cape, C9/P116
Emelia Passage, C5/P119
Emily Rock, C5/P55
Emma Island, C3/P124
Enauolik, Cape, C8/P43
Englefield, Cape, C9/P295
Entrance, Pointe (Point), C1/P218
Entrance Island, C2/P130
Entry Islands, C3/P15
Enukso Point, C8/P40
Ephemeral Cove, C6/P121
Eqe Bay, C9/P141
Era Island, C9/P150
Erik Cove, C2/P187
Escarpement Eyrie, C2/P9
Escarpement Tryon, C1/P175
Esker Island, C7/P42
Eskimo Harbour, C4/P179
Eskimo Island, C7/P149
Eskimo Point *(Arviat)*, C7/P115
Eskimo Point *(Churchill)*, C7/P149
Eskimo Point *(community)*, C7/P118
Etuksit Point, C6/P195
Evans Strait, C6/P10
Eveeska, C3/P93
Ewerat Point, C9/P166
Expectation Point, C6/P7
Eyrie, Escarpement, C2/P9

**F**ace Channel, C4/P214
Fafard Island, C5/P173
Fair Island, C4/P228
Fair Ness, C3/P129
Fairway Island *(Algerine Channel)*, C4/P124
Fairway Island *(Chesterfield Inlet)*, C6/P86
Fairway Island *(Passe Digges)*, C2/P203
Fairway Shoals, C7/P25
Fairweather Harbour, C4/P229
Fairweather Sound, C4/P227
Falcon Anchorage, C1/P135
Falcon Strait, C8/P69
False, Pointe, C1/P140
False, Rivière, C1/P74
False Bight, C1/P200
False Cove, C2/P158
False Inlet, C6/P115
False Islet, C1/P140
False Knoll, C7/P22
False Passage, C2/P155
Falstaff Island, C7/P22
Farhill Point, C8/P102
Farley Point, C9/P86
Farmer Island, C4/P99
Farther Hope Point, C6/P158
Fat, Île, C4/P75
Fee Peninsula, C9/P112
Fer, Pointe au, C1/P146
Ferguson River, C7/P100
Feuilles, Lac aux, C1/P130
Feuilles, Passage aux, C1/P130
Feuilles, Rivière aux, C1/P171
Fife Point, C9/P174
Fife Rock, C8/P8
Figgures Point, C9/P93
Fingernail Island, C2/P27
Finger Point *(Chesterfield Inlet)*, C6/P96
Finger Point *(Longstaff Bluff)*, C9/P230
Finnie Bay, C8/P48
Fish, Pointe, C4/P74
Fish Bay *(Ranger Seal Bay)*, C6/P143
Fish Bay *(Sakpik Bay)*, C6/P92
Fisher, Cape *(Southampton Island)*, C8/P20
Fisher, Cape *(Winter Island)*, C8/P117
Fisher Bay, C2/P95
Fisher Harbour, C3/P114
Fisher Rock, C2/P102

C = Chapter/P = Paragraph

Fisher Strait, C6/P23
Fist Point, C7/P31
Five-Hawser Bay, C8/P114
Five Islands, C1/P236
Five Mile Inlet, C4/P111
Flagstaff Point, C7/P221
Flaherty Island, C4/P177
Flamborough Head, C7/P194
Flat, Pointe, C1/P140
Flat Island *(Diana Bay)*, C2/P22
Flat Island *(Killiniq Island)*, C1/P12
Flat Island *(King George Archipelago)*, C2/P124
Flat Point, C6/P191
Flattop Island, C7/P96
Flint Island, C4/P274
Flock Geese Islands, C5/P91
Floe Bay, C9/P86
Foley Island, C9/P206
Forbes Sound, C1/P18
Ford, Île, C1/P62
Ford, Pointe (Point), C2/P84
Ford Channel, C2/P172
Ford Island, C2/P29
Ford Lake, C8/P175
Ford River, C6/P49
Foreman Island, C2/P145
Fort Albany, C5/P184
Fort Chimo, C1/P112
Fort-George, C5/P36
Fort George, C5/P36
Fort George, Île de, C5/P36
Fort George Anchorage, C5/P26
Fort Hope, C8/P190
Fort Prince of Wales, C7/P149
Fort-Rupert, C5/P133
Fort Severn, C7/P215
Foster Bay, C9/P49
Fougère Rouge, Pointe de la, C5/P136
Foul Bay, C2/P138
Foul Passage, C3/P7
Four Steps Hill, C4/P188
Fox, Cap, C1/P148
Foxe Basin, C9/P1
Foxe Channel, C8/P1
Foxe Peninsula *(SE coast)*, C3/P139
Fox Harbour, C1/P15
Fox Islands, C7/P144
Fox Trap Island, C6/P92
Fraley Island, C4/P126
Fraser Island, C3/P183
Frazier Island, C4/P143
Freakly Point, C4/P208
Fredericks Island, C5/P122
Freuchen Bay, C8/P129
Freuchen Point, C9/P282
Friday Point, C9/P278
Frigid, Cape, C8/P83
Frontenac, Pointe, C2/P60
Frozen Strait, C8/P55
Frustration Point, C9/P170
Fullerton, Cape, C6/P64
Fullerton Harbour, C6/P67
Funnel Cove, C1/P185
Fury and Hecla Strait, C9/P238

**G**able, Pointe, C1/P183
Gabriel Strait, C3/P45
Garnet Bay, C9/P83
Garnet Island, C8/P90
Garnier, Ruisseau, C1/P249
Garry, Pointe, C1/P148
Gasket Island, C5/P160
Gasket Rock, C5/P155
Geillini River, C7/P127
George, Rivière (River), C1/P37
George Bay *(Markham Bay)*, C3/P131
George Bay *(Pointe Louis-XIV)*, C4/P329
Georgina Island, C8/P93
Gibbons Point, C6/P60
Gibson Bay, C9/P81
Gibson Cove, C8/P190
Gibson Peninsula, C4/P212
Gifford Fiord, C9/P272
Gifford River, C9/P272
Gillam, Pointe (Point) , C2/P111
Gillian, Lake, C9/P146
Gillies Island *(Grande rivière de la Baleine)*, C4/P291
Gillies Island *(Nastapoka Islands)*, C4/P258
Gilmour Island, C4/P94
Gilmour Peninsula, C4/P191
Glasgow Bay, C3/P94
Glasgow Falls, C3/P99
Glasgow Inlet, C3/P99
Glasgow Island, C3/P95
Glencoe Island, C3/P126
Gobin, Île, C4/P54
Goddard Island, C1/P26
God's Mercie, Islands of, C3/P132
Gods Mercy, Bay of, C6/P60
Goose Bay, C5/P8
Gooseberry Brook, C7/P217
Goose Creek, C7/P217
Goose Islands, C5/P48
Gorden Bay, C8/P13
Gordon Island, C4/P255
Gordon Point, C7/P140
Gordon River, C8/P158
Gore Bay, C8/P103
Gore Point, C8/P15
Goulet, Le, C4/P277
Governor Island, C5/P32
Goyeau, Pointe, C5/P114
Grande île Elbow, C1/P109
Grande Ravine, La, C1/P147
Grande Rivière, La, C5/P31
Grande rivière de la Baleine, C4/P296
Grant-Suttie Bay, C9/P137
Grass Island, C5/P24
Gravel Islets, C7/P33
Gravell Point, C9/P109
Grave, Pointe, C2/P43
Grave Point, C2/P43
Graves Strait, C3/P43
Gray Goose Islands, C3/P75
Gray Strait, C1/P12
Great Plain of the Koukdjuak, C9/P88
Grebe Point, C6/P230
Grebe Shoals, C6/P231
Green Point, C8/P40
Gregson Inlet, C1/P31
Grey Goose Island, C5/P9
Griffith, Cape, C9/P270
Griffiths Bay, C9/P291
Grimmington Bay, C5/P48
Ground Squirrel Island, C7/P29
Guard Rock, C6/P55
Guillaume, Rivière, C5/P8
Guillaume-Delisle, Lac, C4/P276
Guillemot Bank, C7/P37
Guillemot Island, C7/P37
Guillemot Rocks, C7/P37
Guillemot Shoal, C1/P207
Guindon, Île, C1/P249
Gull Bay, C5/P138
Gullery Island, C5/P158
Gull Island, C5/P84
Gull Point, C5/P138
Gushie Point, C4/P189
Gushue Island, C5/P120
Gutway, The, C5/P173
Gyrfalcon Islands, C1/P133

**H**alfway, Cap, C1/P148
Halfway Point *(approaches to Churchill)*, C7/P144
Halfway Point *(James Bay)*, C5/P186
Hall Bay, C2/P17
Hall Beach, C9/P27
Hall Beach *(hamlet)*, C9/P48
Hall Cove, C5/P125
Hallé Rock, C5/P124
Hall Islands, C8/P191
Hall Lake, C9/P23
Hallowell, Cape, C9/P289
Hall Point, C9/P28
Hanbury Island, C6/P117
Handkerchief Inlet, C8/P166
Handkerchief Point, C8/P162
Hannah Bay, C5/P139
Hannah Island, C2/P22
Hantzsch Bay, C9/P96
Hantzsch River, C9/P96
Harbour Bay, C9/P140
Harbour Islands, C8/P192
Harder River, C9/P132
Hare Islet, C3/P82
Harkin Bay, C8/P42
Harlequin Rock, C2/P41
Harp Cove, C1/P240
Harp Rock, C7/P37
Harricanaw River, C5/P139
Harrison Island, C4/P124
Hatton Headland, C3/P4
Haven Island, C3/P10
Haviland Bay, C8/P191
Hayes River, C7/P197
Hazy Islet, C7/P7
Headwind Point, C6/P155
Hearn Island, C2/P9
Hébert, Cap, C2/P185
Hector Island, C3/P132
Heel, The, C3/P100
Heel Cove, C2/P47
Hélicoptère, Île de l', C1/P161
Helicopter Island, C6/P195
Helix Point, C6/P258
Hell Gate, C7/P81
Hell Point, C1/P241
Helmet, The, C2/P132
Hen and Chicks, C3/P17
Henderson, Point, C8/P73
Henderson, Pointe, C1/P142
Henderson Harbour, C3/P115
Hendry, Île, C1/P103
Henrietta Maria, Cape, C5/P143

C = Chapter/P = Paragraph

Héricart, Baie, C2/P54
Héron, Pointe au, C5/P49
Hettash Island, C1/P12
Hidden Rock, C7/P22
Hiding Rock, C5/P18
High Bluff Island, C3/P87
High Rock Island, C5/P88
Hillock Islet, C7/P52
Hobart Island, C3/P135
Hook Island, C5/P46
Hook Point, C5/P146
Hooper Inlet, C9/P56
Hope, Cape, C8/P190
Hopes Advance, Cap (Cape), C1/P251
Hopes Advance Bay, C1/P177
Hopewell Islands, C4/P115
Hopewell Narrows, C4/P127
Hopewell Sound, C4/P115
Hoppner Inlet, C8/P107
Hoppner Strait, C8/P119
Horizon Islands, C6/P187
Hornet Point, C6/P262
Horseshoe Deep, C7/P33
Horseshoe Islands, C5/P205
Horseshoe Shoals, C5/P206
Hotchkiss Island, C4/P143
House Island, C4/P96
Houston Point, C5/P158
Howard Peninsula, C4/P177
Howard Point, C4/P177
Huard, Pointe au, C5/P49
Hubbard, Pointe, C1/P33
Hubbart Point, C7/P131
Hudson Bay, C4/P1
Hudson Strait, C1/P1
Hump Island, C7/P52
Hurd Channel, C8/P92
Hurin Throughlet, C3/P170
Husky Island, C4/P158
Hut Point, C6/P26

**I**ceberg Shoal, C2/P24
Ice Breaker Islet, C6/P220
Ice Breaker Point, C6/P220
Ice Cutter Point, C6/P220
Ice Harbour, C4/P6
Ice Hunter Rock, C6/P211
Igloo, Pointe de l' (Point) *(Bassin Payne)*, C1/P225
Igloo Island, C2/P43
Igloolik *(hamlet)*, C9/P68
Igloolik Island, C9/P59
Igloo Point *(Pork Peninsula)*, C7/P70
Iglujat Hills, C6/P262
Iglukjuak Point, C3/P146
Ignerit Point, C9/P137
Ignertok Point, C9/P20
Ijjurittiak Island, C3/P95
Ikalupilinak Point, C6/P121
Ikattok Bay, C1/P174
Ikerasak River, C9/P23
Ikpik Bay, C9/P145
Ikpik River, C9/P146
Iktotat, Rivière, C4/P57
Ikuma Bay, C9/P272
Île Bar, C1/P109
Île Basking, C1/P225
Île Big *(Rivière de Puvirnituq)*, C4/P75
Île Cairn, C4/P75
Île de Fort George, C5/P36
Île de l'Hélicoptère, C1/P161
Île Edge, C1/P97
Île en Cône, C1/P162
Île Fat, C4/P75
Île Ford, C1/P62
Île Gobin, C4/P54
Île Guindon, C1/P249
Île Hendry, C1/P103
Île Illutalialuk, C2/P43
Île Inussuliapik, C4/P75
Île Lemoine, C5/P127
Île Lodestone, C1/P223
Île Mackays, C1/P103
Île Middleton, C5/P127
Île Midway, C1/P109
Île Pakkivik, C1/P103
Île Pikiulirjuakallak, C1/P222
Île Qikirtaapik, C2/P159
Île Qirnilik, C1/P169
Île Rowe, C1/P165
Îles Arvalik, C1/P66
Îles Naujakallak, C1/P47
Îles Nauyut, C1/P66
Îles Radisson, C1/P159
Îles Smoky, C1/P142
Îlets Sitamat, C1/P221
Iligliak Point, C9/P28
Illukotat, Rivière, C4/P51
Illukuluttalik, Pointe, C1/P110
Illusion Sound, C1/P203
Illusive Islands, C6/P130
Illutalialuk, Île, C2/P43
Îlot Bittern, C1/P162
Îlot Irqituq, C1/P145
Îlot Mandarin, C1/P163
Îlot Poly, C1/P163
Imarujuk Island, C9/P137
Imiligaarjuk Island, C7/P102
Imilijjuaq Island, C7/P102
Imiliq Island, C9/P137
Imilit Islands, C6/P126
Imnak Island, C2/P29
Index Point, C9/P230
Inenew Passage, C5/P128
Ingilik Point, C6/P258
Inman Island, C4/P110
Innelatevik Island, C4/P74
Inner Flock Geese Islands, C5/P93
Innetalling Island, C4/P218
Inniq Point, C9/P144
Innuksuac, Rivière, C4/P129
Inooksulik Island, C4/P72
Inoucdjouac, C4/P134
Inuit Islet, C3/P78
Inukjuak, C4/P134
Inuksulik, Colline, C1/P68
Inuksutujuq, Cap, C1/P77
Inukuk Point, C6/P121
Inussuliapik, Île, C4/P75
Ippijjuaq Bay, C6/P210
Iqaijuq Cove, C3/P99
Irik Island, C7/P81
Iripajuk Island, C6/P130
Iron Shoal, C1/P149
Irqituq, Îlot, C1/P145
Irving Bay, C3/P117
Iserhoff Island, C5/P180
Iskoyaskweyau Point, C5/P139
Island, Detroit, C1/P144
Islands of God's Mercie, C3/P132
Isle of Cairns, C7/P19
Isortoq Fiord, C9/P137
Iterdlak Bay, C8/P158
Itijjagiaq Trail, C3/P106
Itittaviit Islands, C1/P122
Itivirk Bay, C3/P89
Ivaluarjuk Island, C8/P89
Ivik Island, C1/P203
Ivisaat Island, C3/P93
Ivugivik Harbour, C2/P213
Ivujivik, C2/P215
Ivujivik, Pointe d', C2/P213
Ivuniraarjuq Island, C7/P102

**J**ackson Island, C1/P15
Jacob Island, C5/P117
Jaeger Point, C6/P84
Jagged, Cap, C2/P18
Jagged, Collines, C2/P18
James Bay, C5/P1
James, Cape, C3/P136
James Point, C6/P250
Jauge, Pointe de la, C1/P161
Jean-Talon, Pointe, C2/P3
Jeffers Islet, C6/P250
Jensen, Cape, C9/P130
Jens Munk Island, C9/P114
Jermain, Cape, C9/P17
Jessiman Islet, C6/P244
J. Gordon Island, C4/P95
Jigging Point, C6/P257
Johnnys Island, C4/P228
Johnson Island, C4/P173
Johnston Cove, C7/P42
Jolicoeur, Rivière, C5/P102
Jolly Islands, C5/P126
Jones, Cape, C7/P69
Josephine River, C7/P3
Joy Bay, C2/P60
Jubilee Island, C3/P136
Juet Island, C3/P86
Julian Point, C3/P136
Junction Bay, C6/P7

**K**abiskaubakau River, C5/P186
Kakachischuan, Pointe, C5/P7
Kakachischuane, Pointe, C5/P7
Kakago Island, C5/P180
Kakassitug, Pointe, C5/P7
Kamarvik Creek, C8/P159
Kamarvik Harbour, C8/P159
Kamik Bay, C2/P45
Kanangnaaqslirjuaq Island, C6/P248
Kangiqsualujjuaq, C1/P57
Kangiqsujuaq, C2/P85
Kangirsuk, C1/P234
Kango Island, C7/P52
Kanik, Anse (Cove), C1/P226
Kapiskau River, C5/P170
Kapitattalik, Pointe, C1/P48
Kapsaouis, Rivière, C5/P6
Karlay Island, C4/P197
Kasegalik Lake, C4/P208
Kasegalik River, C4/P208
Kashechewan, C5/P184
Kaskattama River, C7/P207
Kattaktoc, Cap, C1/P32

C = Chapter/P = Paragraph

Kattatuuq, Cap, C1/P39
Kayak Island, C7/P81
Kazan River, C6/P253
Keeka Hill, C9/P86
Keglo Bay, C1/P34
Kelp Rock, C7/P37
Keltie Inlet, C3/P136
Kendall, Cape *(south coast Southampton Island)*, C6/P62
Kennedy, Pointe, C1/P168
Kennedy Point, C6/P235
Kernertut, Cap, C1/P67
Kesagami River, C5/P139
Ketoria, Cape, C9/P84
Kettle River, C7/P207
Kettlestone Bay, C4/P35
Ketyet River, C6/P257
Khemig Island, C9/P57
Kidlikpait Islet, C1/P203
Kidlikpait Reefs, C1/P203
Kidney Island, C4/P153
Kihl Bay, C4/P214
Kikkerteluc, Rivière, C4/P148
Kikkertoksoak Islands, C1/P34
Killinek Island, C1/P12
Killiniq Island, C1/P12
Kimmirut, C3/P105
Kinak Island, C2/P16
Kind Islet, C7/P21
Kingatnaaq Hill, C6/P256
King Charles Cape, C3/P166
King George Archipelago, C2/P114
King George Islands, C4/P156
King George Sound, C2/P125
Kingmitokvik Point, C9/P29
Kingnait, C3/P157
Kingnait Hill, C3/P156
Kingnait Range, C3/P155
Kingnektak Island, C2/P29
Kinoje River, C5/P186
Kinosheo River, C5/P186
Kinushseo River, C7/P229
Kipalu Inlet, C4/P213
Kirchoffer River, C6/P40
Kisarvik, Pointe, C1/P99
Kitdliat Islet, C1/P203
Kitdliat Reefs, C1/P203
Kite Island, C9/P23
Kit Island, C4/P119
Knife Delta, C7/P136
Knight Harbour *(Hudson Bay, east coast)*, C4/P54
Knight Harbour *(Marble Island)*, C7/P15
Knights Hill, C7/P146
Knob Hill, C6/P235
Knoll, The, C7/P134
Koartac, C2/P13
Koch Island, C9/P187
Kogaluc, Lac, C4/P66
Kogaluc, Rivière, C4/P66
Kogaluk, Ruisseau, C2/P34
Kogaluk Bay, C4/P105
Kokittwa Hill, C9/P86
Koksoak, Rivière (River), C1/P79
Koktac, Rivière, C4/P106
Kokumiak Harbour, C8/P28
Komaluk Islands, C4/P108
Kommanik River, C9/P81
Kongut, Rivière, C4/P127
Konig Cape, C9/P114
Kootyuk Point, C9/P165
Korak, Rivière, C4/P58
Korak Bay, C4/P58
Koroc, Rivière, C1/P39
Korok Inlet, C3/P136
Kotuko Point, C9/P206
Koukdjuak, Great Plain of the, C9/P88
Koukdjuak River, C9/P90
Kovic, Rivière, C4/P11
Kovik Bay, C4/P11
Kresik Island, C7/P38
Kudloovik Point, C1/P235
Kudlulik Peninsula, C7/P31
Kugluk Cove, C2/P183
Kuglukvik Point, C1/P235
Kugong Island, C4/P174
Kuujjaq, C1/P112
Kuujjuaq, C1/P112
Kuujjuarapik, C4/P299
Kuurujjuaq, C1/P48
Kyak Bay, C1/P211

La Boule, C2/P75
Labrador Channel, C9/P181
Lac aux Feuilles, C1/P130
Lac Guillaume-Delisle, C4/P276
Lac Kogaluc, C4/P66
Laddie Harbour, C4/P201
Laddie Island, C4/P173
La Duke Island, C4/P224
La Grande Ravine, C1/P147
La Grande Rivière, C5/P31
Lajus, Pointe, C1/P160
Lake Cove, C2/P49
Lake Gillian, C9/P146
Lake Harbour, C3/P100
Lake Harbour *(community)*, C3/P105
Lakitusaki River, C5/P156
La Longue Pointe, C5/P74
Lamprenen, Cape, C9/P118
Landlocked Harbour, C4/P148
Langley Inlet, C1/P31
Lansdowne, Mount, C3/P131
Lanyard Passage, C3/P15
La Pérouse Bay, C7/P140
Laperrière, Port de, C2/P194
La Petite Ile, C2/P22
La Petite Ravine, C1/P147
La Potherie, Cap, C2/P96
Larch Reef, C3/P93
Latourette, Rivière, C2/P34
Laverock Bay, C4/P307
Lawabiskau River, C5/P186
Lawashi River, C5/P170
Leaf Bay, C1/P130
Le Dôme, C2/P173
Lee Island, C3/P90
Lefaivre Island, C5/P124
Lefroy, Rivière, C1/P201
Leftfoot Islet, C7/P41
Le Goulet, C4/P277
Lemming Island, C6/P174
Lemoine, Île, C5/P127
Le Moyne Passage, C5/P196
Lenz Strait, C1/P12
Leonard Island, C4/P143
Levy Island, C4/P110
Leyson Point, C6/P8
Liddon Island, C9/P282
Lillico Point, C4/P174
Lilly, Cape, C9/P277
Lindenwald, Cape, C9/P182
Linklater Island, C5/P180
Lisbon Rocks, C5/P109
Little Big Island, C6/P164
Little Cape, C7/P229
Little Duck Bar, C5/P207
Little Duck Island, C5/P205
Little Islands, C6/P260
Little Lake Cove, C2/P9
Little Pod Rock, C7/P27
Little Seal River, C7/P133
Lloyd Point *(Foxe Channel)*, C8/P30
Lloyd Point *(Hudson Strait)*, C3/P169
Loaf Island, C4/P186
Lodestone, Île (Island), C1/P223
Lodestone, Récif (Reef), C1/P223
Lofthouse Hill, C6/P253
Lofthouse Point, C6/P253
Lona Bay, C3/P167
London Rock, C6/P144
Lonebutte Bay, C8/P37
Long, Récif, C1/P162
Long Cove, C2/P16
Long Island *(Chesterfield Inlet)*, C6/P195
Long Island *(SE Hudson Bay)*, C4/P318
Long Island Sound, C4/P323
Longland, Rivière, C4/P244
Long Point, C5/P194
Long Reach Island, C4/P69
Longridge Point, C5/P186
Long-Sault, Cap du, C2/P170
Longspur Island, C7/P29
Longstaff Bluff, C9/P224
Longue Pointe, La, C5/P74
Lookout, Cape, C7/P227
Lookout Island, C1/P181
Loon, Pointe (Point), C5/P102
Loon Islands, C5/P20
Lorillard River, C6/P69
Louis-XIV, Pointe, C4/P327
Low, Cape, C6/P23
Lower Savage Islands, C3/P48
Low Inlet, C1/P31
Low Islands, C1/P181
Low Point *(Baker Lake)*, C6/P242
Low Point *(Chesterfield Inlet)*, C6/P167
Lucy Point, C5/P57
Lukisee Islands, C4/P173
Lunan Point, C6/P249
Luttit Island, C4/P266
Lyon Inlet, C8/P104
Lyon Rocks, C3/P71

Macdonald Island, C3/P132
Mackay Bluff, C8/P170
Mackays, Île, C1/P103
Magnet Island, C4/P60
Maguse Point, C7/P108
Maguse River, C7/P108
Maiden Island, C2/P120
Maidmans Islands, C5/P218
Main Channel, C2/P156
Majuriarvik, Pointe, C4/P324
Makalu Point, C9/P206
Makok Reefs, C1/P223
Mallet Cove, C5/P125

C = Chapter/P = Paragraph

Mallik Island, C3/P151
Maloney Islands, C5/P122
Malrok, Récifs, C1/P223
Mandarin, Îlot, C1/P163
Maneetok Island, C9/P187
Manico Point, C6/P60
Maniittur Cape, C3/P85
Manimaniit Hills, C6/P253
Manitounuk Islands, C4/P286
Manitounuk Sound, C4/P286
Mannik Islet, C7/P37
Manning Islands, C9/P157
Mansel Island, C4/P12
Maquatua River, C5/P70
Marble Island, C7/P15
Marcopeet Islands, C4/P150
Maricourt, C2/P85
Marker Island, C5/P22
Markham Bay, C3/P131
Mark Island, C3/P10
Marsh Point, C7/P199
Martineau, Cape, C8/P105
Mary, Pointe, C1/P152
Mary Island, C2/P20
Mary Rock, C3/P76
Mata Island, C4/P197
Mathiassen Brook, C8/P27
Matthew Smith, Cape, C9/P57
Maurepas, Promontoire, C2/P169
Maurice Point, C6/P26
Maver Islands, C4/P293
Mavor Island, C4/P227
McCaig Bay, C9/P19
McConnell River, C7/P127
McCormack Island, C4/P113
McGill Islet, C6/P242
McKellar Bay, C3/P90
McLaren, Cape, C8/P102
McLeary Point, C4/P202
McLelan Strait, C1/P26
M'Clure Point, C8/P15
McMurdo Point, C8/P18
McNabb Lake, C8/P52
McNab Rocks, C5/P120
McTavish Island, C4/P239
Meeko Point, C4/P196
Melville Peninsula, C9/P1
Melvin Bay, C7/P51
Merganser, Anse, C1/P187
Merganser, Pointe, C1/P187
Merganser, Rivière, C2/P46
Meridian, Point, C3/P48
Merles Harbour, C6/P130
Merry, Cape, C7/P149
Merry Headland, C6/P131
Merry Island, C4/P286
Merry Rock, C7/P150
Mésaconane, Pointe, C5/P137
Message Island, C9/P228
Meta Incognita Peninsula, C3/P60
Michael Point, C3/P82
Midbay Shoal, C4/P102
Middle Island, C2/P126
Middle Savage Islands, C3/P71
Middle Shoals, C7/P22
Middleton, Île, C5/P127
Middleton Island, C2/P20
Midway, Île, C1/P109
Migeon, Pointe, C4/P44
Mikitok Narrows, C1/P222
Mikittuq, Passe, C1/P222
Mikoalat Island, C2/P25
Miller Island, C4/P257
Mill Island, C3/P170
Minion Rock, C3/P178
Ministikawatin, Péninsule, C5/P114
Minto, Mount, C8/P16
Mirage Islands, C7/P19
Misfortune Shoals, C2/P42
Mission Cove *(Diana Bay)*, C2/P12
Mission Cove *(Port Burwell)*, C1/P20
Missisicabi River, C5/P139
Mistake Bay *(east coast Hudson Bay)*, C4/P106
Mistake Bay *(Whale Cove)*, C7/P80
Mistake Creek, C8/P155
Mittik Island, C7/P36
Mittilik Island, C7/P15
Mizzen Island, C3/P10
Moar Bay, C5/P73
Mocklin Islands, C9/P296
Mogg Bay, C9/P57
Monark Reef, C6/P165
Monkey Hill, C5/P31
Monkey Islands, C5/P73
Montagu, Cape, C8/P93
Montague, Cape, C8/P179
Mont de la Table, C2/P158
Mont (Mount) Albert-Low, C2/P100
Mont (Mount) Young, C2/P100
Monts d'Youville, C4/P51
Mont Sugar Loaf, C1/P236
Monument Bay, C6/P235
Mooneshine Island, C8/P84
Moore Island *(Belcher Islands)*, C4/P176
Moore Island *(Hopewell Islands)*, C4/P116
Moore Island *(Rupert Bay)*, C5/P124
Moor Island, C6/P123
Moose Factory, C5/P210
Moose Factory Island, C5/P205
Moose Flats, C5/P205
Moosehead Island, C2/P159
Moose River, C5/P190
Moosonee, C5/P209
Morin, Pointe, C4/P56
Morrisey Point, C9/P163
Morrissey Harbour, C3/P172
Morse, Pointe du, C5/P44
Morso Islands, C7/P78
Moses Island, C6/P214
Moses Oates, Cape, C2/P143
Mosisee Point, C4/P180
Mosquito Bay, C4/P57
Moss Island, C5/P120
Mount Allan, C4/P94
Mount Chaunsler, C3/P89
Mount Lansdowne, C3/P131
Mount Minto, C8/P16
Mount Sabine, C9/P265
Mount Scotch Tom, C6/P39
Mouton, Rivière au, C5/P102
Mowat Island, C4/P251
Mukpollo Peninsula, C4/P213
Munn, Cape, C8/P145
Munn Bay, C6/P41
Munro Harbour, C1/P15
Murray Harbour, C4/P94
Murray Island, C4/P119
Murray Maxwell Bay, C9/P123
Murray River, C8/P143

**N**abukjuak Bay, C8/P52
Nakertok Narrows, C1/P222
Nakirtuq, Chenal, C1/P222
Nalojoaq Bay, C8/P16
Nanertak Island, C1/P173
Nanertak Reefs, C1/P173
Nannuk Harbour, C3/P63
Nannuk Rock, C2/P75
Nanook Islet, C1/P210
Nanuk Islet, C1/P210
Nanuttuvik, Baie, C2/P169
Napatak Island, C1/P211
Napparti Point, C3/P90
Nappatak Island, C1/P211
Narrow Island, C2/P34
Narrow Passage, C4/P220
Narrows, The *(Rivière George)*, C1/P51
Narrows, The *(Rivière Koksoak)*, C1/P97
Narrows, The *(Wakeham Bay)*, C2/P87
Narruriat Islands, C1/P72
Narwhal Anchorage, C5/P26
Nascopie, Anse, C1/P110
Nascopie Point, C3/P99
Nascopie Reefs, C3/P152
Nasissaturarvik, Pointe, C4/P324
Nastapoka, Rivière, C4/P253
Nastapoka Falls, C4/P253
Nastapoka Islands, C4/P233
Nastapoka Sound, C4/P235
Native Bay, C6/P32
Native Point, C6/P13
Natsek Islet, C1/P210
Natsik Islet, C1/P210
Nattabisha Point, C5/P136
Nauja Bay, C9/P202
Nauja Cove, C7/P15
Nauja Harbour, C9/P113
Naujakallak, Îles, C1/P47
Nauyut, Îles, C1/P66
Navy Channel, C9/P160
Neakok Lake, C3/P142
Neakongut Bay, C4/P59
Nedlik Island, C7/P19
Needle Point *(Chesterfield Inlet)*, C6/P148
Needle Point *(Rowley Island)*, C9/P169
Neerlonakto Island, C9/P253
Negus Bay, C3/P146
Neilsen Island, C4/P286
Nelson River, C7/P189
Nelson Shoal, C7/P188
Neptune, Cap (Head), C2/P62
Neptune Island, C2/P153
Nero Island, C4/P197
Neta Islands, C3/P146
Netchek, Cape, C6/P18
Netchik Point, C8/P198
Net Island, C7/P53
Netitishi Point, C5/P136
Nettichi River, C5/P186
Nettilling Lake, C9/P90
Ne Ultra Strait, C8/P136
Nevill Bay, C7/P100
Ney Island, C4/P214
Niaqunnguut, Pointe, C2/P175
Nias Island, C8/P69
Nicholls Island, C6/P260

C = Chapter/P = Paragraph

Nichols, Pointe (Point), C2/P84
Nichols Bluff, C9/P102
Nicholson Island, C4/P247
Nicolson Rock, C5/P124
Nielson Bar, C5/P189
Ningiuluit Islands, C1/P38
Nipper Island, C1/P135
Nipper Reef, C1/P135
Niskibi River, C7/P210
Noel Harbour, C3/P117
Noire, Pointe, C2/P157
Nomansland Point, C5/P186
Noovoksit, C3/P90
Noovoserparalo, C3/P94
Normand, Pointe, C4/P144
Norman Inlet, C8/P109
North Bay, C3/P85
North Bear Island, C5/P150
North Belcher Islands, C4/P162
North Belcher Shoals, C4/P169
North Bluff, C3/P123
Northbluff Point, C5/P188
North Channel *(Albany River)*, C5/P172
North Channel *(Baker Lake)*, C6/P234
North Channel *(Moose River)*, C5/P207
Northeast Cape, C9/P277
Northeast Cliff, C1/P241
North Head, C2/P21
North Knife River, C7/P136
North Kopak Island, C4/P69
North Midway Island, C6/P155
North Ooglit Islands, C9/P50
North Point, C5/P188
North Pole River, C8/P190
North River, C7/P136
North Skerries, C2/P204
North Spicer Island, C9/P153
North Star Shoal, C5/P11
North Tweedsmuir Island, C9/P216
North Twin Island, C5/P52
North Walrus Island, C5/P67
Norton Island, C6/P214
Nottaway, Rivière, C5/P127
Nottingham Island, C3/P182
Nouvelle-France, Cap de, C2/P141
Novoa, Cape, C3/P88
Novoalojuak, C3/P94
Nowashe Creek, C5/P156
Nugsanarsuk Point, C9/P29
Nunagiak Point, C6/P260
Nunalla, C7/P128
Nunavik, Region of, C1/P4
Nunavut, C1/P5
Nuvualujjuaq Peninsula, C3/P94
Nuvuc, Pointe, C2/P222
Nuvudlik Island, C8/P167
Nuvugapik Point, C2/P21
Nuvuit Peninsula, C9/P130
Nuvukallak, Cap, C1/P50
Nuvuk Harbour, C2/P218
Nuvuk Islands, C2/P206
Nuvuk Point, C8/P160
Nuvursirpaaraaluk Island, C3/P94
Nuvuttuaq Point, C6/P258
Nuwata, C8/P45

**O**aqulluk Rock, C6/P155
Observation Cove, C3/P78
Observation Point, C6/P115
Ocean Eagle Point, C9/P153
Octave, Rivière, C5/P127
October Island, C8/P90
Octopus Reef, C1/P80
Okivik Island, C2/P39
Okolli Island, C3/P148
Old Factory Bay, C5/P77
O'Leary Island, C4/P218
Oman Point, C7/P221
Omarolluk Sound, C4/P188
Ongalaota, C3/P96
Ooglukjuak Island, C3/P145
Opingivik Island, C2/P27
Opinnagau River, C5/P156
Opposite Island, C8/P86
Orbit Rock, C6/P169
Ormonde Island, C9/P276
Ossory, Cape, C9/P278
Otaska Harbour, C4/P312
Ottawa Islands, C4/P92
Ours Noir, Pointe à l', C5/P128
Outcrop Point, C9/P106
Outer Island, C2/P140
Outer Shoals, C7/P22
Overflow Lake, C3/P126
Owlitteeweek Island, C8/P132
Owl River, C7/P185

**P**ain, Cap, C2/P19
Paint Hills Bay, C5/P70
Paint Hills Islands, C5/P67
Paint Islands, C4/P290
Pakkivik, Île, C1/P103
Paliak Islands, C8/P167
Palisade Cliffs, C4/P126
Palmated Bay, C8/P90
Palmer Bay, C8/P126
Pamialluk, Pointe, C4/P244
Pamiok Island, C1/P206
Pamiok Point, C1/P206
Pamiuq, Pointe, C4/P105
Panalik Point, C8/P186
Pangertot Peninsula, C7/P9
Panorama Island, C7/P56
Papik Island, C2/P39
Papik Point, C7/P21
Parketuk Bay, C3/P151
Parry Bay, C9/P21
Parry Point, C9/P100
Parsons Island, C2/P97
Partridge Island, C7/P211
Paskwachi Point, C5/P186
Passage aux Feuilles, C1/P130
Passage Island, C8/P82
Passe de l'Algerine, C1/P152
Passe Digges, C2/P201
Passe Mikittuq, C1/P222
Passe Smoky, C1/P141
Patchepawapoka River, C5/P156
Patch Island, C6/P156
Pattee Island, C4/P95
Patterson Island, C4/P120
Pauktorvik Island, C1/P122
Paul Bay, C5/P7
Paunraqtuuq Hill, C6/P262
Paw Island, C2/P32
Payne, Bassin (Basin), C1/P225
Payne Bay, C1/P208
Payne Bay *(village)*, C1/P234
Payne River, C1/P219
Peak Island, C2/P116
Peawanuck, C7/P224
Pebble Island, C5/P65
Peckham Island, C4/P108
Peck Inlet, C4/P8
Peck Point, C6/P244
Pecten Harbour, C4/P38
Pelican Rock, C2/P79
Pelletier Bay, C6/P145
Pelletier Point, C6/P145
Pembroke, Cape, C4/P23
Péninsule Bates, C4/P110
Péninsule Ministikawatin, C5/P114
Penny Islet, C7/P33
Penrhyn, Cape, C9/P13
Peregrine Point, C9/P79
Peregrine Sound, C1/P139
Peril Island, C5/P18
Peril Point *(Chesterfield Inlet)*, C6/P177
Perkins Rock, C5/P122
Perley Island, C4/P95
Pérouse Bay, La, C7/P140
Perrett Island, C1/P12
Peters, Point, C9/P105
Petersen Bay, C8/P85
Petite Ile, La, C2/P22
Petite île Elbow, C1/P109
Petite Ravine, La, C1/P147
Petite rivière de la Baleine, C4/P282
Peuplier, Pointe du, C5/P131
Peuplier, Rivière du, C5/P73
Phoque, Rivière au, C5/P6
Piagochioui, Rivière, C5/P7
Pikiulirjuakallak, Île, C1/P222
Pikiyulik Island, C1/P222
Piksimanik River, C8/P171
Pikuk Rock, C7/P41
Piling Bay, C9/P221
Piling Lake, C9/P223
Pilon Island, C6/P236
Pinger Point, C9/P49
Pink Island, C2/P25
Pinnacle Bluff, C2/P110
Pinnacle Islands, C2/P122
Pin Rock, C7/P25
Pintail Island, C6/P77
Pipowitan River, C7/P210
Piscapecassy River, C5/P139
Pissiulaarsitik Island, C1/P67
Pissiulaarsitik Islands, C1/P38
Pistol Bay, C7/P70
Plage du Bombardier, C2/P166
Pleasant Inlet, C3/P88
Plover Islands, C1/P246
Pod Rock, C7/P27
Poillon Point, C6/P66
Point Belford, C8/P117
Pointe Aisavartalik, C1/P92
Pointe Akulivik, C4/P46
Pointe Allatalik, C1/P49
Pointe à l'Ours Noir, C5/P128
Pointe Apiskutikutasich, C5/P69
Pointe Aquttutalik, C4/P324
Pointe Asuqaaq, C1/P122
Pointe Asuraaq, C1/P122
Pointe Attikuan, C5/P7
Pointe Attiquane, C5/P7
Pointe au Canon, C4/P246

C = Chapter/P = Paragraph

Pointe au Fer, C1/P146
Pointe au Héron, C5/P49
Pointe au Huard, C5/P49
Pointe au Sable, C4/P296
Pointe aux Écueils, C4/P65
Pointe Bernier, C4/P11
Pointe Big Finger, C4/P74
Pointe Bluff, C1/P151
Pointe Boucher, C4/P105
Pointe Bourjoli, C4/P105
Pointe Bourlamaque, C5/P69
Pointe Breakwater, C1/P187
Pointe Buteo, C2/P45
Pointe Cachechu, C5/P137
Pointe Cantley, C2/P96
Pointe Copper, C1/P160
Pointe Coutlée, C4/P62
Pointe Cusson, C4/P59
Pointe de la Baleine Blanche, C4/P249
Pointe de la Consolation, C5/P130
Pointe de la Fougère Rouge, C5/P136
Pointe de la Jauge, C1/P161
Pointe de l'Algerine, C1/P152
Pointe de la Rivière, C1/P163
Pointe de l'Igloo *(Bassin Payne)*, C1/P225
Pointe Demers, C4/P57
Pointe de Sainte-Hélène, C4/P10
Pointe Despins, C4/P106
Pointe de Tracy, C2/P54
Pointe De Villiers, C1/P175
Pointe d'Ivujivik, C2/P213
Pointe du Bois Brûlé, C5/P125
Pointe Duchesnau, C2/P28
Pointe Dufrost, C4/P65
Pointe du Morse, C5/P44
Pointe du Peuplier, C5/P131
Pointe du Poste, C4/P132
Pointe du Profond, C4/P35
Pointe Elson, C1/P40
Pointe Entrance, C1/P218
Pointe False, C1/P140
Pointe Fish, C4/P74
Pointe Flat, C1/P140
Pointe Ford, C2/P84
Pointe Frontenac, C2/P60
Pointe Gable, C1/P183
Pointe Garry, C1/P148
Pointe Gillam, C2/P111
Pointe Goyeau, C5/P114
Pointe Grave, C2/P43
Pointe Henderson, C1/P142
Pointe Hubbard, C1/P33
Pointe Illukuluttalik, C1/P110
Pointe Jean-Talon, C2/P3
Pointe Kakachischuan, C5/P7
Pointe Kakachischuane, C5/P7
Pointe Kakassitug, C5/P7
Pointe Kapitattalik, C1/P48
Pointe Kennedy, C1/P168
Pointe Kisarvik, C1/P99
Pointe Lajus, C1/P160
Point Elizabeth, C8/P127
Pointe Loon, C5/P102
Pointe Louis-XIV, C4/P327
Pointe Majuriarvik, C4/P324
Pointe Mary, C1/P152
Pointe Merganser, C1/P187
Pointe Mésaconane, C5/P137
Pointe Migeon, C4/P44
Pointe Morin, C4/P56
Pointe Nasissaturarvik, C4/P324
Pointe Niaqunnguut, C2/P175
Pointe Nichols, C2/P84
Pointe Noire, C2/P157
Pointe Normand, C4/P144
Pointe Nuvuc, C2/P222
Pointe Pamialluk, C4/P244
Pointe Pamiuq, C4/P105
Pointe Qilalugarsiuvik, C4/P282
Pointe Qirniraujaq, C1/P75
Pointe Radisson, C2/P138
Pointe Ragged, C1/P122
Pointe Range, C1/P185
Pointe Reef, C1/P150
Pointe Rouge, C2/P153
Pointe Saouayane, C5/P114
Pointe Savik, C1/P210
Pointe Shave, C4/P329
Pointe Short, C2/P9
Pointe Skidoo, C5/P31
Pointe Spur, C1/P148
Pointe Stony, C1/P127
Pointe Takiyok, C1/P175
Pointe Taliruq, C2/P222
Pointe Tasker, C1/P74
Pointe Théron *(Deception Bay)*, C2/P160
Pointe Théron *(Diana Bay)*, C2/P37
Pointe Tikiraassiaq, C2/P175
Pointe Tikirakallaaluk, C4/P324
Pointe Tupialuviniq, C4/P324
Pointe Vauquelin, C4/P315
Pointe Walton, C4/P295
Pointe Wedgehead, C1/P143
Point Henderson, C8/P73
Point Islands, C2/P37
Point Meridian, C3/P48
Point of the Woods, C7/P134
Point Peters, C9/P105
Points, The, C6/P26
Polaris Narrows, C6/P245
Polar Point, C5/P153
Polecat Point, C9/P188
Polemond, Rivière, C4/P105
Polunin Inlet, C1/P31
Poly, Îlot, C1/P163
Pontax, Rivière (River), C5/P126
Pontchartrain, Promontoire, C2/P169
Poodlatee Island, C3/P90
Poole Point, C9/P108
Pork Peninsula, C7/P70
Porpoise Cove, C4/P144
Porsild Mountains, C8/P11
Portage Bay, C4/P110
Port Burwell, C1/P20
Port de Boucherville, C3/P189
Port de Laperrière, C2/P194
Port Harrison, C4/P134
Portland, Promontoire, C4/P110
Port Nelson, C7/P189
Port-Nouveau-Québec, C1/P57
Position Rock, C7/P25
Poste, Pointe du, C4/P132
Poste-de-la-Baleine, C4/P299
Poston Point, C6/P130
Povungnituk, C4/P86
Povungnituk, Rivière de, C4/P74
Povungnituk Bay, C4/P65
Prairie Bay, C7/P31
Prairie Point, C6/P32
Prefontaine, Cape, C6/P14
Presqu'île Castle, C4/P280
Pricket Point, C3/P177
Primrose Island, C6/P174
Prince Charles Island, C9/P106
Prince-de-Galles, Cap du, C2/P65
Prince of Wales, Cape, C2/P65
Prince of Wales, Fort, C7/P149
Prince of Wales Fort National Historic Site of Canada, C7/P149
Prince River, C6/P258
Pritzler Harbour, C3/P69
Profond, Pointe du, C4/P35
Profonde, Baie, C1/P164
Promise Island, C6/P82
Promise Point, C6/P161
Promontoire Colbert, C2/P186
Promontoire De Martigny, C2/P137
Promontoire Maurepas, C2/P169
Promontoire Pontchartrain, C2/P169
Promontoire Portland, C4/P110
Prophet Island, C5/P124
Ptarmigan Island, C6/P115
Ptarmigan Islet, C6/P242
Puck Rock, C3/P11
Pudla Inlet, C3/P146
Puffin Rock, C2/P41
Pungnertuk Point, C3/P143
Purfur Cove, C9/P291
Pursuit Point, C9/P183
Putnam Highland, C9/P87
Putnam Island, C3/P170
Puvirnituq, C4/P86
Puvirnituq, Rivière de, C4/P74

**Q**airtualuk, Cap, C1/P50
Qairtuinnaq Rock, C4/P67
Qairulik Reef, C5/P17
Qakutaak Bay, C8/P25
Qavvialuk Point, C9/P21
Qiggutuq Islands, C1/P38
Qikiqtaujaq Island, C6/P261
Qikirtaajuit Islands, C1/P122
Qikirtaaluk Island, C1/P41
Qikirtaaluk Islands, C1/P69
Qikirtaapik, Île, C2/P159
Qikirtaguluk Island, C1/P122
Qikirtajuaq Island, C1/P72
Qikirtaujaq, Colline, C1/P52
Qilalugarsiuvik, Pointe, C4/P282
Qirnilik, Île, C1/P169
Qirniraujaq, Pointe, C1/P75
Quaqtaq, C2/P13
Quarman Point, C9/P25
Quartzite Island, C7/P15
Queen, Cape, C8/P41
Quilliam Bay, C9/P57
Qulaituijarvik River, C6/P253
Quoich River, C6/P191
Quorik Point, C4/P202
Qurlutuq, Rivière, C1/P67

**R**abbit Island *(Ashe Inlet)*, C3/P119
Rabbit Island *(Baird Bay)*, C7/P7
Radar Island, C4/P173
Radio Island, C3/P15
Radisson, Îles, C1/P159

C = Chapter/P = Paragraph

Radisson, Pointe, C2/P138
Ragged, Pointe, C1/P122
Ragged Island, C6/P135
Ragged Point, C6/P163
Rainbow Point, C4/P227
Ramsay River, C3/P117
Range Island, C4/P190
Range, Pointe, C1/P185
Ranger Brook, C6/P23
Ranger Island, C1/P206
Ranger Reef, C1/P207
Ranger Seal Bay, C6/P145
Rankin Inlet, C7/P2
Rankin Inlet *(hamlet)*, C7/P60
Rascal Rock, C6/P127
Ravn River, C9/P132
Rawson Island, C3/P135
Récif Lodestone, C1/P223
Récif Long, C1/P162
Récifs Malrok, C1/P223
Red Fox Cove, C4/P225
Red Point *(Baker Lake)*, C6/P244
Red Point *(Lyon Inlet)*, C8/P107
Reef, Pointe, C1/P150
Reef Bay, C4/P66
Reeves Harbour, C3/P118
Reference Island, C6/P155
Refuges, Anse aux, C1/P169
Regina Narrows, C6/P240
Region of Nunavik, C1/P4
Reid, Cape, C8/P106
Reid Point, C9/P145
Renny Point, C6/P39
Renouf Island, C4/P179
Repulse Bay, C8/P187
Repulse Bay *(hamlet)*, C8/P204
Resolution Harbour, C3/P8
Resolution Island, C3/P2
Resolution Tickle, C3/P8
Reversing Falls, C8/P175
Revillon Island, C4/P207
Richards Bay, C9/P267
Ridge Passage, C4/P218
Rightfoot Islet, C7/P36
Rio Island, C6/P236
Riot Rock, C6/P173
Rivière, Pointe de la, C1/P163
Rivière à la Baleine, C1/P70
Rivière à la Truite, C5/P126
Rivière Arnaud, C1/P219
Rivière au Chien Rouge, C1/P186
Rivière au (du) Castor, C5/P46
Rivière au Mouton, C5/P102
Rivière au Phoque, C5/P6
Rivière aux Feuilles, C1/P171
Rivière Bérard, C1/P166
Rivière Boniface, C4/P239
Rivière Borel, C1/P200
Rivière Broadback, C5/P127
Rivière Brochant, C1/P202
Rivière Chukotat, C4/P56
Rivière Clergue, C5/P73
Rivière Deception, C2/P151
Rivière de Povungnituk, C4/P74
Rivière de Puvirnituq, C4/P74
Rivière du Peuplier, C5/P73
Rivière du Vieux Comptoir, C5/P77
Rivière False, C1/P74
Rivière George, C1/P37
Rivière Guillaume, C5/P8
Rivière Iktotat, C4/P57
Rivière Illukotat, C4/P51
Rivière Innuksuac, C4/P129
Rivière Jolicoeur, C5/P102
Rivière Kapsaouis, C5/P6
Rivière Kikkerteluc, C4/P148
Rivière Kogaluc, C4/P66
Rivière Koksoak, C1/P79
Rivière Koktac, C4/P106
Rivière Kongut, C4/P127
Rivière Korak, C4/P58
Rivière Koroc, C1/P39
Rivière Kovic, C4/P11
Rivière Latourette, C2/P34
Rivière Lefroy, C1/P201
Rivière Longland, C4/P244
Rivière Merganser, C2/P46
Rivière Nastapoka, C4/P253
Rivière Nottaway, C5/P127
Rivière Octave, C5/P127
Rivière Piagochioui, C5/P7
Rivière Polemond, C4/P105
Rivière Pontax, C5/P126
Rivière Qurlutuq, C1/P67
Rivière Roggan, C5/P6
Rivière Rupert, C5/P133
Rivière Sabascunica, C5/P73
Rivière Saint-Fond, C1/P200
Rivière Sorehead, C4/P59
Rivière Tuttutuuq, C1/P68
Rivière Vauquelin, C4/P315
Rivière Wakeham, C2/P89
Robert Brown, Cape, C9/P16
Robert Point, C3/P131
Robertson Bay, C4/P208
Robinhood Bay, C6/P156
Roche Bay, C9/P21
Rocher Tulugarnaq, C2/P158
Rockhouse Island, C6/P77
Rock Island, C4/P72
Rock Passage, C4/P216
Rocky Brook, C6/P40
Roes Welcome Sound, C8/P136
Roggan, Rivière (River), C5/P6
Roggan River *(fishing camp)*, C5/P6
Root Creek, C7/P191
Ross Bay, C8/P109
Ross Island, C4/P269
Rouge, Pointe, C2/P153
Round Island, C6/P195
Round Rocks Island, C2/P39
Rowatt Harbour, C4/P195
Rowe, Île, C1/P165
Rowley Island, C9/P162
Rowley River, C9/P135
Rubble Rock, C6/P145
Ruin Point, C6/P25
Ruisseau Garnier, C1/P249
Ruisseau Kogaluk, C2/P34
Rupert, Rivière, C5/P133
Rupert Bay, C5/P114
Rupert Creek, C7/P185
Rushmore Bay, C9/P204

**S**abascunica, Rivière, C5/P73
Sabine, Mount, C9/P265
Sable, Pointe au, C4/P296
Saddleback Island, C3/P71
Saddle Island, C2/P123
Sadlek, Cape, C9/P183
Saeglorsoak Island, C1/P72
Safety Cove, C8/P113
Sagliq Island, C6/P261
Sainsbury Point, C4/P218
Sainte-Hélène, Pointe de, C4/P10
Saint-Fond, Rivière, C1/P200
Sakkiak Island, C3/P148
Sakpik Bay, C6/P89
Sakpik Channel, C6/P89
Sakpik Island, C6/P89
Sala Point, C4/P229
Salikuit Islands, C4/P205
Salisbury Island, C3/P174
Sallijuaq Islands, C1/P72
Sallijukak Islet, C1/P42
Salluit, C2/P176
Salmon Creek, C7/P185
Salty Bill Hill, C4/P196
Sam Island, C5/P32
Sanderling Island, C7/P36
Sanderson Island, C8/P84
Sand Head, C5/P192
Sand Head Beacon, C5/P202
Sandpiper Island, C6/P82
Sandpiper Islet, C1/P181
Sandy Island, C5/P190
Sandy Islets, C7/P21
Sandy Point, C7/P105
Sanikiluaq, C4/P182
Santianna Point, C6/P21
Saouayane, Pointe, C5/P114
Sarfak Point, C1/P211
Sarvak, Cap, C1/P211
Saunders Point, C8/P14
Savage Harbour, C3/P52
Savage Islands, C8/P167
Savik, Pointe (Point), C1/P210
Sawpit Island, C5/P205
Sawtooth Bay, C1/P122
Sawtooth Reef, C1/P176
Scarab Point, C7/P9
Schnak Cove, C1/P93
Schooner Cove, C6/P218
Schooner Harbour *(Chesterfield Inlet)*, C6/P207
Schooner Harbour *(Hudson Strait)*, C3/P168
Schooner Opening, C4/P289
Scotch Tom, Mount, C6/P39
Scree Point, C1/P240
Sculpin Island, C6/P172
Sea Horse Gully, C7/P137
Seahorse Point *(Southampton Island, south coast)*, C6/P6
Sealer Narrows, C3/P96
Seal Islands, C5/P26
Seal Point, C6/P41
Seal River, C7/P134
Sèche, Baie *(Kap Inuksutujuq)*, C1/P122
Sèche, Baie *(Lac aux Feuilles)*, C1/P160
Seekoo Island, C8/P79
Sentinel Island, C3/P17
Sentinel Reef, C1/P173
Sentry Island, C7/P110
Sentry Island Shoal, C7/P112
Sentry Islet, C3/P82
Separation Shoals, C7/P27
Seven Fathom Bank, C8/P7

C = Chapter/P = Paragraph

Severn Harbour, C6/P117
Severn Point, C6/P232
Severn River, C7/P211
Sévigny Point, C9/P273
Shackleton, Cape, C8/P90
Shaftesbury Inlet, C3/P82
Shallow Bay, C4/P66
Sham Bay, C1/P122
Shartowitok Bay, C3/P146
Shave, Pointe, C4/P329
Shears Beacon, C5/P202
Sheep Island *(approaches to Inukjuak)*, C4/P128
Sheep Island *(Cape Dorset Harbour)*, C3/P154
Sheep River, C5/P102
Sheldrake Shoal, C5/P151
Shell Brook, C7/P217
Shell Island, C6/P230
Shemia Islands, C3/P146
Shepherd Island, C2/P99
Sheppard Island, C5/P74
Sherer Inlet, C8/P109
Sherrick, Colline, C5/P114
Ship Sands, C5/P189
Ship Sands Island, C5/P190
Shoal Harbour, C4/P105
Shoals, Bay of, C8/P112
Shoran Bay, C4/P32
Short, Pointe (Point), C2/P9
Shugba Bay, C3/P137
Shukbuk Bay, C3/P137
Shuke Islands, C3/P165
Siakkaaluk, Cap, C2/P212
Sidjegiak Point, C9/P202
Sikosak Bay, C9/P287
Silent Cove, C7/P52
Silumiut, Cape, C6/P77
Sinclair Island, C5/P173
Singer Inlet, C1/P31
Singer Point, C1/P241
Siorarsuk Peninsula, C9/P122
Siskin Point, C7/P31
Sister Islets, C3/P66
Sitamat, Îlets (Islands), C1/P221
Siukkaaluk, Cap, C2/P212
Skelton Bay, C9/P156
Skeoch Bay, C9/P117
Skidoo, Pointe, C5/P31
Skua Reef, C6/P169
Slab Island, C7/P52
Slate Island, C5/P24
Sleeper Islands, C4/P151
Slim Island, C2/P32
Slippery Point, C6/P212
Smith, Cape, C4/P39
Smith Island, C4/P39
Smoky, Îles, C1/P142
Smoky, Passe, C1/P141
Smooth Island *(Diana Bay)*, C2/P29
Smooth Island *(King George Archipelago)*, C2/P118
Smooth Island *(Rankin Inlet)*, C7/P29
Smyth Harbour, C8/P61
Snafu Beaches, C6/P47
Snape Island, C4/P216
Snape Point, C5/P114
Snelgrove Rock, C2/P200
Snowbank River, C8/P185
Sokongen Bay, C8/P85
Solomon Island, C2/P32
Solomons Temple Islands, C5/P64
Sooloosoogut, C3/P95
Soper Lake, C3/P88
Sorehead, Rivière, C4/P59
Sorry Harbour, C3/P37
Southampton, Cape, C4/P32
Southampton Island *(NE coast)*, C8/P11
Southampton Island *(south coast)*, C6/P1
Southampton Island *(west coast)*, C8/P140
South Bay, C6/P28
South Bear Island, C5/P150
South Channel *(Albany River)*, C5/P172
South Channel *(Baker Lake)*, C6/P230
South Channel *(Moose River)*, C5/P206
Southeast Arm, C2/P133
Southeast Point, C1/P240
South Island, C4/P72
South Knife River, C7/P136
South Kopak Island, C4/P69
South Midway Island, C6/P155
South Ooglit Island, C9/P24
South Passage, C9/P120
South Reefs, C3/P62
South Shoals, C7/P25
South Skerries, C2/P204
South Spicer Island, C9/P150
South Tweedsmuir Island, C9/P214
South Twin Island, C5/P57
South Walrus Island, C5/P67
Southwest Arm, C2/P134
Spence Harbour, C4/P195
Spencer Island, C5/P50
Spicer Island, C3/P128
Spit Island, C5/P88
Split Island, C4/P167
Spracklin Point, C4/P229
Springs Reef, C1/P80
Spur, Pointe, C1/P148
Staffe Islet, C2/P207
Staff Island, C4/P110
Stag Island, C5/P120
Stag Rock, C5/P120
Stanley Harbour, C8/P22
Stanley Reef, C3/P93
Star Island, C3/P7
Steensby Inlet, C9/P130
Steep Bank Bay, C6/P143
Stevens Island, C5/P124
Stickle Islet, C7/P53
Stock Island, C3/P10
Stony, Pointe, C1/P127
Stony Islands, C1/P124
Stony Knoll, C7/P146
Stony Point, C6/P169
Stony Shoals, C1/P140
Store Island, C6/P67
Straits Bay, C9/P219
Strathcona Islands, C3/P125
Strivewell Island, C6/P195
Strivewell Narrows, C6/P212
Stromness Harbour, C5/P28
Stromness Island, C5/P28
Strutton Harbour, C5/P105
Strutton Islands, C5/P104
Stupart Bay, C2/P62
Sturges Bourne Islands, C8/P100
Sturges Islands, C8/P100
Success Island, C4/P145
Sugar Loaf, Mont, C1/P236
Sugarloaf Mountain, C6/P256
Sugluk, C2/P176
Sugluk Basin, C2/P177
Sugluk Inlet, C2/P174
Sugluk Island, C2/P172
Suluk Islet, C7/P41
Sulussugut Peninsula, C3/P95
Sunday Island, C5/P150
Sun Island, C8/P88
Surge Islands, C4/P101
Survey Point, C7/P58
Sutton River *(Little Cape)*, C7/P229
Sutton River *(Southampton Island)*, C6/P26
Swaffield Harbour, C4/P12
Swan Island, C7/P34
Swan River, C5/P156
Sweetwater Lake, C3/P13
Swirlers, The, C3/P9

Table, Mont de la, C2/P158
Takeyooala, C3/P95
Takijuq Island, C6/P254
Takiyok, Pointe, C1/P175
Takiyok Reef, C1/P176
Taktuk Island, C2/P25
Taligok Point, C2/P21
Taliruq, Pointe, C2/P222
Talon Reefs, C1/P138
Talun Bay, C8/P194
Tanataluk Islands, C6/P254
Tanfield, Cape, C3/P86
Tangle Island, C9/P259
Target Rock, C6/P169
Tariujaq Arm, C9/P134
Tasiujaaluk, Baie, C2/P49
Tasiujaaluk Bay, C1/P39
Tasiujaq, C1/P167
Tasiujaq Bay, C6/P257
Tasker, Pointe, C1/P74
Tasseoyak Bay, C3/P95
Tatnam, Cape, C7/P203
Tatnam Shoal, C7/P203
Tattiggaq Point, C6/P145
Tavani, C7/P96
Taverner Bay, C9/P92
Tavernier, Cap, C2/P185
Taylor Island, C4/P257
Tees Bay, C5/P43
Tellik Bay, C3/P151
Tellik Inlet, C3/P151
Ten Foot Patch, C5/P121
Tent Bay, C6/P161
Tent Island, C5/P116
Term Point, C7/P81
Tern Island *(Fury and Hecla Strait)*, C9/P256
Tern Island *(Munn Bay)*, C6/P45
Terrace Hill, C6/P249
Terra Nivea Ice Cap, C3/P57
Terreoukchuk Bay, C3/P142
Terror Point, C6/P177
Terror Point *(Southampton Island)*, C8/P14
Tha-anne River, C7/P127
Thalbitzer, Cape, C9/P127
The Bar *(Moose River)*, C5/P198
The Bar *(Sugluk Inlet)*, C2/P177
The Bluff, C4/P177

C = Chapter/P = Paragraph

The Elbow *(Moose River)*, C5/P189
The Elbow *(Rivière Koksoak)*, C1/P109
The Gutway, C5/P173
The Heel, C3/P100
The Helmet, C2/P132
The Knoll, C7/P134
Thelon River, C6/P262
The Narrows *(Rivière George)*, C1/P51
The Narrows *(Rivière Koksoak)*, C1/P97
The Narrows *(Wakeham Bay)*, C2/P87
The Points, C6/P26
Théron, Pointe *(Deception Bay)*, C2/P160
Théron, Pointe *(Diana Bay)*, C2/P37
Theron Bay, C2/P37
Theron Island, C7/P56
The Swirlers, C3/P9
The Throat, C4/P249
The Wart, C1/P92
Thibert Point, C6/P94
Thlewiaza River, C7/P127
Thompson Harbour, C4/P60
Thompson Island, C3/P69
Thompson Point, C7/P187
Thomsen River, C8/P73
Thomson Island, C7/P33
Thomson Passage, C7/P34
Throat, The, C4/P249
Thuban Point, C9/P188
Tideflat Bay, C9/P165
Tiders Islands, C5/P86
Tiercel Island, C1/P135
Tikerarsuk Point, C9/P142
Tikilak Point, C8/P169
Tikiraaluk Island, C1/P38
Tikiraassiaq, Pointe, C2/P175
Tikirakallaaluk, Pointe, C4/P324
Tikirakuluk Point, C6/P261
Tikko Peninsula, C3/P88
Tikkuut Peninsula, C3/P88
Tingaujaqtujut Islands, C6/P257
Tiny Island *(Diana Island)*, C2/P27
Tiny Island *(La Grande Rivière approaches)*, C5/P24
Tiny Rock, C7/P28
Tomisidenik Island, C5/P205
Toms Harbour, C8/P80
Top Hill, C6/P235
Topsail Head, C3/P8
Tordenskjold, Cape, C9/P287
Tracy, Pointe de, C2/P54
Trading Post Cove, C1/P159
Tragedy Point, C4/P191
Tremblay Bay, C9/P182
Trident Island, C3/P15
Trident Lake, C9/P144
Trident River, C9/P144
Trinitie Rock, C3/P178
Trinity Islands, C8/P37
Trodely Island, C5/P86
Truite, Rivière à la, C5/P126
Tryon, Escarpement, C1/P175
Tudlik Peninsula, C7/P51
Tukarak Island, C4/P188
Tulugak Point, C2/P21
Tulugarnaq, Rocher, C2/P158
Tunitjuak Island, C3/P145
Tupialuviniq, Pointe, C4/P324
Turner Point, C9/P188
Turning Island, C5/P20
Turton Bay, C9/P61
Turton Island, C8/P122
Tusk Island, C3/P6
Tuttle Point, C2/P60
Tuttutuuq, Rivière, C1/P68
Tuvak Bay, C2/P28
Tuvak Reefs, C1/P203
Tuvakutaaq Channel, C1/P72
Tuvalik Bay, C1/P210
Tuvalik Point, C1/P210
Tuwak Reefs, C1/P203
Twin Cairns Island, C4/P186
Twin Knolls, C7/P22
Twin Pack Island, C6/P191
Twin Rocks, C3/P11
Twist Point, C6/P220
Two Cubs Islands, C5/P150

**U**glik Islands, C2/P71
Ujagasukjulik Point, C6/P143
Ukkusiksalik National Park of Canada, C8/P178
Ullit Island, C9/P148
Umiak Cove, C1/P240
Umiak Island, C5/P22
Umiujaq, C4/P261
Ungava Bay, C1/P8
Unhealing Brook, C6/P61
Upper Savage Islands, C3/P87
Uugalautiit Island, C3/P96
Uvauk Inlet, C6/P167
Uvillutuuq Islands, C4/P67

**V**alets, Cap, C2/P172
Vansittart Island, C8/P85
Vauquelin, Pointe, C4/P315
Vauquelin, Rivière, C4/P315
Vieux Comptoir, Rivière du, C5/P77
Viola Bay, C9/P83

**W**abuk Point, C7/P219
Wachi Creek, C7/P227
Wager Bay, C8/P162
Wager Bay Narrows, C8/P162
Wag Islands, C6/P82
Wakeham, C2/P85
Wakeham, Rivière (River), C2/P89
Wakeham Bay, C2/P74
Wales Island, C2/P104
Wales Point, C7/P136
Wales Rock, C2/P106
Wales Sound, C2/P108
Walker Island, C6/P186
Wallace Head, C9/P182
Walrus Island *(Daly Bay)*, C6/P69
Walrus Island *(Fisher Strait)*, C6/P19
Walrus Island *(Hall Lake)*, C9/P23
Walrus Island *(Repulse Bay)*, C8/P194
Walrus Island *(Wakeham Bay)*, C2/P77
Walrus Island *(Whale Cove)*, C7/P75
Walrus Island Reef, C7/P82
Walrus Islands, C5/P67
Walrus Point, C5/P43
Walter Island, C5/P55
Walton, Pointe, C4/P295
Walton Island, C4/P221
Ward Island, C4/P110
Wart, The, C1/P92
Warwick, Cape, C3/P32
Waskaganish, C5/P133
Wastikun Island, C5/P8
Waterfall Cove, C2/P31
Watering Cove, C3/P28
Waters Island, C4/P97
Watson Point, C7/P140
Watt Islands, C3/P7
Wavy Creek, C5/P190
Wedd Islet, C6/P248
Wedgehead, Pointe, C1/P143
Weeks Bay, C9/P99
Weggs Island, C2/P139
Welsford, Cape, C8/P65
Wemindji, C5/P70
Westbourne Bay, C3/P94
Western Passage, C2/P32
Western Reefs, C3/P95
West Foxe Islands, C3/P145
West Inlet, C3/P151
West Mussel Island, C2/P43
Weston, Cape, C8/P50
Weston Escarpment, C8/P49
Weston Island, C5/P79
West Pen Island, C7/P208
West Point, C6/P156
Wetalltok Bay, C4/P212
Weymouth, Cape, C3/P85
Weymouth Inlet, C1/P31
Whaleback Reef, C1/P158
Whale Cove, C7/P74
Whale Cove *(hamlet)*, C7/P84
Whale Point, C8/P154
Whales, Cap, C1/P106
Whale's Back Rock, C5/P151
Whale Sound, C8/P81
Whapmagoostui, C4/P299
Wharton Harbour, C3/P128
White Bear Bay, C3/P131
White Head, C3/P28
White Island, C8/P78
White Rock, C6/P195
White Strait, C3/P110
White Whale River, C7/P185
Whitley Bay, C2/P58
Whitney Inlet, C6/P76
Whitney Island, C4/P110
Whyte Inlet, C9/P287
Wicked Reef, C5/P18
Wiegand Island, C4/P179
Wight, Cape, C3/P94
Wight Inlet, C3/P75
Wildbird Islands, C8/P46
William-Smith, Cap (Cape), C1/P18
Willingdon, Cape, C3/P143
Willoughby, Cape, C9/P78
Wilson, Cape, C8/P129
Wilson Bay, C7/P74
Winchester Inlet, C6/P71
Winisk, C7/P223
Winisk River, C7/P218
Winter Island, C8/P117
Witch Bay, C4/P110
Wivanhoe Island, C2/P106
Wolf Islet, C5/P107
Wolstenholme, C2/P187
Wolstenholme, Cap, C2/P191
Woman Islands, C2/P109
Wood Creek, C7/P217

C = Chapter/P = Paragraph

Woods, Point of the, C7/P134
Wordie Bay, C9/P102

**Y**ellow Beach, C3/P35
Yellow Bluff, C8/P156
York Factory, C7/P197
York Roads, C7/P200
Young, Mont (Mount), C2/P100
Young Inlet, C1/P26
Young Island *(Hopes Advance Bay)*, C1/P181
Young Island *(Hopewell Islands)*, C4/P119
Young Point, C4/P191
Youville, Monts d', C4/P51



C = Chapter/P = Paragraph




## Sailing Directions Booklets

ARC 400
General Information, Northern Canada

ARC 401
Hudson Strait, Hudson Bay and Adjoining Waters

ARC 402
Eastern Arctic

ARC 403
Western Arctic

ARC 404
Great Slave Lake and Mackenzie River

CANADIAN HYDROGRAPHIC SERVICE
SERVICE HYDROGRAPHIQUE DU CANADA